



# DuPage Water Commission

600 E. Butterfield Road, Elmhurst, IL 60126-4642  
(630)834-0100 Fax: (630)834-0120

**NOTICE IS HEREBY GIVEN THAT THE RESCHEDULED APRIL 2004 ENGINEERING COMMITTEE MEETING OF THE DU PAGE WATER COMMISSION WILL BE HELD AT 6:30 P.M. ON WEDNESDAY, APRIL 7, 2004, AT ITS OFFICES LISTED BELOW. THE AGENDA FOR THE RESCHEDULED APRIL 2004 REGULAR COMMITTEE MEETING IS AS FOLLOWS:**

**AGENDA**  
**ENGINEERING COMMITTEE**  
**WEDNESDAY, APRIL 7, 2004**  
**6:30 P.M.**

**COMMITTEE MEMBERS**  
G. Wilcox, Chair  
R. Benson  
W. Mueller

**600 EAST BUTTERFIELD ROAD**  
**ELMHURST, IL 60126**

- I. Roll Call
- II. Approval of Minutes for Committee Meeting of March 12, 2004
- III. Report of Status of Construction/Operations
- IV. Status Report of Contract TW-3
- V. Change Orders
  - A. Change Order No. 1: Contract TIB-1 (Innerbelt Transmission Main)
  - B. Change Order No. 2: Contract TIB-1 (Innerbelt Transmission Main)
  - C. Change Order No. 3: Contract TIB-1 (Innerbelt Transmission Main)
  - D. Change Order No. 4: Contract TIB-1 (Innerbelt Transmission Main)
  - E. Change Order No. 42: Contract TW-2 (West Transmission Main)
- VI. Partial Pay Request
  - A. Progress Payment No. 20: Contract BOV-1 (Blow Off Valve Repair)
  - B. Quick Response Contract
    - 1. QR6-004A – (Installation of Cathodic Protection Station – Downers Grove)

All visitors must present a valid drivers license or other government-issued photo identification, sign in at the reception area and wear a visitor badge while at the DuPage Pumping Station.

- VII. Engineering Capacity Study
- VIII. Resolution R-15-04: A Resolution Approving and Ratifying Certain Work Authorization Order(s) Under Quick Response Contract QR-6/02 at the April 7, 2004 DuPage Water Commission Meeting
- IX. Resolution R-16-04: A Resolution Authorizing the Execution of an Intergovernmental Agreement between the DuPage Water Commission and the Village of Villa Park Concerning Watermain Replacement Work in the Village of Villa Park
- X. Other
- XI. Adjournment

**MINUTES OF A MEETING OF THE  
ENGINEERING & CONSTRUCTION COMMITTEE  
OF THE DU PAGE WATER COMMISSION  
HELD ON MARCH 11, 2004  
600 EAST BUTTERFIELD ROAD  
ELMHURST, ILLINOIS**

The meeting was called to order at 6:50 P.M.

Committee members in attendance: R. Benson, W. Mueller and G. Wilcox

Committee members absent: None

Also in attendance: R. Martin, E. Kazmierczak and W. Green (AB&H)

Commissioner Mueller moved that the Minutes of the January 8, 2003 Engineering Committee be approved. Motion seconded by Commissioner Benson and passed unanimously as follows:

Aye: R. Benson, W. Mueller and G. Wilcox

Nay: None

Absent: None

The Committee reviewed memoranda regarding the Status of Facilities Construction/Operation dated March 5, 2004 and Status of Pipeline Construction dated March 5, 2004.

The Committee reviewed the memorandum and status map by Alvord, Burdick & Howson dated March 2, 2004 regarding Contract TW-3.

Commissioner Benson moved to recommend to the Commission approval of the change orders in the amount of \$35,605.10 and approval of Resolution No. R-8-04 during the Omnibus Vote Agenda.

- A. Change Order No. 7: Contract BOV-1 (Blow Off Valve Improvements) in the amount of \$9,359.24
- B. Change Order No. 8: Contract BOV-1 (Blow Off Valve Improvements) in the amount of \$5,765.86
- C. Change Order No. 9: Contract BOV-1 (Blow Off Valve Improvements) in the credit amount of \$20,480.00

## Minutes 3/11/04 Engineering Meeting

Motion seconded by Commissioner Mueller and passed unanimously as follows:

Aye: R. Benson, W. Mueller and G. Wilcox  
Nay: None  
Absent: None

Commissioner Mueller moved to recommend approval of progress payments in the amount of \$240,697.69 as part of the Accounts Payable, subject to submission of all contractually required documentation.

A. Progress Payment No. 19: Contract BOV-1 (Blow Off Valve Repair) in the amount of \$233,930.67

B. Quick Response

a. QR6-003A Repair Sanitary Sewer at 20 Interstate Road in Addison in the amount of \$6,767.02

Motion seconded by Commissioner Benson and passed unanimously as follows:

Aye: R. Benson, W. Mueller and G. Wilcox  
Nay: None  
Absent: None

The Committee discussed the memorandum from the Acting General Manager dated December 31, 2003 regarding the proposed Engineering Capacity Study. Commissioner Benson moved to recommend approving Task Order No. 18 from draft Resolution No. R-6-04. Motion seconded by Commissioner Mueller and passed unanimously as follows:

Aye: R. Benson, W. Mueller and G. Wilcox  
Nay: None  
Absent: None

The Committee discussed the TW-3 project. It was the Committee's recommendation to split the TW-3 project into multiple contracts if needed to allow the installation of portions of the pipeline prior to certain scheduled roadway improvement projects (along Fair Oaks Road in Carol Stream and Wayne Township, and along Stearns Road in Bartlett). The Committee also discussed delaying the reservoir project to eliminate the need for inter-fund borrowing from the Rate Stabilization Reserve in order to construct the TW-3 project on its current schedule.

Minutes 3/11/04 Engineering Meeting

Commissioner Mueller moved to adjourn the meeting at 7:28 P.M. Seconded by Commissioner Benson and unanimously approved by a Voice Vote.

Aye: R. Benson, W. Mueller and G. Wilcox

Nay: None

Absent: None

Board/Minutes/Engineering/ENG0403.doc



# DuPage Water Commission

## MEMORANDUM

TO: Engineering Committee

FROM: Robert L. Martin, P.E.  
Acting General Manager

DATE: April 2, 2004

SUBJECT: Status of Operations

### Operations Overview

The Commission's sales for the month of March were a total of 2.241 billion gallons. This represents an average day of 72.3 million gallons per day (MGD), which is higher than the March 2003 average day demand of 75.7 MGD. The maximum day demand was 75.9 million gallons (March 13, 2004), which is lower than the March 2003 maximum day of 79.6 million gallons. The minimum day flow was 67.6 million gallons. The Commission recorded a total precipitation for the month of March of 3.54 inches compared to 1.06 inches for March 2003.

### Construction Overview

#### Reservoir Project

Consoer Townsend Envirodyne (CTE) completed the study phase of the project. The study phase is to verify past evaluations. A design report was submitted on March 22, 2004. Staff is evaluating the report.

#### Electrical Generation Project

Camp Dresser & McGhee (CDM) is conducting the study phase of the project. A preliminary design report was submitted on March 12, 2004. Staff is evaluating the report.

The following are attachments to this memorandum:

1. DuPage Laboratory Bench Sheet for March, 2004
2. Water Sales Analysis 01-May-00 to 31-March-04
3. Chart showing Commission sales versus allocations
4. Chart showing Commission sales versus historical averages

Operations\Memorandums\Status of Operations 040402.doc

DUPAGE WATER COMMISSION LABORATORY BENCH SHEET  
MONTHLY REPORT FOR MARCH 2004

## LEXINGTON SUPPLY

## DUPAGE DISCHARGE

DAY	FREE CL <sub>2</sub> mg/l	TURBIDITY NTU	PO <sub>4</sub> mg/l	FREE CL <sub>2</sub> mg/l	TURBIDITY NTU	TEMP °F	pH	Fluoride mg/l	PO <sub>4</sub> mg/l	P.A.C. LBS/MG	ANALYST INT
1	0.82	0.10	0.47	0.80	0.09	39	7.4	0.9	0.47	0	NB
2	0.78	0.11	0.48	0.79	0.08	40	7.4	1.0	0.48	0	NB
3	0.79	0.12	0.48	0.79	0.09	40	7.4	1.0	0.48	0	MB
4	0.77	0.10	0.48	0.79	0.09	40	7.4	1.0	0.48	0	MB
5	0.80	0.11	0.50	0.81	0.09	40	7.4	1.0	0.49	0	MB
6	0.78	0.12	0.48	0.80	0.10	40	7.4	1.0	0.47	0	MB
7	0.81	0.11	0.50	0.78	0.10	41	7.4	1.0	0.45	0	NB
8	0.78	0.11	0.50	0.76	0.10	41	7.4	1.0	0.45	0	NB
9	0.79	0.12	0.51	0.79	0.10	42	7.4	1.1	0.46	0	NB
10	0.78	0.13	0.48	0.79	0.08	42	7.4	1.1	0.45	0	NB
11	0.79	0.12	0.47	0.79	0.09	41	7.4	1.1	0.44	0	MB
12	0.81	0.11	0.49	0.79	0.09	41	7.4	1.1	0.47	0	MB
13	0.79	0.10	0.49	0.81	0.10	41	7.4	1.2	0.47	0	MB
14	0.81	0.09	0.47	0.82	0.09	41	7.4	1.0	0.48	0	MB
15	0.82	0.11	0.49	0.78	0.09	41	7.4	1.0	0.45	0	NB
16	0.80	0.11	0.49	0.80	0.09	41	7.4	1.0	0.45	0	NB
17	0.81	0.10	0.49	0.77	0.08	42	7.4	1.0	0.46	0	NB
18	0.81	0.11	0.52	0.80	0.10	41	7.4	1.0	0.44	0	NB
19	0.78	0.12	0.50	0.79	0.10	41	7.4	1.0	0.47	0	MB
20	0.78	0.11	0.47	0.78	0.10	41	7.4	1.0	0.45	0	MB
21	0.79	0.10	0.48	0.78	0.08	41	7.3	1.0	0.45	0	MB
22	0.81	0.10	0.48	0.77	0.09	41	7.3	1.1	0.47	0	MB
23	0.80	0.10	0.48	0.77	0.09	42	7.4	1.1	0.46	0	NB
24	0.78	0.09	0.47	0.79	0.09	42	7.4	1.1	0.48	0	NB
25	0.80	0.12	0.51	0.78	0.10	42	7.4	1.1	0.45	0	NB
26	0.80	0.12	0.51	0.79	0.10	42	7.4	1.1	0.44	0	NB
27	0.82	0.12	0.49	0.81	0.11	42	7.4	1.0	0.45	0	MB
28	0.83	0.11	0.49	0.81	0.09	42	7.4	1.0	0.47	0	MB
29	0.78	0.10	0.48	0.80	0.09	41	7.4	1.0	0.42	0	MB
30	0.81	0.10	0.48	0.79	0.08	41	7.4	1.1	0.44	0	MB
31	0.82	0.10	0.49	0.78	0.10	43	7.4	1.1	0.45	0	NB
AVG	0.80	0.11	0.49	0.79	0.09	41	7.4	1.0	0.46	0	
MAX	0.83	0.13	0.52	0.82	0.11	43	7.4	1.2	0.49	0	
MIN	0.77	0.09	0.47	0.76	0.08	39	7.3	0.9	0.42	0	

  
TERRANCE MCGHEE  
MAINTENANCE SUPERINTENDENT

  
ROBERT L. MARTIN  
MANAGER OF WATER OPERATIONS

DU PAGE WATER COMMISSION  
WATER SALES ANALYSIS

01-May-92 TO 31-Mar-04

PER DAY AVERAGE 80,717,563


MONTH	SALES TO CUSTOMERS (GALLONS)	PURCHASES FROM CHICAGO (GALLONS)	GALLONS BILLED %	BILLINGS TO CUSTOMERS	BILLINGS FROM CHICAGO	DOCUMENTED COMMISSION WATER USE (2)	DOCUMENTED COMMISSION WATER USE %	TOTAL ACCOUNTED FOR %
May-00	2,669,079,000	2,757,885,612	96.78%	\$3,523,184.28	\$2,997,140.76	1,063,700	0.04%	96.82%
Jun-00	2,679,123,000	2,765,987,535	96.86%	\$3,536,442.36	\$3,005,945.55	964,900	0.03%	96.89%
Jul-00	3,147,101,000	3,250,023,197	96.83%	\$4,154,173.32	\$3,531,972.81	1,313,300	0.04%	96.87%
Aug-00	3,150,764,000	3,263,518,921	96.54%	\$4,159,008.48	\$3,546,639.33	1,424,700	0.04%	96.59%
Sep-00	2,905,099,000	3,014,700,861	96.36%	\$3,834,730.68	\$3,276,235.53	1,496,600	0.05%	96.41%
Oct-00	2,523,491,000	2,609,574,787	96.70%	\$3,331,008.12	\$2,835,963.51	11,969,523	0.46%	97.16%
Nov-00	2,276,425,000	2,330,256,690	97.69%	\$3,004,881.00	\$2,532,413.70	1,226,800	0.05%	97.74%
Dec-00	2,416,208,000	2,481,365,409	97.37%	\$3,189,394.56	\$2,696,631.57	1,073,000	0.04%	97.42%
Jan-01	2,390,741,000	2,454,238,938	97.41%	\$3,155,778.12	\$2,773,290.00	1,011,300	0.04%	97.45%
Feb-01	2,126,216,000	2,167,739,071	98.08%	\$2,806,605.12	\$2,449,545.15	818,800	0.04%	98.12%
Mar-01	2,311,827,000	2,378,966,637	97.18%	\$3,051,611.64	\$2,688,232.30	3,238,200	0.14%	97.31%
Apr-01	2,291,524,000	2,346,378,053	97.66%	\$3,024,811.68	\$2,651,407.20	784,200	0.03%	97.70%
May-01	2,679,850,000	2,792,321,195	95.97%	\$3,564,200.50	\$3,155,322.95	12,320,840	0.44%	96.41%
Jun-01	2,944,352,000	3,026,438,540	97.29%	\$3,915,988.16	\$3,419,875.55	10,068,050	0.33%	97.62%
Jul-01	3,729,441,000	3,839,156,549	97.14%	\$4,960,156.53	\$4,338,246.90	2,171,700	0.06%	97.20%
Aug-01	3,217,436,000	3,265,655,796	98.52%	\$4,279,189.88	\$3,690,191.05	1,156,800	0.04%	98.56%
Sep-01	2,552,219,000	2,639,772,522	96.68%	\$3,394,451.27	\$2,982,942.95	7,064,124	0.27%	96.95%
Oct-01	2,382,399,000	2,441,347,080	97.59%	\$3,168,590.67	\$2,758,722.20	7,511,120	0.31%	97.89%
Nov-01	2,212,776,000	2,246,511,018	98.50%	\$2,942,992.08	\$2,538,557.45	7,110,473	0.32%	98.81%
Dec-01	2,289,859,000	2,319,285,708	98.73%	\$3,045,512.47	\$2,620,792.85	917,200	0.04%	98.77%
Jan-02	2,320,798,000	2,351,613,013	98.69%	\$3,086,661.34	\$2,763,145.29	1,017,300	0.04%	98.73%
Feb-02	2,101,092,000	2,140,899,881	98.14%	\$2,794,452.36	\$2,515,557.36	1,134,300	0.05%	98.19%
Mar-02	2,282,553,000	2,369,611,940	96.33%	\$3,035,795.49	\$2,784,293.72	18,554,160	0.78%	97.11%
Apr-02	2,279,744,000	2,353,213,915	96.88%	\$3,032,059.52	\$2,765,026.04	1,118,700	0.05%	96.93%
May-02	2,530,549,000	2,620,422,434	96.57%	\$3,390,935.66	\$3,078,996.36	10,740,300	0.41%	96.98%
Jun-02	2,974,993,000	3,064,246,366	97.09%	\$3,986,490.62	\$3,600,489.48	2,949,188	0.10%	97.18%
Jul-02	3,818,677,000	3,928,688,630	97.20%	\$5,117,027.18	\$4,616,209.14	1,407,000	0.04%	97.24%
Aug-02	3,243,485,000	3,347,860,391	96.88%	\$4,346,269.90	\$3,933,735.96	1,155,200	0.03%	96.92%
Sep-02	2,941,334,000	3,026,340,894	97.19%	\$3,941,387.56	\$3,555,950.55	1,130,900	0.04%	97.23%
Oct-02	2,515,785,000	2,551,823,030	98.59%	\$3,371,216.38	\$2,998,392.06	1,354,600	0.05%	98.64%
Nov-02	2,264,094,000	2,328,010,928	97.25%	\$3,034,011.20	\$2,735,412.84	811,900	0.03%	97.29%
Dec-02	2,384,875,000	2,439,819,728	97.75%	\$3,195,844.10	\$2,866,788.18	885,300	0.04%	97.78%
Jan-03	2,430,849,000	2,496,371,382	97.38%	\$3,257,685.17	\$3,053,062.20	751,400	0.03%	97.41%
Feb-03	2,166,550,000	2,216,028,831	97.77%	\$2,903,280.54	\$2,710,203.26	919,100	0.04%	97.81%
Mar-03	2,347,318,000	2,412,660,360	97.29%	\$3,145,477.42	\$2,950,683.62	835,700	0.03%	97.33%
Apr-03	2,338,518,000	2,401,856,926	97.36%	\$3,133,682.63	\$2,937,471.02	12,052,576	0.50%	97.86%
May-03	2,622,301,000	2,711,004,309	96.73%	\$3,619,032.96	\$3,315,558.27	3,119,550	0.12%	96.84%
Jun-03	3,031,274,000	3,129,263,410	96.87%	\$4,183,476.12	\$3,827,089.15	9,583,535	0.31%	97.17%
Jul-03	3,114,181,000	3,213,079,828	96.92%	\$4,297,569.78	\$3,929,596.63	3,414,287	0.11%	97.03%
Aug-03	3,137,669,000	3,237,477,343	96.92%	\$4,330,318.18	\$3,959,434.79	6,589,500	0.20%	97.12%
Sep-03	2,775,903,000	2,842,321,431	97.66%	\$3,830,750.38	\$3,476,159.11	1,081,000	0.04%	97.70%
Oct-03	2,463,017,000	2,531,079,199	97.31%	\$3,361,577.64	\$3,095,509.86	1,199,100	0.05%	97.36%
Nov-03	2,220,837,000	2,263,237,760	98.13%	\$3,110,603.92	\$2,767,939.78	1,004,600	0.04%	98.17%
Dec-03	2,302,995,000	2,357,446,124	97.69%	\$3,178,138.40	\$2,883,156.61	785,500	0.03%	97.72%
Jan-04	2,353,099,000	2,415,231,136	97.43%	\$3,247,276.62	\$3,040,776.00	999,500	0.04%	97.47%
Feb-04	2,205,542,000	2,253,789,245	97.86%	\$3,043,647.96	\$2,837,520.66	799,100	0.04%	97.89%
Mar-04	2,240,813,000	2,290,496,569	97.83%	\$3,092,321.94	\$2,883,735.18	883,800	0.04%	97.87%
TOTALS (1)	351,363,551,000	362,007,237,178	97.06%	\$469,754,903.08	\$385,769,815.07	269,932,391	0.07%	97.13%

(1) - SINCE MAY 1, 1992


(2) - REPRESENTS DU PAGE PUMP STATION, METER TESTING AND CONSTRUCTION PROJECT USAGE



**DU PAGE WATER COMMISSION SALES  
FY 2003-04 VS. ALLOCATION**



**DU PAGE WATER COMMISSION SALES  
FY 2003-04 & FY 2002-03 VS. HISTORICAL AVERAGE**





# DuPage Water Commission

## MEMORANDUM

TO: Acting General Manager

FROM: Supervisor of Pipeline Maintenance and Construction

DATE: April 2, 2004

SUBJECT: Status of Pipeline Construction

### **CONTRACT TSW-3/98 SOUTHWEST TRANSMISSION MAIN**

### **CONTRACT TW-2/00 WEST TRANSMISSION MAIN**

Shop testing for the valves under these contracts was scheduled for March 16 and 17 in Houston Texas. On Friday March 12 the manufacturer canceled the scheduled tests. The manufacturer informed staff on March 30, that it may take up to an additional 3 months to repair and prep each valve for shop testing. As a result of the manufacturer's continuing delays in furnishing metal seated valves that comply with the contract specifications, staff is proposing to eliminate these valves from the contracts. A credit for Contract TW-2 has been negotiated and appears on the Engineering Committee's agenda as change order number 42. We are negotiating a change order for Contract TSW-3 and will present to the board for their approval.

Lost Time Accidents to Date 04/02/04      0 Days

### **CONTRACT BOV-1/02 BLOW-OFF VALVE Improvements**

Rossi Contracting Co. Inc. has completed 306 blow-off valves to date with 39 remaining. This represents 89% of contract completion.

Lost Time Accidents to Date 04/02/04      0 Days

### **CONTRACT TIB-1/03 INNER BELT TRANSMISSION MAIN**

Tunnel shaft excavation is progressing at the Elmhurst WWTP and the relocation of the Villa Park water main continues. West Shore pipeline relocation work may begin sometime mid to late April. Manufacturing and testing of steel pipe is tentatively scheduled for mid April.

Lost Time Accidents To Date 04/02/04      0 Days

### **CONTRACT TW-3 WEST TRANSMISSION MAIN**

Fair Oaks Road preliminary plan and profile sheets for Phase 1 engineering were received from Earthtech on March 18, 2004. These preliminary drawings have been forwarded to AB&H for consideration in possible design revisions to the proposed alignment of the main along Fair Oaks Road.

# ALVORD, BURDICK & HOWSON, L.L.C.

## ENGINEERS

SERVICES  
WATER SUPPLY, PURIFICATION AND DISTRIBUTION  
WASTEWATER COLLECTION AND TREATMENT  
FLOOD CONTROL  
STORMWATER FACILITIES  
INVESTIGATIONS, REPORTS AND DESIGNS  
CONSTRUCTION AND OPERATION SERVICES  
APPRAISALS AND RATE REPORTS

4710-3 MAIN STREET  
LISLE, IL 60532  
TEL. (630) 493-1841 FAX: (630) 493-1843  
E-MAIL: DUPAGE@ABHENGINEERS.COM

JOHN W. ALVORD 1861-1943	CHARLES B. BURDICK 1874-1955	LOUIS R. HOWSON 1887-1985
DONALD E. ECKMANN DR. YA-TAI LIN		
J. WARREN GREEN BON G. MUI DR. RAY S.T. CHENG		
JAMES W. HEDGES WILLIAM L. MEINHOLZ RICHARD D. SHEA		

MEMBERS  
AMERICAN CONSULTING ENGINEERS COUNCIL  
AMERICAN PUBLIC WORKS ASSOCIATION  
AMERICAN SOCIETY OF CIVIL ENGINEERS  
AMERICAN WATER WORKS ASSOCIATION  
NATIONAL ASSOCIATION OF  
CORROSION ENGINEERS  
WATER ENVIRONMENT FEDERATION  
WESTERN SOCIETY OF ENGINEERS

April 1, 2004

Mr. Robert L. Martin, P.E.  
Acting General Manager  
DuPage Water Commission  
600 E. Butterfield Road  
Elmhurst, IL 60126-4642

Re: DuPage Water Commission  
West Transmission Main  
Contract TW - 3/04

Dear Mr. Martin:

As requested, the design status of referenced project is as follows:

1. We estimate that the total number of drawings for the entire project would be approximately 108. We estimate, at this time, six additional drawings for 16" connection to MS-18C.
2. As of 3/31/04, 39 preliminary plan & profile sheets along Fair Oaks Road, Army Trail Road, Gerber Road, Schick Road, Bartlett Road, Stearns Road, Greenbrook Boulevard and Central Avenue are complete and are in the internal review process.
3. The preliminary plans have been sent to Carol Stream, Wayne Township, Bartlett, Hanover Park, Roselle and DuPage County Division of Transportation. Recently we have received review comments from Village of Bartlett and Village of Roselle.
4. As instructed by the Commission staff we have asked our consultant to proceed with the preparation of legal description for the amended route along Lake Street and Bartels Road. We have also ordered the topographic survey of the amended route.

5. We have also ordered the topographic survey for the 16" main to MS-18C and collected utility information.

If you have any questions, please contact us.

Very truly yours,

ALVORD, BURDICK & HOWSON L.L.C.

By Girish K. Machhar  
Girish K. Machhar, P.E.

cc: Mr. Ed Kazmierczak, DWC

# CHANGE ORDER

## THE DUPAGE WATER COMMISSION

SHEET 1 OF 3

PROJECT NAME: Innerbelt Transmission Main

CHANGE ORDER NO. 01

LOCATION: Butterfield Road To Prairie Path

CONTRACT NO. TIB-1/03

CONTRACTOR: Rossi Contractors, Inc.

DATE: March 25, 2004

### I. A. DESCRIPTION OF CHANGES INVOLVED:

1. Replace the existing Villa park watermain with an 8" diameter Villa park watermain instead of 6' diameter Villa Park watermain shown on Contract Drawings from and after march 25, 2004, together with appurtenances and all associated work.
2. Revise the second paragraph of Subsection 3E, entitled "Village of Villa park Watermain Replacement." of the special Conditions of Contract to read as follows:

"The existing 6" watermain on the frontage Road (being replaced with an 8" watermain except for that portion replaced prior to March 25, 2004 with a 6" watermain) may be abandoned in place. All house services shall be transferred to the new main and replaced from the house side of the buffalo box (curb stop) to the new main with 1" type K copper tubing, unless otherwise shown or directed by the Village. No splicing of water services will be allowed."
3. The Schedule of Prices inadvertently omitted unit price for 6" diameter gate valve in vault for the 6" watermain that has already been relocated .As a result, new unit prices are added and the Contract Unit Price Items Nos. 40 and 41 are reduced as listed below.

### B. REASON FOR CHANGE:

The Village of Villa Park requested that the existing 6-inch watermain that was to be relocated with a 6-inch water main be upgraded to an 8-inch watermain from and after march 25, 2004. The Village of Villa Park will reimburse the Commission for this additional cost under an Intergovernmental Agreement. The Schedule of Prices inadvertently omitted unit price for 6" diameter gate valves in vault for the 6" watermain that has already been relocated.

## CHANGE ORDER NO. 01

**C. REVISION IN PRICE:**

## NEGOTIATED PRICE:

## ADDITION:

1. 8" DI Water main	1200 LF @ \$49.21/Lf	\$59,052.00
2. 8" Gate Valve in Valve Box	3 Ea @ \$3957.84/Ea	\$11,873.52
3. 8" Gate Valve in Valve Vault	3 Ea @ \$4257.84/Ea	\$12,773.52
4. 6" Gate Valve in Valve Vault	5 Ea @ \$4057.84/Ea	\$20,289.20

## DEDUCTION:

1. 6" Di Water Main(Item #40)	1200 LF @ \$35.52/LF	(\$42,624.00)
2. 6" Gate Valve in Valve Box (Item #41)	3 Ea @ \$3757.84/Ea	<u>(\$11,273.52)</u>

**TOTAL \$50,090.72****II. CHANGE ORDER CONDITIONS:**

1. The Contract completion date established in the Original Contract or as modified by previous Change Orders is hereby extended by 0 calendar days, making the final completion date **August 29, 2005**.
2. Any additional work to be performed under this Change Order shall be carried out in compliance with the specifications included in the preceding Description of Changes Involved, with the Contract Drawings designated as Innerbelt Transmission Main, and under the provisions of the Original Contract, including compliance with applicable Equipment Specifications, General Specifications, and Project Specifications for the same type of work.
3. This Change Order unless otherwise provided herein does not relieve the contractor from strict compliance with the guarantee provisions of the Original Contract, particularly those pertaining to performance and operation of equipment.
4. The Contractor expressly agrees he will place under coverage of his Performance and Payment Bonds and Contractor's Insurance all work covered by this Change Order. The Contractor will furnish to the Owner evidence of increased coverage of his Performance and Payment Bonds for the accrued value of all Change Orders which exceeds the Original Contract Price by twenty percent (20%).

## CHANGE ORDER NO. 01

## III. ADJUSTMENTS IN AMOUNT OF CONTRACT:

1.	Amount of Original Contract	<u>\$12,730,597.31</u>
2.	Net change due to previous Change Orders	<u>\$0.00</u>
3.	Amount of Contract, not including this Change Order	<u>\$12,730,597.31</u>
4.	Addition to Contract due to this Change Order	<u>\$50,090.72</u>
5.	Amount of Contract including this Change Order	<u>\$12,780,688.03</u>

RECOMMENDED FOR ACCEPTANCE: \_\_\_\_\_ ( \_\_\_\_\_ )  
For Alvord, Burdick, & Howson Date  
Consulting Engineers

ACCEPTED BY CONTRACTOR: Rossi Contractors

BY: \_\_\_\_\_ ( \_\_\_\_\_ )  
Signature of Date  
Authorized Representative

DUPAGE WATER COMMISSION:

BY: \_\_\_\_\_ ( \_\_\_\_\_ )  
James J. Holzwart Date  
General Manager



## CHANGE ORDER

**THE DUPAGE WATER COMMISSION**

SHEET 1 OF 3

PROJECT NAME: Innerbelt Transmission Main

CHANGE ORDER NO. 02

LOCATION: Butterfield Road To Prairie Path

CONTRACT NO. TIB-1/03

CONTRACTOR: Rossi Contractors, Inc.

DATE: March 26, 2004

**I. A. DESCRIPTION OF CHANGES INVOLVED:**

Delete Unit Price Items Nos. 27, South Fence Gate Remove & Replace, and 28, North Fence Gate Remove & Replace.

**B. REASON FOR CHANGE:**

The City of Elmhurst has informed the Commission that they do not wish to have the gate replacement work performed under this Contract. The Special Conditions of Contract provide that the gate replacement work would be performed only if requested by the City.

**C. REVISION IN PRICE:**

UNIT PRICE:

DEDUCTION:

1. South Fence Gate, R& R (Item # 27)	1 Ea @ \$29,960.00/Ea	(\$29,960.00)
2. North Fence Gate, R & R (Item # 28)	1 Ea @ \$29,960.00/Ea	<u>(\$29,960.00)</u>

**TOTAL (\$59,920.00)**

**CHANGE ORDER NO. 02**

**II. CHANGE ORDER CONDITIONS:**

1. The Contract completion date established in the Original Contract or as modified by previous Change Orders is hereby extended by 0 calendar days, making the final completion date **August 29, 2005**.
2. Any additional work to be performed under this Change Order shall be carried out in compliance with the specifications included in the preceding Description of Changes Involved, with the Contract Drawings designated as Innerbelt Transmission Main, and under the provisions of the Original Contract, including compliance with applicable Equipment Specifications, General Specifications, and Project Specifications for the same type of work.
3. This Change Order unless otherwise provided herein does not relieve the contractor from strict compliance with the guarantee provisions of the Original Contract, particularly those pertaining to performance and operation of equipment.
4. The Contractor expressly agrees he will place under coverage of his Performance and Payment Bonds and Contractor's Insurance all work covered by this Change Order. The Contractor will furnish to the Owner evidence of increased coverage of his Performance and Payment Bonds for the accrued value of all Change Orders which exceeds the Original Contract Price by twenty percent (20%).

## CHANGE ORDER NO. 02

## III. ADJUSTMENTS IN AMOUNT OF CONTRACT:

1.	Amount of Original Contract	<u>\$12,730,597.31</u>
2.	Net change due to previous Change Order No. 1	<u>\$50,090.72</u>
3.	Amount of Contract, not including this Change Order	<u>\$12,780,688.03</u>
4.	Deduction to Contract due to this Change Order	<u>(\$59,920.00)</u>
5.	Amount of Contract including this Change Order	<u>\$12,720,768.03</u>

RECOMMENDED FOR ACCEPTANCE: \_\_\_\_\_ ( \_\_\_\_\_ )  
For Alvord, Burdick, & Howson Date  
Consulting Engineers

ACCEPTED BY CONTRACTOR: Rossi Contractors, Inc.

BY: \_\_\_\_\_ ( \_\_\_\_\_ )  
Signature of Date  
Authorized Representative

DUPAGE WATER COMMISSION:

BY: \_\_\_\_\_ ( \_\_\_\_\_ )  
Robert L. Martin Date  
Acting General Manager

## CHANGE ORDER

**THE DUPAGE WATER COMMISSION**

SHEET 1 OF 3

PROJECT NAME: Innerbelt Transmission Main

CHANGE ORDER NO. 03

LOCATION: Butterfield Road To Prairie Path

CONTRACT NO. TIB-1/03

CONTRACTOR: Rossi Contractors, Inc.

DATE: March 26, 2004

**I. A. DESCRIPTION OF CHANGES INVOLVED:**

Additional cost for removing and disposing those portions of the abandoned 16-inch West Shore petroleum pipeline that are in conflict with trench excavation for 72-inch transmission main, approximately from Station 28+00 to Station 56+50 and from Station 77+00 to Station 79+50.

**B. REASON FOR CHANGE:**

The cost of removal and disposal of the abandoned West Shore pipeline in conflict with the trench excavation for 72-inch transmission main was not included in the agreement between West Shore and the Commission because removal and disposal by the Contractor will eliminate duplication of work and traffic disruption.

**C. REVISION IN PRICE:**

NEGOTIATED PRICE:

ADDITION:

Remove & Dispose 16"  
West Shore Pipe

3,100 LF @ \$28.00/LF

\$86,800.00

**TOTAL \$86,800.00**

**CHANGE ORDER NO. 03**

**II. CHANGE ORDER CONDITIONS:**

1. The Contract completion date established in the Original Contract or as modified by previous Change Orders is hereby extended by 0 calendar days, making the final completion date **August 29, 2005**.
2. Any additional work to be performed under this Change Order shall be carried out in compliance with the specifications included in the preceding Description of Changes Involved, with the Contract Drawings designated as Innerbelt Transmission Main, and under the provisions of the Original Contract, including compliance with applicable Equipment Specifications, General Specifications, and Project Specifications for the same type of work.
3. This Change Order unless otherwise provided herein does not relieve the contractor from strict compliance with the guarantee provisions of the Original Contract, particularly those pertaining to performance and operation of equipment.
4. The Contractor expressly agrees he will place under coverage of his Performance and Payment Bonds and Contractor's Insurance all work covered by this Change Order. The Contractor will furnish to the Owner evidence of increased coverage of his Performance and Payment Bonds for the accrued value of all Change Orders which exceeds the Original Contract Price by twenty percent (20%).

## CHANGE ORDER NO. 03

## III. ADJUSTMENTS IN AMOUNT OF CONTRACT:

1.	Amount of Original Contract	<u>\$12,730,597.31</u>
2.	Net change due to previous Change Order No. 1 & 2	<u>(\$9,829.28)</u>
3.	Amount of Contract, not including this Change Order	<u>\$12,720,768.03</u>
4.	Addition to Contract due to this Change Order	<u>\$86,800.00</u>
5.	Amount of Contract including this Change Order	<u>\$12,807,568.03</u>

RECOMMENDED FOR ACCEPTANCE: \_\_\_\_\_ ( \_\_\_\_\_ )  
For Alvord, Burdick, & Howson Date  
Consulting Engineers

ACCEPTED BY CONTRACTOR: Rossi Contractors, Inc.

BY: \_\_\_\_\_ ( \_\_\_\_\_ )  
Signature of Date  
Authorized Representative

DUPAGE WATER COMMISSION:

BY: \_\_\_\_\_ ( \_\_\_\_\_ )  
Robert L. Martin Date  
Acting General Manager

## CHANGE ORDER

### THE DUPAGE WATER COMMISSION

SHEET 1 OF 3

PROJECT NAME: Innerbelt Transmission Main

CHANGE ORDER NO. 04

LOCATION: Butterfield Road To Prairie Path

CONTRACT NO. TIB-1/03

CONTRACTOR: Rossi Contractors, Inc.

DATE: March 29, 2004

#### I. A. DESCRIPTION OF CHANGES INVOLVED:

Additional cost for installing 72-inch pipe from approximate Station 57+70 to Station 58+55 in steel tunnel casing at the intersection of Monroe Street, Riverside Drive and the Frontage Road.

#### B. REASON FOR CHANGE:

The City of Elmhurst has raised concerns about installation of 72-inch pipe in open cut across the intersection and its impact on traffic. This is a rather complex intersection with five streets converging at one point. It is also the sole access for Frontage Road from Route 83 and is used by heavy truck traffic serving the businesses along the Frontage Road. Because of the traffic problems that would develop in case of open cut construction, installing the 72-inch pipe in steel tunnel casing across the intersection would eliminate traffic delays and congestion during construction and reduce adverse impact on the businesses.

#### C. REVISION IN PRICE:

##### UNIT PRICE ITEMS:

##### ADDITION:

1. 72" Dia. Steel Pipe in Casing	85 LF @ \$2258.56/LF	\$191,977.60
2. 84" Min. Dia. Steel Casing	85 LF @ \$1610.35/LF	\$136,879.75

##### DEDUCTION:

1. 72" Dia. Steel Pipe in Open Cut	85 LF @ \$288.07/LF	(\$24,485.95)
2. Curb & Gutter, Rem. & Replace	32 LF @ \$16.05/LF	(\$513.60)
3. Asphalt Pavement, Rem. & Repl.	344 SY @ \$37.45/SY	(\$12,882.80)
4. Granular Trench backfill	404 CY @ \$18.08/CY	(\$7,304.32)
5. Topsoil & Seeding	267 SY @ \$5.92/SY	(\$1,580.64)
6. 1.5" Grind & Overlay	1287 SY @ \$20.33/SY	(\$26,164.71)

**TOTAL \$255,925.33**

**II. CHANGE ORDER CONDITIONS:**

1. The Contract completion date established in the Original Contract or as modified by previous Change Orders is hereby extended by 0 calendar days, making the final completion date **August 29, 2005**.
2. Any additional work to be performed under this Change Order shall be carried out in compliance with the specifications included in the preceding Description of Changes Involved, with the Contract Drawings designated as Innerbelt Transmission Main, and under the provisions of the Original Contract, including compliance with applicable Equipment Specifications, General Specifications, and Project Specifications for the same type of work.
3. This Change Order unless otherwise provided herein does not relieve the contractor from strict compliance with the guarantee provisions of the Original Contract, particularly those pertaining to performance and operation of equipment.
4. The Contractor expressly agrees he will place under coverage of his Performance and Payment Bonds and Contractor's Insurance all work covered by this Change Order. The Contractor will furnish to the Owner evidence of increased coverage of his Performance and Payment Bonds for the accrued value of all Change Orders which exceeds the Original Contract Price by twenty percent (20%).



## CHANGE ORDER NO. 04

**III. ADJUSTMENTS IN AMOUNT OF CONTRACT:**

1.	Amount of Original Contract	<u>\$12,730,597.31</u>
2.	Net change due to previous Change Order No. 1 through 3	<u>\$76,970.72</u>
3.	Amount of Contract, not including this Change Order	<u>\$12,807,568.03</u>
4.	Addition to Contract due to this Change Order	<u>\$255,925.33</u>
5.	Amount of Contract including this Change Order	<u>\$13,063,493.36</u>

RECOMMENDED FOR ACCEPTANCE: \_\_\_\_\_ ( \_\_\_\_\_ )  
For Alvord, Burdick, & Howson Date  
Consulting Engineers

ACCEPTED BY CONTRACTOR: Rossi Contractors, Inc.

BY: \_\_\_\_\_ ( \_\_\_\_\_ )  
Signature of Date  
Authorized Representative

DUPAGE WATER COMMISSION:

BY: \_\_\_\_\_ ( \_\_\_\_\_ )  
Robert L. Martin Date  
Acting General Manager

## CHANGE ORDER

**THE DUPAGE WATER COMMISSION**

SHEET 1 OF 4

PROJECT NAME: West Transmission Main

CHANGE ORDER NO. 42

LOCATION: Butterfield Road To Kuhn Road

CONTRACT NO. TW-2

CONTRACTOR: Rossi Contractors

DATE: March 30, 2004

**I. A. DESCRIPTION OF CHANGES INVOLVED:**

Delete Unit Price Item No. 30, 48" Remotely Operated Valve (ROV) and Vault at Station 465+50. The Contractor will deliver the materials already purchased for this work to the DWC.

**B. REASON FOR CHANGE:**

The Contractor had proposed using metal seated ROV from Adams Valves Company. After several attempts by the Manufacturer to test the valve, it has not passed the required tests. Therefore, DWC staff has decided to eliminate the ROV and Vault and take appropriate credit from the Contractor as indicated below.

**C. REVISION IN PRICE:**

NEGOTIATED PRICE:

DEDUCTION:

1. 48" ROV Butterfly Valve and Vault	1 EA @ \$157,620.00/EA	\$157,620.00
2. Expenses Incurred by the Contractor for Materials and Services (See Page 2 for Details)	1 LS @ \$47,741.92/LS	(\$47,741.92)

**TOTAL DEDUCTION      \$109,878.08**

## CHANGE ORDER NO. 42

## West Transmission Contract TW-2

Item	Unit	Qty	Unit Price	Extension
48" ROV Butterfly Valve & Vault	EA	1	157,620.00	157,620.00
Rossi Contractors				
Mechanic-(2) Laborer, attempt to seat valve	Hour	24	(156.33)	(3,751.92)
Mechanic-(2) Laborer, prepare for test	Hour	16	(156.33)	(2,501.28)
Mechanic-Laborer, pack valve for return	Hour	4	(109.38)	(437.52)
				-
				-
Subcontractors				
Layout (Initial Layout plus one refresh)	Hour	4	(120.00)	(480.00)
Pipefitter (Sump pump, float switches)	Lump Sum	1	(1,110.00)	(1,110.00)
Turn over this material to Commission				
Welder (Modify flanges for use)	Lump Sum	1	(4,256.00)	(4,256.00)
Electrician (U.S. Electric--see attached list)	Lump Sum	1	(18,340.20)	(18,340.20)
Control panel, valve vault cover switch, pressure transmitter, (2) disconnect switches,				
(2) NEMA 4 boxes, heat tracing and control. Turn this material over to Commission.				
Electrician (Aldridge Electric)	Lump Sum	1	(660.96)	(660.96)
				-
Suppliers				
Isolation Gaskets	Each	2	(1,190.00)	(2,380.00)
Elastomeric Gaskets	Each	2	(70.00)	(140.00)
Bolts-Adams Valve	Lump Sum	1	(1,430.00)	(1,430.00)
Bolts-long-Saunders valve	Each	72	(8.44)	(607.68)
Bolts-short-Saunders valve	Each	16	(7.75)	(124.00)
Nuts-Saunders valve	Each	72	(1.63)	(117.36)
Flanges (set for Adams valve)	Each	1	(8,695.00)	(8,695.00)
Turn this over to the Commission.				
Buttstrap-set	Each	2	(350.00)	(700.00)
Incidental: primer, tapecoat, packing				-
Tapecoat, primer, grout, packing mat'l, etc.	Lump Sum	1	-	-
Castings	Lump Sum	1	(1,135.00)	(1,135.00)
Stainless Steel Fabrications	Set	1	(875.00)	(875.00)
				-
				-
				-

Subtotal Cost \$ (47,741.92)  
NET CREDIT 109,878.08

**CHANGE ORDER NO. 42**

**II. CHANGE ORDER CONDITIONS:**

1. The Contract completion date established in the Original Contract or as modified by previous Change Orders is hereby extended by 0 calendar days, making the final completion date **July 09, 2003**.
2. Any additional work to be performed under this Change Order shall be carried out in compliance with the specifications included in the preceding Description of Changes Involved, with the Supplemental Contract Drawings designated as West Transmission Main, and under the provisions of the Original Contract, including compliance with applicable Equipment Specifications, General Specifications, and Project Specifications for the same type of work.
3. This Change Order unless otherwise provided herein does not relieve the contractor from strict compliance with the guarantee provisions of the Original Contract, particularly those pertaining to performance and operation of equipment.
4. The Contractor expressly agrees he will place under coverage of his Performance and Payment Bonds and Contractor's Insurance all work covered by this Change Order. The Contractor will furnish to the Owner evidence of increased coverage of his Performance and Payment Bonds for the accrued value of all Change Orders which exceeds the Original Contract Price by twenty percent (20%).

## CHANGE ORDER NO. 42

## III. ADJUSTMENTS IN AMOUNT OF CONTRACT:

1.	Amount of Original Contract	<u>\$17,476,112.15</u>
2.	Net change due to previous Change Orders No.1 to 41	<u>\$ 611,206.70</u>
3.	Amount of Contract, not including this Change Order	<u>\$18,087,318.85</u>
4.	Deduction to Contract due to this Change Order	<u>(\$109,878.08)</u>
5.	Amount of Contract including this Change Order	<u>\$17,977,440.77</u>

RECOMMENDED FOR ACCEPTANCE: \_\_\_\_\_ ( \_\_\_\_\_ )  
For Alvord, Burdick, & Howson Date  
Consulting Engineers

ACCEPTED BY CONTRACTOR: Rossi Contractors

BY: \_\_\_\_\_ ( \_\_\_\_\_ )  
Signature of Date  
Authorized Representative



DUPAGE WATER COMMISSION:

BY: \_\_\_\_\_ ( \_\_\_\_\_ )  
Robert L. Martin Date  
Acting General Manager

DU PAGE WATER COMMISSION  
 BLOW OFF VALVE REPAIR (BOV-1)  
 ROSSI CONTRACTORS  
 201 WEST LAKE STREET  
 NORTHLAKE, ILLINOIS 60164

PAYMENT # 20  
 DATE 03/30/04  
 ACCOUNT # AMOUNT  
 WF-6631 \$367,151.53  
 WF-3520 (\$36,715.16)  
 WF-3530 (\$780.00)

#	ITEM	ORIGINAL CONTRACT QUANTITY	UNIT	UNIT PRICE	ORIGINAL CONTRACT PRICE	AMENDED CONTRACT QUANTITY	AMENDED CONTRACT PRICE	CURRENT QUANTITY	TO DATE EXTENSION	PREVIOUS QUANTITY	PAYMENT EXTENSION	THIS QUANTITY	PAYMENT EXTENSION	CONTRACT QUANTITY	BALANCE EXTENSION
	CONTRACT SUB-TOTALS				\$7,812,435.00 *****		\$7,747,959.40 *****		\$6,042,778.25		\$5,675,626.72		\$367,151.53		\$1,705,181.15
	RETENTION	10.00%							(\$804,277.83)		(\$567,562.67)		(\$36,715.16)		\$804,277.83
	CONTRACT TOTALS								\$5,438,500.42		\$5,108,064.05		\$330,436.37		\$2,309,458.98 *****
DEDUCTS/BONUS															
1X	EXCESS ENGINEERING COSTS-DWC		HRS.	(60.00)				573.50	(\$34,410.00)	560.50	(\$33,630.00)	13.00	(\$780.00)		
	NET PAYMENT TO CONTRACTOR								\$5,404,090.42 *****		\$5,074,434.05 *****		\$329,658.37 *****		
	CHANGE ORDER PERCENTAGE								-0.83%						

STAFF APPROVALS	
ENGINEERING	
ACCOUNTING	

BLOW OFF VALVE REPAIR (BOV-1)  
ROSSI CONTRACTORS  
201 WEST LAKE STREET  
NORTHLAKE, ILLINOIS 60164

DATE  
ACCOUNT # AMOUNT  
WF-6631 \$367,151.53  
WF-3520 (\$36,715.16)  
WF-3530 (\$780.00)

#	ITEM	ORIGINAL CONTRACT QUANTITY	UNIT	UNIT PRICE	ORIGINAL CONTRACT PRICE	AMENDED CONTRACT QUANTITY	AMENDED CONTRACT PRICE	CURRENT QUANTITY	TO DATE EXTENSION	PREVIOUS QUANTITY	PAYMENT EXTENSION	THIS QUANTITY	PAYMENT EXTENSION	CONTRACT QUANTITY	BALANCE EXTENSION
1	Valve #1	100%	Lump Sum	\$0.00	\$0.00	100%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$0.00
2	Valve #2	100%	Lump Sum	\$12,500.00	\$12,500.00	100%	\$12,500.00	100%	\$12,500.00	100%	\$12,500.00	0%	\$0.00	0%	\$0.00
3	Valve #3	100%	Lump Sum	\$0.00	\$0.00	100%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$0.00
4	Valve #4	100%	Lump Sum	\$0.00	\$0.00	100%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$0.00
5	Valve #5	100%	Lump Sum	\$0.00	\$0.00	100%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$0.00
6	Valve #6	100%	Lump Sum	\$50,500.00	\$50,500.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00
7	Valve #7	100%	Lump Sum	\$0.00	\$0.00	100%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$0.00
8	Valve #8	100%	Lump Sum	\$0.00	\$0.00	100%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$0.00
9	Valve #9	100%	Lump Sum	\$0.00	\$0.00	100%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$0.00
10	Valve #10	100%	Lump Sum	\$19,300.00	\$19,300.00	100%	\$19,300.00	100%	\$19,300.00	100%	\$19,300.00	0%	\$0.00	0%	\$0.00
11	Valve #11	100%	Lump Sum	\$0.00	\$0.00	100%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$0.00
12	Valve #12	100%	Lump Sum	\$16,200.00	\$16,200.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00
13	Valve #13	100%	Lump Sum	\$14,600.00	\$14,600.00	100%	\$14,600.00	100%	\$14,600.00	100%	\$14,600.00	0%	\$0.00	0%	\$0.00
14	Valve #14	100%	Lump Sum	\$49,600.00	\$49,600.00	100%	\$49,600.00	100%	\$49,600.00	100%	\$49,600.00	0%	\$0.00	0%	\$0.00
15	Valve #15	100%	Lump Sum	\$15,900.00	\$15,900.00	100%	\$15,900.00	100%	\$15,900.00	100%	\$15,900.00	0%	\$0.00	0%	\$0.00
16	Valve #16	100%	Lump Sum	\$48,500.00	\$48,500.00	100%	\$48,500.00	100%	\$48,500.00	100%	\$48,500.00	0%	\$0.00	0%	\$0.00
17	Valve #17	100%	Lump Sum	\$0.00	\$0.00	100%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$0.00
18	Valve #18	100%	Lump Sum	\$49,400.00	\$49,400.00	100%	\$49,400.00	100%	\$49,400.00	100%	\$49,400.00	0%	\$0.00	0%	\$0.00
19	Valve #19	100%	Lump Sum	\$0.00	\$0.00	100%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$0.00
20	Valve #20	100%	Lump Sum	\$13,900.00	\$13,900.00	100%	\$13,900.00	100%	\$13,900.00	100%	\$13,900.00	0%	\$0.00	0%	\$0.00
21	Valve #21	100%	Lump Sum	\$19,600.00	\$19,600.00	100%	\$19,600.00	100%	\$19,600.00	100%	\$19,600.00	0%	\$0.00	0%	\$0.00
22	Valve #22	100%	Lump Sum	\$0.00	\$0.00	100%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$0.00
23	Valve #23	100%	Lump Sum	\$0.00	\$0.00	100%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$0.00
24	Valve #24	100%	Lump Sum	\$11,800.00	\$11,800.00	100%	\$11,800.00	100%	\$11,800.00	100%	\$11,800.00	0%	\$0.00	0%	\$0.00
25	Valve #25	100%	Lump Sum	\$18,700.00	\$18,700.00	100%	\$18,700.00	100%	\$18,700.00	100%	\$18,700.00	0%	\$0.00	0%	\$0.00
26	Valve #26	100%	Lump Sum	\$19,400.00	\$19,400.00	100%	\$19,400.00	100%	\$19,400.00	0%	\$0.00	100%	\$19,400.00	0%	\$0.00
27	Valve #27	100%	Lump Sum	\$15,700.00	\$15,700.00	100%	\$15,700.00	100%	\$15,700.00	100%	\$15,700.00	0%	\$0.00	0%	\$0.00
28	Valve #28	100%	Lump Sum	\$16,900.00	\$16,900.00	100%	\$16,900.00	100%	\$16,900.00	100%	\$16,900.00	0%	\$0.00	0%	\$0.00
29	Valve #29	100%	Lump Sum	\$16,500.00	\$16,500.00	100%	\$16,500.00	100%	\$16,500.00	100%	\$16,500.00	0%	\$0.00	0%	\$0.00
30	Valve #30	100%	Lump Sum	\$14,800.00	\$14,800.00	100%	\$14,800.00	100%	\$14,800.00	100%	\$14,800.00	0%	\$0.00	0%	\$0.00
31	Valve #31	100%	Lump Sum	\$15,700.00	\$15,700.00	100%	\$15,700.00	100%	\$15,700.00	100%	\$15,700.00	0%	\$0.00	0%	\$0.00
32	Valve #32	100%	Lump Sum	\$11,800.00	\$11,800.00	100%	\$11,800.00	100%	\$11,800.00	100%	\$11,800.00	0%	\$0.00	0%	\$0.00
33	Valve #33	100%	Lump Sum	\$68,600.00	\$68,600.00	100%	\$68,600.00	100%	\$68,600.00	100%	\$68,600.00	0%	\$0.00	0%	\$0.00
34	Valve #34	100%	Lump Sum	\$16,400.00	\$16,400.00	100%	\$16,400.00	100%	\$16,400.00	100%	\$16,400.00	0%	\$0.00	0%	\$0.00
35	Valve #35	100%	Lump Sum	\$13,800.00	\$13,800.00	100%	\$13,800.00	100%	\$13,800.00	100%	\$13,800.00	0%	\$0.00	0%	\$0.00
36	Valve #36	100%	Lump Sum	\$51,700.00	\$51,700.00	100%	\$51,700.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$51,700.00
37	Valve #37	100%	Lump Sum	\$69,500.00	\$69,500.00	100%	\$69,500.00	100%	\$69,500.00	100%	\$69,500.00	0%	\$0.00	0%	\$0.00
38	Valve #38	100%	Lump Sum	\$19,500.00	\$19,500.00	100%	\$19,500.00	100%	\$19,500.00	100%	\$19,500.00	0%	\$0.00	0%	\$0.00
39	Valve #39	100%	Lump Sum	\$15,500.00	\$15,500.00	100%	\$15,500.00	100%	\$15,500.00	100%	\$15,500.00	0%	\$0.00	0%	\$0.00
40	Valve #40	100%	Lump Sum	\$16,000.00	\$16,000.00	100%	\$16,000.00	100%	\$16,000.00	100%	\$16,000.00	0%	\$0.00	0%	\$0.00
41	Valve #41	100%	Lump Sum	\$18,600.00	\$18,600.00	100%	\$18,600.00	100%	\$18,600.00	100%	\$18,600.00	0%	\$0.00	0%	\$0.00
42	Valve #42	100%	Lump Sum	\$47,600.00	\$47,600.00	100%	\$47,600.00	100%	\$47,600.00	100%	\$47,600.00	0%	\$0.00	0%	\$0.00
43	Valve #43	100%	Lump Sum	\$16,200.00	\$16,200.00	100%	\$16,200.00	100%	\$16,200.00	100%	\$16,200.00	0%	\$0.00	0%	\$0.00
44	Valve #44	100%	Lump Sum	\$48,800.00	\$48,800.00	100%	\$48,800.00	100%	\$48,800.00	100%	\$48,800.00	0%	\$0.00	0%	\$0.00
45	Valve #45	100%	Lump Sum	\$48,500.00	\$48,500.00	100%	\$48,500.00	100%	\$48,500.00	100%	\$48,500.00	0%	\$0.00	0%	\$0.00
46	Valve #46	100%	Lump Sum	\$49,300.00	\$49,300.00	100%	\$49,300.00	100%	\$49,300.00	100%	\$49,300.00	0%	\$0.00	0%	\$0.00
47	Valve #47	100%	Lump Sum	\$13,100.00	\$13,100.00	100%	\$13,100.00	100%	\$13,100.00	100%	\$13,100.00	0%	\$0.00	0%	\$0.00
48	Valve #48	100%	Lump Sum	\$15,600.00	\$15,600.00	100%	\$15,600.00	100%	\$15,600.00	100%	\$15,600.00	0%	\$0.00	0%	\$0.00
49	Valve #49	100%	Lump Sum	\$49,500.00	\$49,500.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00
50	Valve #50	100%	Lump Sum	\$13,800.00	\$13,800.00	100%	\$13,800.00	100%	\$13,800.00	100%	\$13,800.00	0%	\$0.00	0%	\$0.00
51	Valve #51	100%	Lump Sum	\$11,300.00	\$11,300.00	100%	\$11,300.00	100%	\$11,300.00	100%	\$11,300.00	0%	\$0.00	0%	\$0.00
52	Valve #52	100%	Lump Sum	\$11,600.00	\$11,600.00	100%	\$11,600.00	100%	\$11,600.00	100%	\$11,600.00	0%	\$0.00	0%	\$0.00
53	Valve #53	100%	Lump Sum	\$11,400.00	\$11,400.00	100%	\$11,400.00	100%	\$11,400.00	100%	\$11,400.00	0%	\$0.00	0%	\$0.00
54	Valve #54	100%	Lump Sum	\$19,300.00	\$19,300.00	100%	\$19,300.00	100%	\$19,300.00	100%	\$19,300.00	0%	\$0.00	0%	\$0.00
55	Valve #55	100%	Lump Sum	\$13,800.00	\$13,800.00	100%	\$13,800.00	100%	\$13,800.00	100%	\$13,800.00	0%	\$0.00	0%	\$0.00
56	Valve #56	100%	Lump Sum	\$11,800.00	\$11,800.00	100%	\$11,800.00	100%	\$11,800.00	100%	\$11,800.00	0%	\$0.00	0%	\$0.00
57	Valve #57	100%	Lump Sum	\$11,800.00	\$11,800.00	100%	\$11,800.00	100%	\$11,800.00	100%	\$11,800.00	0%	\$0.00	0%	\$0.00
58	Valve #58	100%	Lump Sum	\$12,500.00	\$12,500.00	100%	\$12,500.00	100%	\$12,500.00	100%	\$12,500.00	0%	\$0.00	0%	\$0.00
59	Valve #59	100%	Lump Sum	\$11,700.00	\$11,700.00	100%	\$11,700.00	100%	\$11,700.00	100%	\$11,700.00	0%	\$0.00	0%	\$0.00
60	Valve #60	100%	Lump Sum	\$11,700.00	\$11,700.00	100%	\$11,700.00	100%	\$11,700.00	100%	\$11,700.00	0%	\$0.00	0%	\$0.00
61	Valve #61	100%	Lump Sum	\$11,600.00	\$11,600.00	100%	\$11,600.00	100%	\$11,600.00	100%	\$11,600.00	0%	\$0.00	0%	\$0.00
62	Valve #62	100%	Lump Sum	\$16,500.00	\$16,500.00	100%	\$16,500.00	100%	\$16,500.00	100%	\$16,500.00	0%	\$0.00	0%	\$0.00
63	Valve #63	100%	Lump Sum	\$15,500.00	\$15,500.00	100%	\$15,500.00	100%	\$15,500.00	100%	\$15,500.00	0%	\$0.00	0%	\$0.00
64	Valve #64	100%	Lump Sum	\$26,600.00	\$26,600.00	100%	\$26,600.00	100%	\$26,600.00	100%	\$26,600.00	0%	\$0.00	0%	\$0.00
65	Valve #65	100%	Lump Sum	\$11,800.00	\$11,800.00	100%	\$11,800.00	100%	\$11,800.00	100%	\$11,800.00	0%	\$0.00	0%	\$0.00
66	Valve #66	100%	Lump Sum	\$19,100.00	\$19,100.00	100%	\$19,100.00	100%	\$19,100.00	100%	\$19,100.00	0%	\$0.00	0%	\$0.00
67	Valve #67	100%	Lump Sum	\$67,900.00	\$67,900.00	100%	\$67,900.00	100%	\$67,900.00	100%	\$67,900.00	0%	\$0.00	0%	\$0.00
68	Valve #68	100%	Lump Sum	\$16,500.00	\$16,500.00	100%	\$16,500.00	100%	\$16,500.00	100%	\$16,500.00	0%	\$0.00	0%	\$0.00
69	Valve #69	100%	Lump Sum	\$16,200.00	\$16,200.00	100%	\$16,200.00	100%	\$16,200.00	100%	\$16,200.00	0%	\$0.00	0%	\$0.00
70	Valve #70	100%	Lump Sum	\$16,200.00	\$16,200.00	100%	\$16,200.00	100%	\$16,200.00	100%	\$16,200.00	0%	\$0.00	0%	\$0.00
71	Valve #71	100%	Lump Sum	\$18,500.00	\$18,500.00	100%	\$18,500.00	100%	\$18,500.00	100%	\$18,500.00	0%	\$0.00	0%	\$0.00
72	Valve #72	100%	Lump Sum	\$18,600.00	\$18,600.00	100%	\$18,600.00	100%	\$18,600.00	100%	\$18,600.00	0%	\$0.00	0%	\$0.00
73	Valve #73	100%	Lump Sum	\$18,500.00	\$18,500.00	100%	\$18,500.00	100%	\$18,500.00	100%	\$18,500.00	0%	\$0.00	0%	\$0.00
74	Valve #74	100%	Lump Sum	\$16,100.00	\$16,100.00	100%	\$16,100.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$16,100.00
75	Valve #75	100%	Lump Sum	\$0.00	\$0.00	100%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$0.00
76	Valve #76	100%	Lump Sum	\$12,600.00	\$12,600.00	100%	\$12,600.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$12,600.00
77	Valve #77	100%	Lump Sum	\$16,500.00	\$16,500.00	100%	\$16,500.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$16,500.00
78	Valve #78	100%	Lump Sum	\$0.00	\$0.00	100%	\$0.0								

BLOW OFF VALVE REPAIR (BOV-1)

DATE 03/30/04

ROSSI CONTRACTORS  
201 WEST LAKE STREET  
NORTH LAKE, ILLINOIS 60164

ACCOUNT #

AMOUNT

WF-6631

\$367,151.53

WF-3520

(\$36,715.18)

WF-3530

(\$780.00)

#	ITEM	ORIGINAL CONTRACT QUANTITY	UNIT	UNIT PRICE	ORIGINAL CONTRACT PRICE	AMENDED CONTRACT QUANTITY	AMENDED CONTRACT PRICE	CURRENT QUANTITY	TO DATE EXTENSION	PREVIOUS QUANTITY	PAYMENT EXTENSION	THIS QUANTITY	PAYMENT EXTENSION	CONTRACT QUANTITY	BALANCE EXTENSION
81	Valve #81	100%	Lump Sum	\$16,300.00	\$16,300.00	100%	\$16,300.00	100%	\$16,300.00	0%	\$0.00	100%	\$16,300.00	0%	\$0.00
82	Valve #82	100%	Lump Sum	\$19,100.00	\$19,100.00	100%	\$19,100.00	100%	\$19,100.00	0%	\$0.00	100%	\$19,100.00	0%	\$0.00
83	Valve #83	100%	Lump Sum	\$14,300.00	\$14,300.00	100%	\$14,300.00	100%	\$14,300.00	0%	\$0.00	100%	\$14,300.00	0%	\$0.00
84	Valve #84	100%	Lump Sum	\$16,000.00	\$16,000.00	100%	\$16,000.00	100%	\$16,000.00	0%	\$0.00	100%	\$16,000.00	0%	\$0.00
85	Valve #85	100%	Lump Sum	\$16,300.00	\$16,300.00	100%	\$16,300.00	100%	\$16,300.00	0%	\$0.00	100%	\$16,300.00	0%	\$0.00
86	Valve #86	100%	Lump Sum	\$16,500.00	\$16,500.00	100%	\$16,500.00	100%	\$16,500.00	0%	\$0.00	100%	\$16,500.00	0%	\$0.00
87	Valve #87	100%	Lump Sum	\$11,300.00	\$11,300.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00
88	Valve #88	100%	Lump Sum	\$0.00	\$0.00	100%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$0.00
89	Valve #89	100%	Lump Sum	\$15,100.00	\$15,100.00	100%	\$15,100.00	100%	\$15,100.00	100%	\$15,100.00	0%	\$0.00	0%	\$0.00
90	Valve #90	100%	Lump Sum	\$12,200.00	\$12,200.00	100%	\$12,200.00	100%	\$12,200.00	100%	\$12,200.00	0%	\$0.00	0%	\$0.00
91	Valve #91	100%	Lump Sum	\$11,200.00	\$11,200.00	100%	\$11,200.00	100%	\$11,200.00	0%	\$0.00	100%	\$11,200.00	0%	\$0.00
92	Valve #92	100%	Lump Sum	\$11,500.00	\$11,500.00	100%	\$11,500.00	100%	\$11,500.00	0%	\$0.00	100%	\$11,500.00	0%	\$0.00
93	Valve #93	100%	Lump Sum	\$0.00	\$0.00	100%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$0.00
94	Valve #94	100%	Lump Sum	\$11,900.00	\$11,900.00	100%	\$11,900.00	100%	\$11,900.00	0%	\$0.00	100%	\$11,900.00	0%	\$0.00
95	Valve #95	100%	Lump Sum	\$16,000.00	\$16,000.00	100%	\$16,000.00	100%	\$16,000.00	100%	\$16,000.00	0%	\$0.00	0%	\$0.00
96	Valve #96	100%	Lump Sum	\$16,800.00	\$16,800.00	100%	\$16,800.00	100%	\$16,800.00	100%	\$16,800.00	0%	\$0.00	0%	\$0.00
97	Valve #97	100%	Lump Sum	\$16,300.00	\$16,300.00	100%	\$16,300.00	100%	\$16,300.00	0%	\$0.00	100%	\$16,300.00	0%	\$0.00
98	Valve #98	100%	Lump Sum	\$16,400.00	\$16,400.00	100%	\$16,400.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$16,400.00
99	Valve #99	100%	Lump Sum	\$70,400.00	\$70,400.00	100%	\$70,400.00	100%	\$70,400.00	100%	\$70,400.00	0%	\$0.00	0%	\$0.00
100	Valve #100	100%	Lump Sum	\$15,000.00	\$15,000.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00
101	Valve #101	100%	Lump Sum	\$50,500.00	\$50,500.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00
102	Valve #102	100%	Lump Sum	\$51,000.00	\$51,000.00	100%	\$51,000.00	100%	\$51,000.00	100%	\$51,000.00	0%	\$0.00	0%	\$0.00
103	Valve #103	100%	Lump Sum	\$49,100.00	\$49,100.00	100%	\$49,100.00	100%	\$49,100.00	100%	\$49,100.00	0%	\$0.00	0%	\$0.00
104	Valve #104	100%	Lump Sum	\$0.00	\$0.00	100%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$0.00
105	Valve #105	100%	Lump Sum	\$0.00	\$0.00	100%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$0.00
106	Valve #106	100%	Lump Sum	\$16,700.00	\$16,700.00	100%	\$16,700.00	100%	\$16,700.00	100%	\$16,700.00	0%	\$0.00	0%	\$0.00
107	Valve #107	100%	Lump Sum	\$12,800.00	\$12,800.00	100%	\$12,800.00	100%	\$12,800.00	100%	\$12,800.00	0%	\$0.00	0%	\$0.00
108	Valve #108	100%	Lump Sum	\$70,700.00	\$70,700.00	100%	\$70,700.00	100%	\$70,700.00	100%	\$70,700.00	0%	\$0.00	0%	\$0.00
109	Valve #109	100%	Lump Sum	\$27,500.00	\$27,500.00	100%	\$27,500.00	100%	\$27,500.00	100%	\$27,500.00	0%	\$0.00	0%	\$0.00
110	Valve #110	100%	Lump Sum	\$27,300.00	\$27,300.00	100%	\$27,300.00	100%	\$27,300.00	100%	\$27,300.00	0%	\$0.00	0%	\$0.00
111	Valve #111	100%	Lump Sum	\$17,600.00	\$17,600.00	100%	\$17,600.00	100%	\$17,600.00	100%	\$17,600.00	0%	\$0.00	0%	\$0.00
112	Valve #112	100%	Lump Sum	\$0.00	\$0.00	100%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$0.00
113	Valve #113	100%	Lump Sum	\$0.00	\$0.00	100%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$0.00
114	Valve #114	100%	Lump Sum	\$0.00	\$0.00	100%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$0.00
115	Valve #115	100%	Lump Sum	\$0.00	\$0.00	100%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$0.00
116	Valve #116	100%	Lump Sum	\$19,400.00	\$19,400.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00
117	Valve #117	100%	Lump Sum	\$17,700.00	\$17,700.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00
118	Valve #118	100%	Lump Sum	\$16,200.00	\$16,200.00	100%	\$16,200.00	100%	\$16,200.00	100%	\$16,200.00	0%	\$0.00	0%	\$0.00
119	Valve #119	100%	Lump Sum	\$12,100.00	\$12,100.00	100%	\$12,100.00	100%	\$12,100.00	0%	\$0.00	100%	\$12,100.00	0%	\$0.00
120	Valve #120	100%	Lump Sum	\$24,500.00	\$24,500.00	100%	\$24,500.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$24,500.00
121	Valve #121	100%	Lump Sum	\$28,000.00	\$28,000.00	100%	\$28,000.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$28,000.00
122	Valve #122	100%	Lump Sum	\$26,700.00	\$26,700.00	100%	\$26,700.00	100%	\$26,700.00	0%	\$0.00	100%	\$26,700.00	0%	\$0.00
123	Valve #123	100%	Lump Sum	\$11,700.00	\$11,700.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00
124	Valve #124	100%	Lump Sum	\$12,100.00	\$12,100.00	100%	\$12,100.00	100%	\$12,100.00	100%	\$12,100.00	0%	\$0.00	0%	\$0.00
125	Valve #125	100%	Lump Sum	\$13,500.00	\$13,500.00	100%	\$13,500.00	100%	\$13,500.00	100%	\$13,500.00	0%	\$0.00	0%	\$0.00
126	Valve #126	100%	Lump Sum	\$11,800.00	\$11,800.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00
127	Valve #127	100%	Lump Sum	\$16,500.00	\$16,500.00	100%	\$16,500.00	100%	\$16,500.00	100%	\$16,500.00	0%	\$0.00	0%	\$0.00
128	Valve #128	100%	Lump Sum	\$15,100.00	\$15,100.00	100%	\$15,100.00	100%	\$15,100.00	100%	\$15,100.00	0%	\$0.00	0%	\$0.00
129	Valve #129	100%	Lump Sum	\$16,700.00	\$16,700.00	100%	\$16,700.00	100%	\$16,700.00	100%	\$16,700.00	0%	\$0.00	0%	\$0.00
130	Valve #130	100%	Lump Sum	\$12,300.00	\$12,300.00	100%	\$12,300.00	100%	\$12,300.00	100%	\$12,300.00	0%	\$0.00	0%	\$0.00
131	Valve #131	100%	Lump Sum	\$16,400.00	\$16,400.00	100%	\$16,400.00	100%	\$16,400.00	100%	\$16,400.00	0%	\$0.00	0%	\$0.00
132	Valve #132	100%	Lump Sum	\$16,500.00	\$16,500.00	100%	\$16,500.00	100%	\$16,500.00	100%	\$16,500.00	0%	\$0.00	0%	\$0.00
133	Valve #133	100%	Lump Sum	\$12,900.00	\$12,900.00	100%	\$12,900.00	100%	\$12,900.00	100%	\$12,900.00	0%	\$0.00	0%	\$0.00
134	Valve #134	100%	Lump Sum	\$12,900.00	\$12,900.00	100%	\$12,900.00	100%	\$12,900.00	0%	\$0.00	100%	\$12,900.00	0%	\$0.00
135	Valve #135	100%	Lump Sum	\$12,700.00	\$12,700.00	100%	\$12,700.00	100%	\$12,700.00	100%	\$12,700.00	0%	\$0.00	0%	\$0.00
136	Valve #136	100%	Lump Sum	\$12,100.00	\$12,100.00	100%	\$12,100.00	100%	\$12,100.00	100%	\$12,100.00	0%	\$0.00	0%	\$0.00
137	Valve #137	100%	Lump Sum	\$15,900.00	\$15,900.00	100%	\$15,900.00	100%	\$15,900.00	100%	\$15,900.00	0%	\$0.00	0%	\$0.00
138	Valve #138	100%	Lump Sum	\$11,800.00	\$11,800.00	100%	\$11,800.00	100%	\$11,800.00	100%	\$11,800.00	0%	\$0.00	0%	\$0.00
139	Valve #139	100%	Lump Sum	\$16,200.00	\$16,200.00	100%	\$16,200.00	100%	\$16,200.00	100%	\$16,200.00	0%	\$0.00	0%	\$0.00
140	Valve #140	100%	Lump Sum	\$16,500.00	\$16,500.00	100%	\$16,500.00	100%	\$16,500.00	100%	\$16,500.00	0%	\$0.00	0%	\$0.00
141	Valve #141	100%	Lump Sum	\$14,300.00	\$14,300.00	100%	\$14,300.00	100%	\$14,300.00	100%	\$14,300.00	0%	\$0.00	0%	\$0.00
142	Valve #142	100%	Lump Sum	\$15,500.00	\$15,500.00	100%	\$15,500.00	100%	\$15,500.00	100%	\$15,500.00	0%	\$0.00	0%	\$0.00
143	Valve #143	100%	Lump Sum	\$16,400.00	\$16,400.00	100%	\$16,400.00	100%	\$16,400.00	100%	\$16,400.00	0%	\$0.00	0%	\$0.00
144	Valve #144	100%	Lump Sum	\$49,900.00	\$49,900.00	100%	\$49,900.00	100%	\$49,900.00	100%	\$49,900.00	0%	\$0.00	0%	\$0.00
145	Valve #145	100%	Lump Sum	\$14,500.00	\$14,500.00	100%	\$14,500.00	100%	\$14,500.00	100%	\$14,500.00	0%	\$0.00	0%	\$0.00
146	Valve #14														



ROSSI CONTRACTORS  
201 WEST LAKE STREET  
NORTH LAKE, ILLINOIS 60164

DATE 03/30/04

ACCOUNT # AMOUNT  
WF-6631 \$387,151.53  
WF-3520 (\$38,715.18)  
WF-3530 (\$780.00)

#	ITEM	ORIGINAL CONTRACT QUANTITY	UNIT	UNIT PRICE	ORIGINAL CONTRACT PRICE	AMENDED CONTRACT QUANTITY	AMENDED CONTRACT PRICE	CURRENT QUANTITY	TO DATE EXTENSION	PREVIOUS QUANTITY	PAYMENT EXTENSION	THIS QUANTITY	PAYMENT EXTENSION	CONTRACT QUANTITY	BALANCE EXTENSION
161	Valve #161	100%	Lump Sum	\$17,800.00	\$17,800.00	100%	\$17,800.00	100%	\$17,800.00	100%	\$17,800.00	0%	\$0.00	0%	\$0.00
162	Valve #162	100%	Lump Sum	\$16,500.00	\$16,500.00	100%	\$16,500.00	100%	\$16,500.00	100%	\$16,500.00	0%	\$0.00	0%	\$0.00
163	Valve #163	100%	Lump Sum	\$17,200.00	\$17,200.00	100%	\$17,200.00	100%	\$17,200.00	100%	\$17,200.00	100%	\$0.00	0%	\$0.00
164	Valve #164	100%	Lump Sum	\$12,500.00	\$12,500.00	100%	\$12,500.00	100%	\$12,500.00	100%	\$12,500.00	100%	\$0.00	0%	\$0.00
165	Valve #165	100%	Lump Sum	\$11,900.00	\$11,900.00	100%	\$11,900.00	100%	\$11,900.00	100%	\$11,900.00	100%	\$0.00	0%	\$0.00
166	Valve #166	100%	Lump Sum	\$15,800.00	\$15,800.00	100%	\$15,800.00	100%	\$15,800.00	100%	\$15,800.00	0%	\$0.00	0%	\$0.00
167	Valve #167	100%	Lump Sum	\$15,300.00	\$15,300.00	100%	\$15,300.00	100%	\$15,300.00	100%	\$15,300.00	0%	\$0.00	0%	\$0.00
168	Valve #168	100%	Lump Sum	\$16,400.00	\$16,400.00	100%	\$16,400.00	100%	\$16,400.00	100%	\$16,400.00	100%	\$0.00	0%	\$0.00
169	Valve #169	100%	Lump Sum	\$17,700.00	\$17,700.00	100%	\$17,700.00	100%	\$17,700.00	100%	\$17,700.00	0%	\$0.00	0%	\$0.00
170	Valve #170	100%	Lump Sum	\$15,800.00	\$15,800.00	100%	\$15,800.00	100%	\$15,800.00	100%	\$15,800.00	0%	\$0.00	0%	\$0.00
171	Valve #171	100%	Lump Sum	\$18,400.00	\$18,400.00	100%	\$18,400.00	100%	\$18,400.00	100%	\$18,400.00	100%	\$0.00	0%	\$0.00
172	Valve #172	100%	Lump Sum	\$15,900.00	\$15,900.00	100%	\$15,900.00	100%	\$15,900.00	100%	\$15,900.00	0%	\$0.00	0%	\$0.00
173	Valve #173	100%	Lump Sum	\$16,300.00	\$16,300.00	100%	\$16,300.00	100%	\$16,300.00	100%	\$16,300.00	0%	\$0.00	0%	\$0.00
174	Valve #174	100%	Lump Sum	\$17,700.00	\$17,700.00	100%	\$17,700.00	100%	\$17,700.00	100%	\$17,700.00	0%	\$0.00	0%	\$0.00
175	Valve #175	100%	Lump Sum	\$18,200.00	\$18,200.00	100%	\$18,200.00	100%	\$18,200.00	100%	\$18,200.00	0%	\$0.00	0%	\$0.00
176	Valve #176	100%	Lump Sum	\$16,900.00	\$16,900.00	100%	\$16,900.00	100%	\$16,900.00	100%	\$16,900.00	0%	\$0.00	0%	\$0.00
177	Valve #177	100%	Lump Sum	\$17,700.00	\$17,700.00	100%	\$17,700.00	100%	\$17,700.00	100%	\$17,700.00	100%	\$0.00	0%	\$0.00
178	Valve #178	100%	Lump Sum	\$16,800.00	\$16,800.00	100%	\$16,800.00	100%	\$16,800.00	100%	\$16,800.00	0%	\$0.00	0%	\$0.00
179	Valve #179	100%	Lump Sum	\$16,800.00	\$16,800.00	100%	\$16,800.00	100%	\$16,800.00	100%	\$16,800.00	0%	\$0.00	0%	\$0.00
180	Valve #180	100%	Lump Sum	\$48,400.00	\$48,400.00	100%	\$48,400.00	100%	\$48,400.00	100%	\$48,400.00	0%	\$0.00	0%	\$0.00
181	Valve #181	100%	Lump Sum	\$12,800.00	\$12,800.00	100%	\$12,800.00	100%	\$12,800.00	100%	\$12,800.00	0%	\$0.00	0%	\$0.00
182	Valve #182	100%	Lump Sum	\$11,800.00	\$11,800.00	100%	\$11,800.00	100%	\$11,800.00	100%	\$11,800.00	0%	\$0.00	0%	\$0.00
183	Valve #183	100%	Lump Sum	\$16,300.00	\$16,300.00	100%	\$16,300.00	100%	\$16,300.00	100%	\$16,300.00	100%	\$0.00	0%	\$0.00
184	Valve #184	100%	Lump Sum	\$12,600.00	\$12,600.00	100%	\$12,600.00	100%	\$12,600.00	100%	\$12,600.00	100%	\$0.00	0%	\$0.00
185	Valve #185	100%	Lump Sum	\$13,500.00	\$13,500.00	100%	\$13,500.00	100%	\$13,500.00	100%	\$13,500.00	0%	\$0.00	0%	\$0.00
186	Valve #186	100%	Lump Sum	\$12,600.00	\$12,600.00	100%	\$12,600.00	100%	\$12,600.00	100%	\$12,600.00	0%	\$0.00	0%	\$0.00
187	Valve #187	100%	Lump Sum	\$12,400.00	\$12,400.00	100%	\$12,400.00	100%	\$12,400.00	100%	\$12,400.00	0%	\$0.00	0%	\$0.00
188	Valve #188	100%	Lump Sum	\$14,900.00	\$14,900.00	100%	\$14,900.00	100%	\$14,900.00	100%	\$14,900.00	0%	\$0.00	0%	\$0.00
189	Valve #189	100%	Lump Sum	\$16,400.00	\$16,400.00	100%	\$16,400.00	100%	\$16,400.00	100%	\$16,400.00	0%	\$0.00	0%	\$0.00
190	Valve #190	100%	Lump Sum	\$16,400.00	\$16,400.00	100%	\$16,400.00	100%	\$16,400.00	100%	\$16,400.00	0%	\$0.00	0%	\$0.00
191	Valve #191	100%	Lump Sum	\$15,600.00	\$15,600.00	100%	\$15,600.00	100%	\$15,600.00	100%	\$15,600.00	0%	\$0.00	0%	\$0.00
192	Valve #192	100%	Lump Sum	\$15,100.00	\$15,100.00	100%	\$15,100.00	100%	\$15,100.00	100%	\$15,100.00	0%	\$0.00	0%	\$0.00
193	Valve #193	100%	Lump Sum	\$16,500.00	\$16,500.00	100%	\$16,500.00	100%	\$16,500.00	100%	\$16,500.00	0%	\$0.00	0%	\$0.00
194	Valve #194	100%	Lump Sum	\$16,500.00	\$16,500.00	100%	\$16,500.00	100%	\$16,500.00	100%	\$16,500.00	0%	\$0.00	0%	\$0.00
195	Valve #195	100%	Lump Sum	\$15,000.00	\$15,000.00	100%	\$15,000.00	100%	\$15,000.00	100%	\$15,000.00	0%	\$0.00	0%	\$0.00
196	Valve #196	100%	Lump Sum	\$15,100.00	\$15,100.00	100%	\$15,100.00	100%	\$15,100.00	100%	\$15,100.00	0%	\$0.00	0%	\$0.00
197	Valve #197	100%	Lump Sum	\$15,600.00	\$15,600.00	100%	\$15,600.00	100%	\$15,600.00	100%	\$15,600.00	0%	\$0.00	0%	\$0.00
198	Valve #198	100%	Lump Sum	\$11,800.00	\$11,800.00	100%	\$11,800.00	100%	\$11,800.00	100%	\$11,800.00	0%	\$0.00	0%	\$0.00
199	Valve #199	100%	Lump Sum	\$16,500.00	\$16,500.00	100%	\$16,500.00	100%	\$16,500.00	100%	\$16,500.00	0%	\$0.00	0%	\$0.00
200	Valve #200	100%	Lump Sum	\$16,500.00	\$16,500.00	100%	\$16,500.00	100%	\$16,500.00	100%	\$16,500.00	0%	\$0.00	0%	\$0.00
201	Valve #201	100%	Lump Sum	\$0.00	\$0.00	100%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$0.00
202	Valve #202	100%	Lump Sum	\$11,400.00	\$11,400.00	100%	\$11,400.00	100%	\$11,400.00	100%	\$11,400.00	0%	\$0.00	0%	\$0.00
203	Valve #203	100%	Lump Sum	\$16,000.00	\$16,000.00	100%	\$16,000.00	100%	\$16,000.00	100%	\$16,000.00	0%	\$0.00	0%	\$0.00
204	Valve #204	100%	Lump Sum	\$17,700.00	\$17,700.00	100%	\$17,700.00	100%	\$17,700.00	100%	\$17,700.00	0%	\$0.00	0%	\$0.00
205	Valve #205	100%	Lump Sum	\$17,200.00	\$17,200.00	100%	\$17,200.00	100%	\$17,200.00	100%	\$17,200.00	0%	\$0.00	0%	\$0.00
206	Valve #206	100%	Lump Sum	\$15,900.00	\$15,900.00	100%	\$15,900.00	100%	\$15,900.00	100%	\$15,900.00	0%	\$0.00	0%	\$0.00
207	Valve #207	100%	Lump Sum	\$15,200.00	\$15,200.00	100%	\$15,200.00	100%	\$15,200.00	100%	\$15,200.00	0%	\$0.00	0%	\$0.00
208	Valve #208	100%	Lump Sum	\$15,700.00	\$15,700.00	100%	\$15,700.00	100%	\$15,700.00	100%	\$15,700.00	0%	\$0.00	0%	\$0.00
209	Valve #209	100%	Lump Sum	\$17,200.00	\$17,200.00	100%	\$17,200.00	100%	\$17,200.00	100%	\$17,200.00	0%	\$0.00	0%	\$0.00
210	Valve #210	100%	Lump Sum	\$19,500.00	\$19,500.00	100%	\$19,500.00	100%	\$19,500.00	100%	\$19,500.00	0%	\$0.00	0%	\$0.00
211	Valve #211	100%	Lump Sum	\$16,000.00	\$16,000.00	100%	\$16,000.00	100%	\$16,000.00	100%	\$16,000.00	0%	\$0.00	0%	\$0.00
212	Valve #212	100%	Lump Sum	\$17,600.00	\$17,600.00	100%	\$17,600.00	100%	\$17,600.00	100%	\$17,600.00	0%	\$0.00	0%	\$0.00
213	Valve #213	100%	Lump Sum	\$16,400.00	\$16,400.00	100%	\$16,400.00	100%	\$16,400.00	100%	\$16,400.00	0%	\$0.00	0%	\$0.00
214	Valve #214	100%	Lump Sum	\$12,000.00	\$12,000.00	100%	\$12,000.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$12,000.00
215	Valve #215	100%	Lump Sum	\$15,000.00	\$15,000.00	100%	\$15,000.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$15,000.00
216	Valve #216	100%	Lump Sum	\$15,800.00	\$15,800.00	100%	\$15,800.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$15,800.00
217	Valve #217	100%	Lump Sum	\$16,300.00	\$16,300.00	100%	\$16,300.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$16,300.00
218	Valve #218	100%	Lump Sum	\$26,200.00	\$26,200.00	100%	\$26,200.00	100%	\$26,200.00	100%	\$26,200.00	0%	\$0.00	0%	\$0.00
219	Valve #219	100%	Lump Sum	\$15,400.00	\$15,400.00	100%	\$15,400.00	100%	\$15,400.00	100%	\$15,400.00	0%	\$0.00	0%	\$0.00
220	Valve #220	100%	Lump Sum	\$16,000.00	\$16,000.00	100%	\$16,000.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$16,000.00
221	Valve #221	100%	Lump Sum	\$15,400.00	\$15,400.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00
222	Valve #222	100%	Lump Sum	\$12,900.00	\$12,900.00	100%	\$12,900.00	100%	\$12,900.00	100%	\$12,900.00	0%	\$0.00	0%	\$0.00
223	Valve #223	100%	Lump Sum	\$16,800.00	\$16,800.00	100%	\$16,800.00	100%	\$16,800.00	100%	\$16,800.00	0%	\$0.00	0%	\$0.00
224	Valve #224	100%	Lump Sum	\$25,400.00	\$25,400.00	100%	\$25,400.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$25,400.00
225	Valve #225	100%	Lump Sum	\$15,700.00	\$15,700.00	100%	\$15,700.00	100%	\$15,700.00	100%	\$15,700.00	0%	\$0.00	0%	\$0.00
226	Valve #226	100%	Lump Sum	\$25,200.00	\$25,200.00	100%	\$25,200.00	100%	\$25,200.00	100%	\$25,200.00	0%	\$0.00	0%	\$0.00
227	Valve #227	100%	Lump Sum	\$12,400.00	\$12,400.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00
228	Valve #228	100%	Lump Sum	\$11,600.00	\$11,600.00	100%	\$11,600.00	100%	\$11,600.00	0%	\$0.00	100%	\$11,600.00	0%	\$0.00
229	Valve #229	100%	Lump Sum	\$11,500.00	\$11,500.00	100%	\$11,500.00	100%	\$11,500.00	0%	\$11,500.00	0%	\$0.00	0%	\$0.00
230	Valve #230	100%	Lump Sum	\$0.00	\$0.00	100%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$0.00
231	Valve #231	100%	Lump Sum	\$16,000.00	\$16,000.00	100%	\$16,000.00	100%	\$16,000.00	0%	\$0.00	100%	\$16,000.00	0%	\$0.00
232	Valve #232	100%	Lump Sum	\$15,400.00	\$15,400.00	100%	\$15,400.00	100%	\$15,400.00	0%	\$0.00	100%	\$15,400.00	0%	\$0.00
233	Valve #233	100%	Lump Sum	\$14,900.00	\$14,900.00	100%	\$14,900.00	100%	\$14,900.00	0%	\$14,900.00	0%	\$0.00	0%	\$0.00
234	Valve #234	100%	Lump Sum	\$16,700.00	\$16,700.00	100%	\$16,700.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$16,700.00
235	Valve #23														

BLOW OFF VALVE REPAIR (BOV-1)

DATE 03/30/04

ROSSI CONTRACTORS  
201 WEST LAKE STREET  
NORTHLAKE, ILLINOIS 60164

ACCOUNT # AMOUNT  
WF-6631 \$367,151.53  
WF-3520 (\$36,715.16)  
WF-3530 (\$780.00)

#	ITEM	ORIGINAL CONTRACT QUANTITY	UNIT	UNIT PRICE	ORIGINAL CONTRACT PRICE	AMENDED CONTRACT QUANTITY	AMENDED CONTRACT PRICE	CURRENT QUANTITY	TO DATE EXTENSION	PREVIOUS QUANTITY	PAYMENT EXTENSION	THIS QUANTITY	PAYMENT EXTENSION	CONTRACT QUANTITY	BALANCE EXTENSION
241	Valve #241	100%	Lump Sum	\$15,800.00	\$15,800.00	100%	\$15,800.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$15,800.00
242	Valve #242	100%	Lump Sum	\$16,400.00	\$16,400.00	100%	\$16,400.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$16,400.00
243	Valve #243	100%	Lump Sum	\$15,800.00	\$15,800.00	100%	\$15,800.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$15,800.00
244	Valve #244	100%	Lump Sum	\$0.00	\$0.00	100%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$0.00
245	Valve #245	100%	Lump Sum	\$0.00	\$0.00	100%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$0.00
246	Valve #246	100%	Lump Sum	\$25,400.00	\$25,400.00	100%	\$25,400.00	100%	\$25,400.00	100%	\$25,400.00	0%	\$0.00	0%	\$0.00
247	Valve #247	100%	Lump Sum	\$16,200.00	\$16,200.00	100%	\$16,200.00	100%	\$16,200.00	100%	\$16,200.00	0%	\$0.00	0%	\$0.00
248	Valve #248	100%	Lump Sum	\$16,900.00	\$16,900.00	100%	\$16,900.00	100%	\$16,900.00	100%	\$16,900.00	0%	\$0.00	0%	\$0.00
249	Valve #249	100%	Lump Sum	\$16,400.00	\$16,400.00	100%	\$16,400.00	100%	\$16,400.00	100%	\$16,400.00	0%	\$0.00	0%	\$0.00
250	Valve #250	100%	Lump Sum	\$0.00	\$0.00	100%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$0.00
251	Valve #251	100%	Lump Sum	\$12,500.00	\$12,500.00	100%	\$12,500.00	100%	\$12,500.00	100%	\$12,500.00	0%	\$0.00	0%	\$0.00
252	Valve #252	100%	Lump Sum	\$16,300.00	\$16,300.00	100%	\$16,300.00	70%	\$11,410.00	70%	\$11,410.00	0%	\$0.00	30%	\$4,890.00
253	Valve #253	100%	Lump Sum	\$15,100.00	\$15,100.00	100%	\$15,100.00	100%	\$15,100.00	100%	\$15,100.00	0%	\$0.00	0%	\$0.00
254	Valve #254	100%	Lump Sum	\$12,900.00	\$12,900.00	100%	\$12,900.00	100%	\$12,900.00	100%	\$12,900.00	0%	\$0.00	0%	\$0.00
255	Valve #255	100%	Lump Sum	\$47,600.00	\$47,600.00	100%	\$47,600.00	100%	\$47,600.00	100%	\$47,600.00	0%	\$0.00	0%	\$0.00
256	Valve #256	100%	Lump Sum	\$16,400.00	\$16,400.00	100%	\$16,400.00	100%	\$16,400.00	100%	\$16,400.00	0%	\$0.00	0%	\$0.00
257	Valve #257	100%	Lump Sum	\$16,400.00	\$16,400.00	100%	\$16,400.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$16,400.00
258	Valve #258	100%	Lump Sum	\$15,900.00	\$15,900.00	100%	\$15,900.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$15,900.00
259	Valve #259	100%	Lump Sum	\$15,300.00	\$15,300.00	100%	\$15,300.00	100%	\$15,300.00	100%	\$15,300.00	100%	\$0.00	0%	\$0.00
260	Valve #260	100%	Lump Sum	\$16,200.00	\$16,200.00	100%	\$16,200.00	100%	\$16,200.00	100%	\$16,200.00	0%	\$0.00	0%	\$0.00
261	Valve #261	100%	Lump Sum	\$16,000.00	\$16,000.00	100%	\$16,000.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$16,000.00
262	Valve #262	100%	Lump Sum	\$15,900.00	\$15,900.00	100%	\$15,900.00	100%	\$15,900.00	100%	\$15,900.00	0%	\$0.00	0%	\$0.00
263	Valve #263	100%	Lump Sum	\$17,000.00	\$17,000.00	100%	\$17,000.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$17,000.00
264	Valve #264	100%	Lump Sum	\$11,800.00	\$11,800.00	100%	\$11,800.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$11,800.00
265	Valve #265	100%	Lump Sum	\$16,200.00	\$16,200.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00
266	Valve #266	100%	Lump Sum	\$11,400.00	\$11,400.00	100%	\$11,400.00	100%	\$11,400.00	100%	\$11,400.00	0%	\$0.00	0%	\$0.00
267	Valve #267	100%	Lump Sum	\$12,100.00	\$12,100.00	100%	\$12,100.00	100%	\$12,100.00	100%	\$12,100.00	0%	\$0.00	0%	\$0.00
268	Valve #268	100%	Lump Sum	\$19,100.00	\$19,100.00	100%	\$19,100.00	100%	\$19,100.00	100%	\$19,100.00	100%	\$0.00	0%	\$0.00
269	Valve #269	100%	Lump Sum	\$29,200.00	\$29,200.00	100%	\$29,200.00	100%	\$29,200.00	100%	\$29,200.00	0%	\$0.00	0%	\$0.00
270	Valve #270	100%	Lump Sum	\$28,700.00	\$28,700.00	100%	\$28,700.00	100%	\$28,700.00	100%	\$28,700.00	0%	\$0.00	0%	\$0.00
271	Valve #271	100%	Lump Sum	\$15,600.00	\$15,600.00	100%	\$15,600.00	100%	\$15,600.00	100%	\$15,600.00	0%	\$0.00	0%	\$0.00
272	Valve #272	100%	Lump Sum	\$15,600.00	\$15,600.00	100%	\$15,600.00	100%	\$15,600.00	100%	\$15,600.00	0%	\$0.00	0%	\$0.00
273	Valve #273	100%	Lump Sum	\$17,400.00	\$17,400.00	100%	\$17,400.00	100%	\$17,400.00	100%	\$17,400.00	0%	\$0.00	0%	\$0.00
274	Valve #274	100%	Lump Sum	\$15,800.00	\$15,800.00	100%	\$15,800.00	100%	\$15,800.00	100%	\$15,800.00	0%	\$0.00	0%	\$0.00
275	Valve #275	100%	Lump Sum	\$25,900.00	\$25,900.00	100%	\$25,900.00	100%	\$25,900.00	100%	\$25,900.00	0%	\$0.00	0%	\$0.00
276	Valve #276	100%	Lump Sum	\$16,700.00	\$16,700.00	100%	\$16,700.00	100%	\$16,700.00	100%	\$16,700.00	0%	\$0.00	0%	\$0.00
277	Valve #277	100%	Lump Sum	\$0.00	\$0.00	100%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$0.00
278	Valve #278	100%	Lump Sum	\$15,800.00	\$15,800.00	100%	\$15,800.00	100%	\$15,800.00	100%	\$15,800.00	0%	\$0.00	0%	\$0.00
279	Valve #279	100%	Lump Sum	\$16,200.00	\$16,200.00	100%	\$16,200.00	100%	\$16,200.00	100%	\$16,200.00	0%	\$0.00	0%	\$0.00
280	Valve #280	100%	Lump Sum	\$19,300.00	\$19,300.00	100%	\$19,300.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$19,300.00
281	Valve #281	100%	Lump Sum	\$25,200.00	\$25,200.00	100%	\$25,200.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$25,200.00
282	Valve #282	100%	Lump Sum	\$14,400.00	\$14,400.00	100%	\$14,400.00	100%	\$14,400.00	100%	\$14,400.00	0%	\$0.00	0%	\$0.00
283	Valve #283	100%	Lump Sum	\$25,800.00	\$25,800.00	100%	\$25,800.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$25,800.00
284	Valve #284	100%	Lump Sum	\$25,400.00	\$25,400.00	100%	\$25,400.00	100%	\$25,400.00	100%	\$25,400.00	0%	\$0.00	0%	\$0.00
285	Valve #285	100%	Lump Sum	\$30,700.00	\$30,700.00	100%	\$30,700.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$30,700.00
286	Valve #286	100%	Lump Sum	\$12,500.00	\$12,500.00	100%	\$12,500.00	100%	\$12,500.00	100%	\$12,500.00	0%	\$0.00	0%	\$0.00
287	Valve #287	100%	Lump Sum	\$15,700.00	\$15,700.00	100%	\$15,700.00	100%	\$15,700.00	100%	\$15,700.00	0%	\$0.00	0%	\$0.00
288	Valve #288	100%	Lump Sum	\$16,600.00	\$16,600.00	100%	\$16,600.00	100%	\$16,600.00	100%	\$16,600.00	0%	\$0.00	0%	\$0.00
289	Valve #289	100%	Lump Sum	\$0.00	\$0.00	100%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$0.00
290	Valve #290	100%	Lump Sum	\$16,400.00	\$16,400.00	100%	\$16,400.00	100%	\$16,400.00	100%	\$16,400.00	0%	\$0.00	0%	\$0.00
291	Valve #291	100%	Lump Sum	\$19,700.00	\$19,700.00	100%	\$19,700.00	100%	\$19,700.00	100%	\$19,700.00	0%	\$0.00	0%	\$0.00
292	Valve #292	100%	Lump Sum	\$16,500.00	\$16,500.00	100%	\$16,500.00	100%	\$16,500.00	100%	\$16,500.00	0%	\$0.00	0%	\$0.00
293	Valve #293	100%	Lump Sum	\$16,400.00	\$16,400.00	100%	\$16,400.00	100%	\$16,400.00	100%	\$16,400.00	0%	\$0.00	0%	\$0.00
294	Valve #294	100%	Lump Sum	\$15,000.00	\$15,000.00	100%	\$15,000.00	100%	\$15,000.00	100%	\$15,000.00	0%	\$0.00	0%	\$0.00
295	Valve #295	100%	Lump Sum	\$16,100.00	\$16,100.00	100%	\$16,100.00	100%	\$16,100.00	100%	\$16,100.00	0%	\$0.00	0%	\$0.00
296	Valve #296	100%	Lump Sum	\$15,900.00	\$15,900.00	100%	\$15,900.00	100%	\$15,900.00	0%	\$0.00	100%	\$15,900.00	0%	\$0.00
297	Valve #297	100%	Lump Sum	\$16,100.00	\$16,100.00	100%	\$16,100.00	100%	\$16,100.00	100%	\$16,100.00	0%	\$0.00	0%	\$0.00
298	Valve #298	100%	Lump Sum	\$16,200.00	\$16,200.00	100%	\$16,200.00	100%	\$16,200.00	100%	\$16,200.00	0%	\$0.00	0%	\$0.00
299	Valve #299	100%	Lump Sum	\$16,400.00	\$16,400.00	100%	\$16,400.00	100%	\$16,400.00	100%	\$16,400.00	0%	\$0.00	0%	\$0.00
300	Valve #300	100%	Lump Sum	\$13,900.00	\$13,900.00	100%	\$13,900.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$13,900.00
301	Valve #301	100%	Lump Sum	\$15,600.00	\$15,600.00	100%	\$15,600.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$15,600.00
302	Valve #302	100%	Lump Sum	\$14,900.00	\$14,900.00	100%	\$14,900.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$14,900.00
303	Valve #303	100%	Lump Sum	\$14,800.00	\$14,800.00	100%	\$14,800.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$14,800.00
304	Valve #304														

## BLOW OFF VALVE REPAIR (BOV-1)

ROSSI CONTRACTORS  
201 WEST LAKE STREET  
NORTHLAKE, ILLINOIS 60164

DATE 03/30/04

ACCOUNT # AMOUNT  
WF-6631 \$367,151.53  
WF-3520 (\$36,715.16)  
WF-3530 (\$780.00)

#	ITEM	ORIGINAL CONTRACT QUANTITY	UNIT	UNIT PRICE	ORIGINAL CONTRACT PRICE	AMENDED CONTRACT QUANTITY	AMENDED CONTRACT PRICE	CURRENT QUANTITY	TO DATE EXTENSION	PREVIOUS QUANTITY	PAYMENT EXTENSION	THIS QUANTITY	PAYMENT EXTENSION	CONTRACT QUANTITY	BALANCE EXTENSION
321	Valve #321	100%	Lump Sum	\$13,300.00	\$13,300.00	100%	\$13,300.00	100%	\$13,300.00	100%	\$13,300.00	0%	\$0.00	0%	\$0.00
322	Valve #322	100%	Lump Sum	\$15,300.00	\$15,300.00	100%	\$15,300.00	100%	\$15,300.00	100%	\$15,300.00	0%	\$0.00	0%	\$0.00
323	Valve #323	100%	Lump Sum	\$13,100.00	\$13,100.00	100%	\$13,100.00	100%	\$13,100.00	100%	\$13,100.00	100%	\$0.00	0%	\$0.00
324	Valve #324	100%	Lump Sum	\$16,300.00	\$16,300.00	100%	\$16,300.00	100%	\$16,300.00	100%	\$16,300.00	100%	\$0.00	0%	\$0.00
325	Valve #325	100%	Lump Sum	\$16,800.00	\$16,800.00	100%	\$16,800.00	100%	\$16,800.00	100%	\$16,800.00	0%	\$0.00	0%	\$0.00
326	Valve #326	100%	Lump Sum	\$15,800.00	\$15,800.00	100%	\$15,800.00	100%	\$15,800.00	100%	\$15,800.00	100%	\$0.00	0%	\$0.00
327	Valve #327	100%	Lump Sum	\$16,400.00	\$16,400.00	100%	\$16,400.00	100%	\$16,400.00	100%	\$16,400.00	100%	\$0.00	0%	\$0.00
328	Valve #328	100%	Lump Sum	\$31,200.00	\$31,200.00	100%	\$31,200.00	100%	\$31,200.00	100%	\$31,200.00	100%	\$0.00	0%	\$0.00
329	Valve #329	100%	Lump Sum	\$11,800.00	\$11,800.00	100%	\$11,800.00	100%	\$11,800.00	100%	\$11,800.00	0%	\$0.00	0%	\$0.00
330	Valve #330	100%	Lump Sum	\$20,400.00	\$20,400.00	100%	\$20,400.00	100%	\$20,400.00	100%	\$20,400.00	100%	\$0.00	0%	\$0.00
331	Valve #331	100%	Lump Sum	\$15,500.00	\$15,500.00	100%	\$15,500.00	100%	\$15,500.00	100%	\$15,500.00	0%	\$0.00	0%	\$0.00
332	Valve #332	100%	Lump Sum	\$15,600.00	\$15,600.00	100%	\$15,600.00	100%	\$15,600.00	100%	\$15,600.00	0%	\$0.00	0%	\$0.00
333	Valve #333	100%	Lump Sum	\$12,300.00	\$12,300.00	100%	\$12,300.00	100%	\$12,300.00	100%	\$12,300.00	0%	\$0.00	0%	\$0.00
334	Valve #334	100%	Lump Sum	\$11,300.00	\$11,300.00	100%	\$11,300.00	100%	\$11,300.00	100%	\$11,300.00	0%	\$0.00	0%	\$0.00
335	Valve #335	100%	Lump Sum	\$16,300.00	\$16,300.00	100%	\$16,300.00	100%	\$16,300.00	100%	\$16,300.00	0%	\$0.00	0%	\$0.00
336	Valve #336	100%	Lump Sum	\$16,500.00	\$16,500.00	100%	\$16,500.00	100%	\$16,500.00	100%	\$16,500.00	0%	\$0.00	0%	\$0.00
337	Valve #337	100%	Lump Sum	\$16,100.00	\$16,100.00	100%	\$16,100.00	100%	\$16,100.00	100%	\$16,100.00	0%	\$0.00	0%	\$0.00
338	Valve #338	100%	Lump Sum	\$12,500.00	\$12,500.00	100%	\$12,500.00	100%	\$12,500.00	100%	\$12,500.00	0%	\$0.00	0%	\$0.00
339	Valve #339	100%	Lump Sum	\$16,200.00	\$16,200.00	100%	\$16,200.00	100%	\$16,200.00	100%	\$16,200.00	0%	\$0.00	0%	\$0.00
340	Valve #340	100%	Lump Sum	\$15,000.00	\$15,000.00	100%	\$15,000.00	100%	\$15,000.00	100%	\$15,000.00	0%	\$0.00	0%	\$0.00
341	Valve #341	100%	Lump Sum	\$24,800.00	\$24,800.00	100%	\$24,800.00	100%	\$24,800.00	100%	\$24,800.00	0%	\$0.00	0%	\$0.00
342	Valve #342	100%	Lump Sum	\$15,600.00	\$15,600.00	100%	\$15,600.00	100%	\$15,600.00	100%	\$15,600.00	0%	\$0.00	0%	\$0.00
343	Valve #343	100%	Lump Sum	\$13,000.00	\$13,000.00	100%	\$13,000.00	100%	\$13,000.00	100%	\$13,000.00	0%	\$0.00	0%	\$0.00
344	Valve #344	100%	Lump Sum	\$15,800.00	\$15,800.00	100%	\$15,800.00	100%	\$15,800.00	100%	\$15,800.00	0%	\$0.00	0%	\$0.00
345	Valve #345	100%	Lump Sum	\$11,600.00	\$11,600.00	100%	\$11,600.00	100%	\$11,600.00	100%	\$11,600.00	0%	\$0.00	0%	\$0.00
346	Valve #346	100%	Lump Sum	\$11,900.00	\$11,900.00	100%	\$11,900.00	100%	\$11,900.00	100%	\$11,900.00	0%	\$0.00	0%	\$0.00
347	Valve #347	100%	Lump Sum	\$21,200.00	\$21,200.00	100%	\$21,200.00	100%	\$21,200.00	100%	\$21,200.00	0%	\$0.00	0%	\$0.00
348	Valve #348	100%	Lump Sum	\$16,300.00	\$16,300.00	100%	\$16,300.00	100%	\$16,300.00	100%	\$16,300.00	0%	\$0.00	0%	\$0.00
349	Valve #349	100%	Lump Sum	\$28,700.00	\$28,700.00	100%	\$28,700.00	100%	\$28,700.00	100%	\$28,700.00	0%	\$0.00	0%	\$0.00
350	Valve #350	100%	Lump Sum	\$16,400.00	\$16,400.00	100%	\$16,400.00	100%	\$16,400.00	100%	\$16,400.00	0%	\$0.00	0%	\$0.00
351	Valve #351	100%	Lump Sum	\$16,100.00	\$16,100.00	100%	\$16,100.00	100%	\$16,100.00	100%	\$16,100.00	0%	\$0.00	0%	\$0.00
352	Valve #352	100%	Lump Sum	\$15,200.00	\$15,200.00	100%	\$15,200.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$15,200.00
353	Valve #353	100%	Lump Sum	\$16,100.00	\$16,100.00	100%	\$16,100.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$16,100.00
354	Valve #354	100%	Lump Sum	\$14,600.00	\$14,600.00	100%	\$14,600.00	100%	\$14,600.00	100%	\$14,600.00	0%	\$0.00	0%	\$0.00
355	Valve #355	100%	Lump Sum	\$36,300.00	\$36,300.00	100%	\$36,300.00	100%	\$36,300.00	100%	\$36,300.00	0%	\$0.00	0%	\$0.00
356	Valve #356	100%	Lump Sum	\$26,900.00	\$26,900.00	100%	\$26,900.00	100%	\$26,900.00	100%	\$26,900.00	0%	\$0.00	0%	\$0.00
357	Valve #357	100%	Lump Sum	\$15,800.00	\$15,800.00	100%	\$15,800.00	100%	\$15,800.00	100%	\$15,800.00	0%	\$0.00	0%	\$0.00
358	Valve #358	100%	Lump Sum	\$16,500.00	\$16,500.00	100%	\$16,500.00	100%	\$16,500.00	100%	\$16,500.00	0%	\$0.00	0%	\$0.00
359	Valve #359	100%	Lump Sum	\$15,500.00	\$15,500.00	100%	\$15,500.00	100%	\$15,500.00	100%	\$15,500.00	0%	\$0.00	0%	\$0.00
360	Valve #360	100%	Lump Sum	\$12,300.00	\$12,300.00	100%	\$12,300.00	100%	\$12,300.00	100%	\$12,300.00	0%	\$0.00	0%	\$0.00
361	Valve #361	100%	Lump Sum	\$16,300.00	\$16,300.00	100%	\$16,300.00	100%	\$16,300.00	100%	\$16,300.00	0%	\$0.00	0%	\$0.00
362	Valve #362	100%	Lump Sum	\$19,000.00	\$19,000.00	100%	\$19,000.00	100%	\$19,000.00	100%	\$19,000.00	0%	\$0.00	0%	\$0.00
363	Valve #363	100%	Lump Sum	\$0.00	\$0.00	100%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$0.00
364	Valve #364	100%	Lump Sum	\$15,900.00	\$15,900.00	100%	\$15,900.00	100%	\$15,900.00	100%	\$15,900.00	0%	\$0.00	0%	\$0.00
365	Valve #365	100%	Lump Sum	\$16,100.00	\$16,100.00	100%	\$16,100.00	100%	\$16,100.00	100%	\$16,100.00	0%	\$0.00	0%	\$0.00
366	Valve #366	100%	Lump Sum	\$28,400.00	\$28,400.00	100%	\$28,400.00	100%	\$28,400.00	100%	\$28,400.00	0%	\$0.00	0%	\$0.00
367	Valve #367	100%	Lump Sum	\$15,500.00	\$15,500.00	100%	\$15,500.00	100%	\$15,500.00	100%	\$15,500.00	0%	\$0.00	0%	\$0.00
368	Valve #368	100%	Lump Sum	\$0.00	\$0.00	100%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$0.00
369	Valve #369	100%	Lump Sum	\$12,900.00	\$12,900.00	100%	\$12,900.00	100%	\$12,900.00	100%	\$12,900.00	0%	\$0.00	0%	\$0.00
370	Valve #370	100%	Lump Sum	\$25,500.00	\$25,500.00	100%	\$25,500.00	100%	\$25,500.00	100%	\$25,500.00	0%	\$0.00	0%	\$0.00
371	Valve #371	100%	Lump Sum	\$11,900.00	\$11,900.00	100%	\$11,900.00	100%	\$11,900.00	100%	\$11,900.00	0%	\$0.00	0%	\$0.00
372	Valve #372	100%	Lump Sum	\$15,700.00	\$15,700.00	100%	\$15,700.00	100%	\$15,700.00	100%	\$15,700.00	0%	\$0.00	0%	\$0.00
373	Valve #373	100%	Lump Sum	\$20,600.00	\$20,600.00	100%	\$20,600.00	100%	\$20,600.00	100%	\$20,600.00	0%	\$0.00	0%	\$0.00
374	Valve #374	100%	Lump Sum	\$12,300.00	\$12,300.00	100%	\$12,300.00	100%	\$12,300.00	100%	\$12,300.00	0%	\$0.00	0%	\$0.00
375	Valve #375	100%	Lump Sum	\$11,900.00	\$11,900.00	100%	\$11,900.00	100%	\$11,900.00	100%	\$11,900.00	0%	\$0.00	0%	\$0.00
376	Valve #376	100%	Lump Sum	\$15,900.00	\$15,900.00	100%	\$15,900.00	100%	\$15,900.00	100%	\$15,900.00	0%	\$0.00	0%	\$0.00
377	Valve #377	100%	Lump Sum	\$26,100.00	\$26,100.00	100%	\$26,100.00	100%	\$26,100.00	100%	\$26,100.00	0%	\$0.00	0%	\$0.00
378	Valve #378	100%	Lump Sum	\$13,700.00	\$13,700.00	100%	\$13,700.00	100%	\$13,700.00	100%	\$13,700.00	0%	\$0.00	0%	\$0.00
379	Valve #379	100%	Lump Sum	\$17,200.00	\$17,200.00	100%	\$17,200.00	100%	\$17,200.00	100%	\$17,200.00	0%	\$0.00	0%	\$0.00
380	Valve #380	100%	Lump Sum	\$12,500.00	\$12,500.00	100%	\$12,500.00	100%	\$12,500.00	100%	\$12,500.00	0%	\$0.00	0%	\$0.00
381	Valve #381	100%	Lump Sum	\$47,900.00	\$47,900.00	100%	\$47,900.00	100%	\$47,900.00	100%	\$47,900.00	0%	\$0.00	0%	\$0.00
382	Valve #382	100%	Lump Sum	\$18,800.00	\$18,800.00	100%	\$18,800.00	100%	\$18,800.00	100%	\$18,800.00	0%	\$0.00	0%	\$0.00
383	Valve #383	100%	Lump Sum	\$12,600.00	\$12,600.00	100%	\$12,600.00	100%	\$12,600.00	100%	\$12,600.00	0%	\$0.00	0%	\$0.00
384	Valve #384	100%	Lump Sum	\$14,900.00	\$14,900.00	100%	\$14,900.00	100%	\$14,900.00	100%	\$14,900.00	0%	\$0.00	0%	\$0.00
385	Valve #385	100%	Lump Sum	\$13,300.00	\$13,300.00	100%	\$13,300.00	100%	\$13,300.00	100%	\$13,300.00	0%	\$0.00	0%	\$0.00
386	Valve #386	100%	Lump Sum	\$47,800.00	\$47,800.00	100%	\$47,800.00	100%	\$47,800.00	100%	\$47,800.00	0%	\$0.00	0%	\$0.00
387	Step 6 - Dewatering of Owner's Water Main	1,700,000	C.F.	\$0.18	\$306,000.00	1,700,000	\$306,000.00	276,013	\$49,682.34	276,013	\$49,682.34	0	\$0.00	1,423,987	\$256,317.66
388	Step 6 - Repair Exterior Leakage of Resilient Wedge Valve	35	EA.	\$2,048.00	\$71,680.00	35	\$71,680.00	37	\$75,776.00	37	\$75,776.00	0	\$0.00	(2)	(\$4,096.00)
389	Step 3 - Retirement of Resilient Wedge Valve	20	EA.	\$2,093.00	\$41,860.00	20	\$41,860.00	0	\$0.00	0	\$0.00	0	\$0.00	20	\$41,860.00
390	Step 7 - Remove and Replace 6" Resilient Wedge Valves	20	EA.	\$2,650.00	\$53,000.00	20	\$53,000.00	2	\$5,300.00	2	\$5,300.00	0	\$0.00	18	\$47,700.00
391	Step 7 - Remove and Replace 8" Resilient Wedge Valves	20	EA.	\$2,945.00	\$58,900.00	20	\$58,900.00	2	\$5,890.00	2	\$5,890.00	0	\$0.00	18	\$53,010.00
392	Step 7 - Remove and Replace 12" Resilient Wedge Valves	20	EA.	\$3,661.00	\$73,220.00	20	\$73,220.00	0	\$0.00	0	\$0.00	0	\$0.00	20	\$73,220.00
393	Step 5 - Remove and Replace Valve and Plug Joint Bolts	18	EA.	\$2,200.00	\$39,600.00	18	\$39,600.00	3	\$6,600.00	3	\$6,600.00	0	\$0.00	15	\$33,000.00

DU PAGE WATER COMMISSION  
BLOW OFF VALVE REPAIR (BOV-1)  
ROSSI CONTRACTORS  
201 WEST LAKE STREET  
NORTHLAKE, ILLINOIS 60164

PAYMENT # 20  
DATE 03/30/04  
ACCOUNT # AMOUNT  
WF-8831 \$367,151.53  
WF-3520 (\$36,715.18)  
WF-3530 (\$780.00)

#	ITEM	ORIGINAL CONTRACT QUANTITY	UNIT	UNIT PRICE	ORIGINAL CONTRACT PRICE	AMENDED CONTRACT QUANTITY	AMENDED CONTRACT PRICE	CURRENT QUANTITY	TO DATE EXTENSION	PREVIOUS QUANTITY	PAYMENT EXTENSION	THIS QUANTITY	PAYMENT EXTENSION	CONTRACT QUANTITY	BALANCE EXTENSION
394	Initial Anodes for Corrosion Control	965	EA.	\$1.00	\$965.00	965	\$965.00	709	\$709.00	664	\$664.00	45	\$45.00	256	\$256.00
395	Traffic Control and Protection	100%	Lump Sum	\$279,375.00	\$279,375.00	97%	\$271,483.00	87%	\$242,124.95	81%	\$225,119.52	6%	\$17,005.43	11%	\$29,358.05
396	Additional Anodes for Corrosion Control	60	EA.	\$1.00	\$60.00	60	\$60.00	0	\$0.00	0	\$0.00	0	\$0.00	60	\$60.00
397	Repair of Damage to exterior coating of prestress conc pipe	250	S.F.	\$230.00	\$57,500.00	250	\$57,500.00	31	\$7,222.00	31	\$7,222.00	0	\$0.00	219	\$50,278.00
I-1	Granular Foundation Material	1,000	C.Y.	\$30.80	\$30,800.00	1,000	\$30,800.00	0	\$0.00	0	\$0.00	0	\$0.00	1,000	\$30,800.00
I-2	Class "SI" Concrete	100	C.Y.	\$100.00	\$10,000.00	100	\$10,000.00	0	\$0.00	0	\$0.00	0	\$0.00	100	\$10,000.00
I-3	Class B Concrete	100	C.Y.	\$80.00	\$8,000.00	100	\$8,000.00	0	\$0.00	0	\$0.00	0	\$0.00	100	\$8,000.00
I-4	Extension Stem	70	EA.	\$342.00	\$23,940.00	70	\$23,940.00	70	\$23,940.00	70	\$23,940.00	0	\$0.00	0	\$0.00
I-5	Valve Box with Cover	15	EA.	\$469.00	\$7,035.00	15	\$7,035.00	15	\$7,035.00	15	\$7,035.00	0	\$0.00	0	\$0.00
I-6	Valve Box Cover	50	EA.	\$100.00	\$5,000.00	50	\$5,000.00	2	\$200.00	2	\$200.00	0	\$0.00	48	\$4,800.00
I-7	Pavement, remove & replace—portland cement concrete surface	15	S.Y.	\$200.00	\$3,000.00	15	\$3,000.00	6	\$1,155.56	6	\$1,155.56	0	\$0.00	9	\$1,844.44
I-8	Pavement, remove & replace—bituminous concrete surface—Rigid Base	15	S.Y.	\$100.00	\$1,500.00	15	\$1,500.00	0	\$0.00	0	\$0.00	0	\$0.00	15	\$1,500.00
I-9	Pavement, remove & replace—bituminous concrete surface—Flexible Base (B.A.M.)	15	S.Y.	\$100.00	\$1,500.00	15	\$1,500.00	0	\$0.00	0	\$0.00	0	\$0.00	15	\$1,500.00
I-10	Pavement, remove & replace—bituminous concrete surface—Flexible Base (Aggregate)	15	S.Y.	\$100.00	\$1,500.00	15	\$1,500.00	0	\$0.00	0	\$0.00	0	\$0.00	15	\$1,500.00
CO 1	Extra lead wire	0	L.F.	\$2.00	\$0.00	354	\$708.00	299	\$598.00	278	\$556.00	21	\$42.00	55	\$110.00
CO 1	Silicone around junction box and installation of box into frame and lid	0	L.F.	\$3.00	\$0.00	354	\$1,062.00	299	\$897.00	278	\$834.00	21	\$63.00	55	\$165.00
CO 2	Additional valve boxes	0	EA.	\$469.00	\$0.00	100	\$46,900.00	100	\$46,900.00	100	\$46,900.00	0	\$0.00	0	\$0.00
CO 3	Delete valves #6, 12, 100, 101, 116, 123, 126, 221, 227 and delete 9 of 354 traffic control sites					Items 6, 12, 100, 101, 116, 123, 126, 221, 227, and 395 adjusted above									
CO 4	Additional Valve Boxes and Covers	0	EA.	\$469.00	\$0.00	100	\$46,900.00	22	\$10,318.00	15	\$7,035.00	7	\$3,283.00	78	\$36,582.00
CO 4	Additional Valve Stems	0	EA.	\$342.00	\$0.00	100	\$34,200.00	37	\$12,654.00	23	\$7,868.00	14	\$4,788.00	63	\$21,546.00
CO 5	Repair 16" Conc. Pipe; Site #259	0%	Lump Sum	\$4,841.30	\$0.00	100%	\$4,841.30	1	\$4,841.30	1	\$4,841.30	0	\$0.00	0	\$0.00
CO 6	Delete valves #49, 117, 265, 87 and 1 Traffic Control Site.					Items 49, 117, 265, 87, and 395 adjusted above									
CO 6	Valve #387	0%	Lump Sum	\$18,400.00	\$0.00	100%	\$18,400.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$18,400.00
CO 6	Valve #388	0%	Lump Sum	\$24,500.00	\$0.00	100%	\$24,500.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$24,500.00
CO 6	Valve #389	0%	Lump Sum	\$27,900.00	\$0.00	100%	\$27,900.00	100%	\$27,900.00	100%	\$27,900.00	0%	\$0.00	0%	\$0.00
CO 7	Site #129 PipeTape Repair	0%	Lump Sum	\$9,359.24	\$0.00	100%	\$9,359.24	100%	\$9,359.24	0%	\$0.00	100%	\$9,359.24	0%	\$0.00
CO 8	Site #148 PipeTape Repair	0%	Lump Sum	\$5,765.86	\$0.00	100%	\$5,765.86	100%	\$5,765.86	0%	\$0.00	100%	\$5,765.86	0%	\$0.00
CO 9	Step 6 - Repair Exterior Leakage of Resilient Wedge Valve	0%	Lump Sum	\$20,480.00	\$0.00	100%	\$20,480.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$20,480.00

## DU PAGE WATER COMMISSION

INSTALLATION OF CATHODIC PROTECTION STATION - DOWNERS GROVE (QR6-004A)

ACCT. # WF-6631

ROSSI CONTRACTORS

201 WEST LAKE STREET

NORTHLAKE, IL 60164

	THU 11/20/03	FRI 11/21/03	HOURS UNITS	RATE	EXTENTION	FEE	AMOUNT
<b>LABOR</b>							
LABOR FOREMAN - (N. D'ANDREA)	8.00	8.00	16.00	37.89	606.24		
LABOR FOREMAN - OT (N. D'ANDREA)	0.50	0.50	1.00	52.89	52.89		
OPERATOR CLASS 1 - (N. MORSELLO)	8.00	8.00	16.00	46.63	746.08		
OPERATOR CLASS 1 - OT (N. MORSELLO)	0.50	0.50	1.00	63.58	63.58		
BOTTOM LABOR - (ISAC ZEPEDA)	8.00	8.00	16.00	37.24	595.84		
BOTTOM LABOR - OT (ISAC ZEPEDA)	1.00	0.50	1.50	51.92	77.88		
TOP LABOR - (IGNACIO ZEPEDA)	8.00	8.00	16.00	36.89	590.24		
TOP LABOR - OT (I. ZEPEDA)	1.00	0.50	1.50	51.39	77.09		
TRUCK DRIVER - (C. MORAVEC)	8.00	8.00	16.00	34.75	556.00		
TRUCK DRIVER - OT (C. MORAVEC)		1.00	1.00	48.43	48.43		
					<u>3,414.27</u>	40.00%	4,779.98
<b>SUPPLIES</b>							
R & R MATERIALS - TICKET # 24273 & 24274		320.00			320.00		
R & R MATERIALS - TICKET # 24272		100.00			100.00		
R & R MATERIALS - INVOICE # 40762		873.00			873.00		
					0.00		
					0.00		
					0.00		
					0.00		
					<u>1,293.00</u>	10.00%	1,422.30
<b>EQUIPMENT</b>							
446B BACKHOE	8.50	9.00	17.50	44.01	770.18		
SERVICE PICKUP 3/4 T	8.50	8.50	17.00	8.23	139.91		
SEMI TRACTOR 6X4 GVW 75,000	4.00	11.50	15.50	44.77	693.94		
DUMP TRUCK - 1 TON	9.00	9.00	18.00	19.65	353.70		
TRAILER DUMP		8.00	8.00	16.02	128.16		
LOWBOY TRAILER - 50T	4.00	3.50	7.50	15.52	116.40		
TRAFFIC PLATES - 1"X4'X14'		8.00	8.00	12.50	100.00		
BRACES		32.00	32.00	0.00	0.00		
					<u>2,302.29</u>	10.00%	2,532.52
							<u>8,734.80</u>

CONFIRMED

BY: ELK DATE: 4-2-04

ACCT #: WF-6631 AMT: 8,734.80

ACCT #:           

APPROVED



# **DuPage Water Commission**

## **MEMORANDUM**

**TO:** Commissioner Benson

**FROM:** Supervisor of Pipeline Maintenance and Construction

**DATE:** April 2 2004

**SUBJECT:** Contract BOV-1 Change Orders 7 and 8.

During the prosecution of the contract repair work for the valves located at site numbers 129, 75th Street and Woodridge Drive, and 148, Naperville Road and Butterfield Road, it was discovered that the integrity of the existing tape coating in the vicinity of the valves being repaired had been compromised. Specifically, the tape coating in these areas exhibited some signs of tearing, and in some areas, lack of adhesion to the pipe.

In order to mitigate the potential for corrosion to occur, a decision was made in the field to remove the questionable areas of the existing tape coating down to pipe, clean and prep the pipe, and apply 3 new layers of tape.

To clarify the reason for the work performed under these change orders; this work was not performed as a result of an absence of tape coating, but rather to repair existing tape coating, which if left in the condition it was discovered, may in time have contributed to the failure of the pipe.