



DuPage Water Commission

600 E. Butterfield Road, Elmhurst, IL 60126-4642
(630)834-0100 Fax: (630)834-0120

NOTICE IS HEREBY GIVEN THAT THE RESCHEDULED AUGUST 2004 ENGINEERING COMMITTEE MEETING OF THE DUPAGE WATER COMMISSION WILL BE HELD AT 8:30 A.M. ON THURSDAY, AUGUST 12, 2004, AT ITS OFFICES LISTED BELOW. THE AGENDA FOR THE RESCHEDULED AUGUST 2004 REGULAR COMMITTEE MEETING IS AS FOLLOWS:

AGENDA

**ENGINEERING COMMITTEE
THURSDAY, AUGUST 12, 2004
8:30 A.M.**

**600 EAST BUTTERFIELD ROAD
ELMHURST, IL 60126**

COMMITTEE MEMBERS

G. Wilcox, Chair
R. Benson
W. Mueller
R. Ferraro

- I. Roll Call
- II. Approval of Minutes for Committee Meeting of July 8, 2004
- III. Report of Status of Construction/Operations
- IV. Partial Pay Request
 - A. Progress Payment No. 24: Contract BOV-1 (Blow Off Valve Repair)
 - B. Progress Payment No. 4: Contract TIB-1 (Inner Belt Transmission Main)
 - C. Progress Payment No. 37: Contract TW-2 (West Transmission Main)
 - D. Quick Response Contract
 - 1. QR6-005A Installation of Cathodic Protection Station – Westmont
 - 2. QR6-007A Water Main Repair – 897 North President St., Carol Stream
 - 3. QR6-007B Water Main Repair – 897 North President St., Carol Stream
 - 4. QR6-008A CP Station Installation – Plainfield Rd. @ Crest Ave., Darien
 - 5. QR6-008B CP Repair – 75th St. @ Naper Blvd., Naperville
 - 6. QR6-009A 8" Blow Off Valve Repair – Naperville

All visitors must present a valid drivers license or other government-issued photo identification, sign in at the reception area and wear a visitor badge while at the DuPage Pumping Station.

- V. Resolution R-40-04: A Resolution Approving and Ratifying Certain Work Authorization Orders Under Quick Response Electrical Contract QRE-1/02 at the August 12, 2004 DuPage Water Commission Meeting
- VI. Resolution R-41-04: A Resolution Approving and Authorizing the Execution of an Eighth Amendment to the Amended and Restated Agreement for Engineering Services
- VII. Resolution R-43-04: A Resolution Approving and Ratifying Certain Work Authorization Orders under Quick Response Contract QR-6/02 at the August 12, 2004, DuPage Water Commission Meeting
- VIII. Resolution R-44-04: A Resolution Approving and Ratifying Certain Task Orders Under a Master Engineering Agreement with Alvord, Burdick & Howson, L.L.C. at the August 12, 2004, DuPage Water Commission Meeting
- IX. Resolution R-45-04: A Resolution Approving and Ratifying Certain Contract Change Orders at the August 12, 2004, DuPage Water Commission Meeting
- X. Other
- XI. Adjournment

**MINUTES OF A MEETING OF THE
ENGINEERING & CONSTRUCTION COMMITTEE
OF THE DU PAGE WATER COMMISSION
HELD ON JULY 8, 2004
600 EAST BUTTERFIELD ROAD
ELMHURST, ILLINOIS**

The meeting was called to order at 8:30 A.M.

Committee members in attendance: R. Benson, R. Ferraro, and W. Mueller

Committee members absent: G. Wilcox

Also in attendance: M. Vondra (*ex officio*), R. Martin and R. Shea (AB&H)

Commissioner Benson moved that the Minutes of the June 10, 2004 Engineering Committee be approved. Motion seconded by Commissioner Ferraro and passed unanimously as follows:

Aye: R. Benson, R. Ferraro and W. Mueller
Nay: None

The Committee reviewed the memorandum regarding the Status of Operations dated July 2, 2004.

Commissioner Wilcox arrived at 8:40 A.M.

Commissioner Benson moved to recommend to the Commission approval of the change orders and recommend approval of Resolution Nos. R-34-04 and R-36-04 during the Omnibus Vote Agenda.

- A. Change Order No. 10: Contract BOV-1 (Blow Off Valve Repair) in the credit amount of \$30,678.40
- B. Change Order No. 11: Contract BOV-1 (Blow Off Valve Repair) in the amount of \$18,419.00
- C. Change Order No. 12: Contract BOV-1 (Blow Off Valve Repair) in the amount of \$10,000.00
- D. Change Order No. 13: Contract BOV-1 (Blow Off Valve Repair) in the amount of \$1,594,200.00
- E. Change Order No. 6: Contract TIB-1 (Inner Belt Transmission Main) in the amount of \$299,625.00

Minutes 7/8/04 Engineering Meeting

Motion seconded by Commissioner Ferraro and passed unanimously as follows:

Aye: R. Benson, R. Ferraro, W. Mueller and G. Wilcox
Nay: None

Commissioner Benson moved to recommend to the Commission approval of the following progress payments in the amount of \$716,547.28 as part of the Accounts Payable, subject to submission of all contractually required documentation.

- A. Progress Payment No. 23: Contract BOV-1 (Blow Off Valve Repair) in the amount of \$88,813.83
- B. Progress Payment No. 3: Contract TIB-1 (Inner Belt Transmission Main) in the amount of \$627,733.45

Motion seconded by Commissioner Mueller and passed unanimously as follows:

Aye: R. Benson, R. Ferraro, W. Mueller and G. Wilcox
Nay: None

Commissioner Benson moved to recommend to the Commission the reduction in retention for Contract TSW-3 and approval of progress payment number 27 for Contract TSW-3 in the amount of \$105,900.00 as part of the Accounts Payable, subject to submission of all contractually required documentation.

Progress Payment No. 27: Contract TSW-3 (Southwest Transmission Main) in the amount of \$105,900.00

Motion seconded by Commissioner Mueller and passed unanimously as follows:

Aye: R. Benson, R. Ferraro, W. Mueller and G. Wilcox
Nay: None

Commissioner Mueller moved to recommend to the Commission approval of Resolution R-37-04: A Resolution Approving and Ratifying Certain Task Orders Under a Master Contract with Consoer Townsend Envirodyne Engineers, Inc. at the July 8, 2004 DuPage Water Commission Meeting. Motion seconded by Commissioner Benson and passed unanimously as follows:

Aye: R. Benson, R. Ferraro, W. Mueller and G. Wilcox
Nay: None

Minutes 7/8/04 Engineering Meeting

The Committee discussed the Darien Drainage Issue. General Manager Martin indicated that a report was prepared and distributed. He was going to have a meeting with various parties involved (Darien, DuPage County, Alvord, Burdick & Howson and Southwind Financial – formerly known as Abbott Contractors). Commissioner Mueller moved to recommend to the Commission to authorize the General Manager to engage an engineering firm to prepare plans and specifications for the relocation of the Commission's transmission main if such engineering services are needed and bring the associated work task order and/or work authorization order under Contract QR-6 to the August Commission meeting for approval. Motion seconded by Commissioner Benson and passed unanimously as follows:

Aye: R. Benson, R. Ferraro, W. Mueller and G. Wilcox
Nay: None

Commissioner Mueller moved to adjourn the meeting at 9:05 P.M. Seconded by Commissioner Benson and unanimously approved by a Voice Vote.

All voted aye. Motion carried.



DuPage Water Commission

MEMORANDUM

TO: Engineering Committee

FROM: Robert L. Martin, P.E.
General Manager

DATE: August 6, 2004

SUBJECT: Status of Operations

Operations Overview

The Commission's sales for the month of July were a total of 3.132 billion gallons. This represents an average day of 101.0 million gallons per day (MGD), which is lower than the July 2003 average day demand of 123.2 MGD. The maximum day demand was 119.1 million gallons (July 29, 2004), which is lower than the July 2003 maximum day of 140.6 million gallons. The minimum day flow was 83.0 million gallons. The Commission recorded a total precipitation for the month of July of 2.33 inches compared to 3.38 inches for July 2003.

Operations Construction Overview

Contract PSD-6 Reservoir Addition

Consoer Townsend Envirodyne (CTE) is in the design phase of the project. Staff is reviewing the 90% design plans and specifications. The design period is 180 days from March 22, 2004, with expected completion on September 18, 2004.

Contract PSD-7 DPPS Electrical Generation

Camp Dresser McKee (CDM) is in the design phase of the project. Staff is working with CDM in finalizing design requirements. The design period is 32 weeks with a completion expected December 24, 2004.

Remote Pipe Storage Facility

CTE continues with the design of this facility. Staff is reviewing the 90% design plans and specifications.

Pipeline Construction Overview**Contract TSW-3/98 Southwest Transmission Main**

Minor restoration and miscellaneous electrical work at the Butterfield and Winfield Road ROV are all that remain to be completed under this contract.

Lost Time Accidents to Date 08/06/04 0 Days

Contract TW-2/00 West Transmission Main

Contractor is working on punch list items and is submitting documentation as required by contract for project acceptance and close out.

Lost Time Accidents to Date 08/06/04 0 Days

Contract BOV-1/02 Blow-Off Valve Improvements

Punch list work and the abandonment of one valve are all that remain to be completed under this contract. A Task Order to initiate design work for the repair of the valves located on the 90" transmission main appears on the agenda as R-44.

Lost Time Accidents to Date 08/06/04 0 Days

Contract TIB-1/03 Inner Belt Transmission Main

Tunnel boring at the Elmhurst WWTP has progressed approximately 1000 feet. Receiving shaft has been excavated 45 feet down to rock. Blasting at this location began on July 29 and is expected to take about 8 days to complete. Roosevelt Road casing installation has progressed approximately 130 feet. No additional casing has been installed at Roosevelt Road since the evening of June 29. When, during tunnel excavation, the contractor experienced a significant surge of water into the tunnel. Site monitoring and efforts to control the entry of water into the tunnel through the installation of deep wells have continued since that time. Additional efforts to stabilize and thereby prevent pavement failure of Roosevelt Road have been successful. The remaining 30 feet of casing pipe will be installed by means of open cutting across Roosevelt Road, once it has been determined that the water level has dropped sufficiently enough to proceed. West Shore Pipeline began relocation work on July 22. BP Amoco is expected to begin relocation work around mid September.

Lost Time Accidents to Date 08/06/04 0 Days

Contract QR-6

Installation of the tee connection at Butterfield Road and Majestic Ave has been completed. This installation will eventually become part of the feeder main to proposed meter station 14 E. A should be restored August 4.

Contract CP-3

Cathodic Protection Management, Together with field assistance provided by pipeline personnel are continuing to investigate, assess and identify corrosion potentials of Commission owned facilities.

The following are attachments to this memorandum:

1. DuPage Laboratory Bench Sheet for July, 2004
2. Water Sales Analysis 01-May-01 to 31-July-04
3. Chart showing Commission sales versus allocations
4. Chart showing Commission sales versus historical averages

DUPAGE WATER COMMISSION LABORATORY BENCH SHEET
MONTHLY REPORT FOR JULY 2004

LEXINGTON SUPPLY

DUPAGE DISCHARGE

DAY	FREE CL ₂ mg/l	TURBIDITY NTU	PO ₄ mg/l	FREE CL ₂ mg/l	TURBIDITY NTU	TEMP °F	pH	Fluoride mg/l	PO ₄ mg/l	P.A.C. LBS/MG	ANALYST INT
1	0.64	0.11	0.51	0.72	0.08	67	7.5	1.1	0.50	0	LS
2	0.65	0.10	0.51	0.72	0.08	67	7.5	1.1	0.50	0	CT
3	0.64	0.10	0.51	0.72	0.09	67	7.4	1.1	0.48	0	CT
4	0.62	0.10	0.48	0.71	0.09	67	7.5	1.0	0.47	0	LS
5	0.65	0.10	0.47	0.73	0.09	66	7.5	1.0	0.47	0	LS
6	0.66	0.11	0.49	0.71	0.09	67	7.5	1.0	0.47	0	LS
7	0.67	0.11	0.51	0.71	0.10	67	7.5	1.1	0.45	0	LS
8	0.68	0.11	0.48	0.70	0.10	67	7.5	1.1	0.46	0	LS
9	0.68	0.09	0.48	0.71	0.10	67	7.5	1.1	0.45	0	MB
10	0.67	0.09	0.48	0.72	0.07	68	7.4	1.1	0.47	0	MB
11	0.66	0.10	0.50	0.73	0.07	68	7.5	1.0	0.48	0	MB
12	0.65	0.10	0.51	0.75	0.08	68	7.5	1.0	0.50	0	MB
13	0.64	0.11	0.51	0.75	0.08	69	7.5	1.0	0.47	0	LS
14	0.67	0.12	0.51	0.74	0.10	70	7.5	1.0	0.48	0	LS
15	0.65	0.12	0.51	0.74	0.10	70	7.5	1.1	0.45	0	LS
16	0.65	0.11	0.47	0.75	0.10	70	7.5	1.1	0.45	0	LS
17	0.65	0.11	0.51	0.72	0.09	70	7.4	1.2	0.48	0	MB
18	0.66	0.11	0.58	0.72	0.10	70	7.5	1.0	0.47	0	MB
19	0.67	0.10	0.51	0.75	0.11	70	7.5	1.1	0.50	0	MB
20	0.68	0.10	0.51	0.74	0.09	70	7.4	1.0	0.50	0	MB
21	0.68	0.10	0.54	0.74	0.09	71	7.4	1.0	0.50	0	LS
22	0.67	0.08	0.51	0.74	0.09	72	7.4	1.0	0.48	0	LS
23	0.64	0.09	0.51	0.70	0.08	72	7.4	1.0	0.48	0	LS
24	0.64	0.10	0.48	0.74	0.08	72	7.4	1.1	0.49	0	Kd
25	0.67	0.10	0.48	0.71	0.08	72	7.4	0.9	0.51	0	Kd
26	0.52	0.08	0.48	0.68	0.08	72	7.4	0.9	0.47	0	Kd
27	0.61	0.08	0.49	0.74	0.10	72	7.4	0.9	0.47	0	Kd
28	0.52	0.09	0.51	0.74	0.10	72	7.4	0.9	0.48	0	Kd
29	0.67	0.09	0.51	0.78	0.08	73	7.4	1.0	0.48	0	JV
30	0.67	0.09	0.51	0.79	0.08	74	7.4	1.0	0.45	0	JV
31	0.67	0.09	0.50	0.79	0.07	71	7.6	1.0	0.46	0	JV
AVG	0.65	0.10	0.50	0.73	0.09	70	7.5	1.0	0.48	0	
MAX	0.68	0.12	0.58	0.79	0.11	74	7.6	1.2	0.51	0	
MIN	0.52	0.08	0.47	0.68	0.07	66	7.4	0.9	0.45	0	



Terrance McGhee
Operations Supervisor



Robert L. Martin
General Manager

DU PAGE WATER COMMISSION
WATER SALES ANALYSIS

01-May-92 TO 31-Jul-04


PER DAY AVERAGE 80,927,350

MONTH	SALES TO CUSTOMERS (GALLONS)	PURCHASES FROM CHICAGO (GALLONS)	GALLONS BILLED %	BILLINGS TO CUSTOMERS	BILLINGS FROM CHICAGO	DOCUMENTED COMMISSION WATER USE (2)	DOCUMENTED COMMISSION WATER USE %	TOTAL ACCOUNTED FOR %
May-01	2,679,850,000	2,792,321,195	95.97%	\$3,564,200.50	\$3,155,322.95	12,320,840	0.44%	96.41%
Jun-01	2,944,352,000	3,026,438,540	97.29%	\$3,915,988.16	\$3,419,875.55	10,068,050	0.33%	97.62%
Jul-01	3,729,441,000	3,839,156,549	97.14%	\$4,960,156.53	\$4,338,246.90	2,171,700	0.06%	97.20%
Aug-01	3,217,436,000	3,265,655,796	98.52%	\$4,279,189.88	\$3,690,191.05	1,156,800	0.04%	98.56%
Sep-01	2,552,219,000	2,639,772,522	96.68%	\$3,394,451.27	\$2,982,942.95	7,064,124	0.27%	96.95%
Oct-01	2,382,399,000	2,441,347,080	97.59%	\$3,168,590.67	\$2,758,722.20	7,511,120	0.31%	97.89%
Nov-01	2,212,776,000	2,246,511,018	98.50%	\$2,942,992.08	\$2,538,557.45	7,110,473	0.32%	98.81%
Dec-01	2,289,859,000	2,319,285,708	98.73%	\$3,045,512.47	\$2,620,792.85	917,200	0.04%	98.77%
Jan-02	2,320,798,000	2,351,613,013	98.69%	\$3,086,661.34	\$2,763,145.29	1,017,300	0.04%	98.73%
Feb-02	2,101,092,000	2,140,899,881	98.14%	\$2,794,452.36	\$2,515,557.36	1,134,300	0.05%	98.19%
Mar-02	2,282,553,000	2,369,611,940	96.33%	\$3,035,795.49	\$2,784,293.72	18,554,160	0.78%	97.11%
Apr-02	2,279,744,000	2,353,213,915	96.88%	\$3,032,059.52	\$2,765,026.04	1,118,700	0.05%	96.93%
May-02	2,530,549,000	2,620,422,434	96.57%	\$3,390,935.66	\$3,078,996.36	10,740,300	0.41%	96.98%
Jun-02	2,974,993,000	3,064,246,366	97.09%	\$3,986,490.62	\$3,600,489.48	2,949,188	0.10%	97.18%
Jul-02	3,818,677,000	3,928,688,630	97.20%	\$5,117,027.18	\$4,616,209.14	1,407,000	0.04%	97.24%
Aug-02	3,243,485,000	3,347,860,391	96.88%	\$4,346,269.90	\$3,933,735.96	1,155,200	0.03%	96.92%
Sep-02	2,941,334,000	3,026,340,894	97.19%	\$3,941,387.56	\$3,555,950.55	1,130,900	0.04%	97.23%
Oct-02	2,515,785,000	2,551,823,030	98.59%	\$3,371,216.38	\$2,998,392.06	1,354,600	0.05%	98.64%
Nov-02	2,264,094,000	2,328,010,928	97.25%	\$3,034,011.20	\$2,735,412.84	811,900	0.03%	97.29%
Dec-02	2,384,875,000	2,439,819,728	97.75%	\$3,195,844.10	\$2,866,788.18	885,300	0.04%	97.78%
Jan-03	2,430,849,000	2,496,371,382	97.38%	\$3,257,685.17	\$3,053,062.20	751,400	0.03%	97.41%
Feb-03	2,166,550,000	2,216,028,831	97.77%	\$2,903,280.54	\$2,710,203.26	919,100	0.04%	97.81%
Mar-03	2,347,318,000	2,412,660,360	97.29%	\$3,145,477.42	\$2,950,683.62	835,700	0.03%	97.33%
Apr-03	2,338,518,000	2,401,856,926	97.36%	\$3,133,682.63	\$2,937,471.02	12,052,576	0.50%	97.86%
May-03	2,622,301,000	2,711,004,309	96.73%	\$3,619,032.96	\$3,315,558.27	3,119,550	0.12%	96.84%
Jun-03	3,031,274,000	3,129,263,410	96.87%	\$4,183,476.12	\$3,827,089.15	9,583,535	0.31%	97.17%
Jul-03	3,114,181,000	3,213,079,828	96.92%	\$4,297,569.78	\$3,929,596.63	3,414,287	0.11%	97.03%
Aug-03	3,137,669,000	3,237,477,343	96.92%	\$4,330,318.18	\$3,959,434.79	6,589,500	0.20%	97.12%
Sep-03	2,775,903,000	2,842,321,431	97.66%	\$3,830,750.38	\$3,476,159.11	1,081,000	0.04%	97.70%
Oct-03	2,463,017,000	2,531,079,199	97.31%	\$3,361,577.64	\$3,095,509.86	1,199,100	0.05%	97.36%
Nov-03	2,220,837,000	2,263,237,760	98.13%	\$3,110,603.92	\$2,767,939.78	1,004,600	0.04%	98.17%
Dec-03	2,302,995,000	2,357,446,124	97.69%	\$3,178,138.40	\$2,883,156.61	785,500	0.03%	97.72%
Jan-04	2,353,099,000	2,415,231,136	97.43%	\$3,247,276.62	\$3,040,776.00	999,500	0.04%	97.47%
Feb-04	2,205,542,000	2,253,789,245	97.86%	\$3,043,647.96	\$2,837,520.66	799,100	0.04%	97.89%
Mar-04	2,240,813,000	2,290,496,569	97.83%	\$3,092,321.94	\$2,883,735.18	883,800	0.04%	97.87%
Apr-04	2,331,090,000	2,380,618,809	97.92%	\$3,218,939.40	\$2,997,199.08	875,000	0.04%	97.96%
May-04	2,600,130,000	2,676,783,908	97.14%	\$3,718,185.90	\$3,370,070.94	1,031,900	0.04%	97.17%
Jun-04	2,721,721,000	2,789,008,356	97.59%	\$3,892,371.69	\$3,511,361.52	1,285,000	0.05%	97.63%
Jul-04	3,133,397,000	3,223,301,033	97.21%	\$4,480,757.71	\$4,058,136.00	4,645,300	0.14%	97.35%
TOTALS (1)	362,149,889,000	373,076,949,284	97.07%	\$485,065,157.78	\$399,706,582.61	277,769,591	0.07%	97.15%


(1) - SINCE MAY 1, 1992

(2) - REPRESENTS DU PAGE PUMP STATION, METER TESTING AND CONSTRUCTION PROJECT USAGE

**DU PAGE WATER COMMISSION SALES
FY 2004-05 & FY 2003-04 VS. HISTORICAL AVERAGE**



**DU PAGE WATER COMMISSION SALES
FY 2004-05 VS. ALLOCATION**



DU PAGE WATER COMMISSION

PAYMENT # 24

BLOW OFF VALVE REPAIR (BOV-1)

DATE 07/30/04

ROSSI CONTRACTORS
201 WEST LAKE STREET
NORTHLAKE, ILLINOIS 60164

ACCOUNT #	AMOUNT
WF-6631	\$109,349.78
WF-3520	(\$10,934.98)
WF-3530	(\$840.00)

#	ITEM	ORIGINAL CONTRACT QUANTITY	UNIT	UNIT PRICE	ORIGINAL CONTRACT PRICE	AMENDED CONTRACT QUANTITY	AMENDED CONTRACT PRICE	CURRENT QUANTITY	TO DATE EXTENSION	PREVIOUS QUANTITY	PAYMENT EXTENSION	THIS QUANTITY	PAYMENT EXTENSION	CONTRACT QUANTITY	BALANCE EXTENSION
	CONTRACT SUB-TOTALS				\$7,812,435.00 =====		\$7,745,700.00 =====		\$6,852,491.77		\$6,743,141.99		\$109,349.78		\$893,208.23
	RETENTION	10.00%							(\$685,249.18)		(\$674,314.20)		(\$10,934.98)		\$685,249.18
	CONTRACT TOTALS								\$6,167,242.59		\$6,068,827.79		\$98,414.80		\$1,578,457.41 =====
DEDUCTS/BONUS															
1X	EXCESS ENGINEERING COSTS-DWC		HRS.	(60.00)				641.50	(\$38,490.00)	627.50	(\$37,650.00)	14.00	(\$840.00)		
	NET PAYMENT TO CONTRACTOR								\$6,128,752.59		\$6,031,177.79		\$97,574.80		
	CHANGE ORDER PERCENTAGE								-0.85%						

STAFF APPROVALS	
ENGINEERING	VB
ACCOUNTING	SKK
	CRP

ROSSI CONTRACTORS
201 WEST LAKE STREET
NORTHLAKE, ILLINOIS 60164

ACCOUNT # AMOUNT
WF-6631 \$109,349.78
WF-3520 (\$10,934.98)
WF-3530 (\$840.00)

#	ITEM	ORIGINAL CONTRACT QUANTITY	UNIT	UNIT PRICE	ORIGINAL CONTRACT PRICE	AMENDED CONTRACT QUANTITY	AMENDED CONTRACT PRICE	CURRENT QUANTITY	TO DATE EXTENSION	PREVIOUS QUANTITY	PAYMENT EXTENSION	THIS QUANTITY	PAYMENT EXTENSION	CONTRACT QUANTITY	BALANCE EXTENSION
1	Valve #1	100%	Lump Sum	\$0.00	\$0.00	100%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$0.00
2	Valve #2	100%	Lump Sum	\$12,500.00	\$12,500.00	100%	\$12,500.00	100%	\$12,500.00	100%	\$12,500.00	0%	\$0.00	0%	\$0.00
3	Valve #3	100%	Lump Sum	\$0.00	\$0.00	100%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$0.00
4	Valve #4	100%	Lump Sum	\$0.00	\$0.00	100%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$0.00
5	Valve #5	100%	Lump Sum	\$0.00	\$0.00	100%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$0.00
6	Valve #6	100%	Lump Sum	\$50,500.00	\$50,500.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00
7	Valve #7	100%	Lump Sum	\$0.00	\$0.00	100%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$0.00
8	Valve #8	100%	Lump Sum	\$0.00	\$0.00	100%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$0.00
9	Valve #9	100%	Lump Sum	\$0.00	\$0.00	100%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$0.00
10	Valve #10	100%	Lump Sum	\$19,300.00	\$19,300.00	100%	\$19,300.00	100%	\$19,300.00	100%	\$19,300.00	0%	\$0.00	0%	\$0.00
11	Valve #11	100%	Lump Sum	\$0.00	\$0.00	100%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$0.00
12	Valve #12	100%	Lump Sum	\$16,200.00	\$16,200.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00
13	Valve #13	100%	Lump Sum	\$14,600.00	\$14,600.00	100%	\$14,600.00	100%	\$14,600.00	100%	\$14,600.00	0%	\$0.00	0%	\$0.00
14	Valve #14	100%	Lump Sum	\$49,600.00	\$49,600.00	100%	\$49,600.00	100%	\$49,600.00	100%	\$49,600.00	0%	\$0.00	0%	\$0.00
15	Valve #15	100%	Lump Sum	\$15,900.00	\$15,900.00	100%	\$15,900.00	100%	\$15,900.00	100%	\$15,900.00	0%	\$0.00	0%	\$0.00
16	Valve #16	100%	Lump Sum	\$48,500.00	\$48,500.00	100%	\$48,500.00	100%	\$48,500.00	100%	\$48,500.00	0%	\$0.00	0%	\$0.00
17	Valve #17	100%	Lump Sum	\$0.00	\$0.00	100%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00
18	Valve #18	100%	Lump Sum	\$49,400.00	\$49,400.00	100%	\$49,400.00	100%	\$49,400.00	100%	\$49,400.00	0%	\$0.00	100%	\$0.00
19	Valve #19	100%	Lump Sum	\$0.00	\$0.00	100%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00
20	Valve #20	100%	Lump Sum	\$13,900.00	\$13,900.00	100%	\$13,900.00	100%	\$13,900.00	100%	\$13,900.00	0%	\$0.00	100%	\$0.00
21	Valve #21	100%	Lump Sum	\$19,600.00	\$19,600.00	100%	\$19,600.00	100%	\$19,600.00	100%	\$19,600.00	0%	\$0.00	0%	\$0.00
22	Valve #22	100%	Lump Sum	\$0.00	\$0.00	100%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00
23	Valve #23	100%	Lump Sum	\$0.00	\$0.00	100%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$0.00
24	Valve #24	100%	Lump Sum	\$0.00	\$0.00	100%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$0.00
25	Valve #25	100%	Lump Sum	\$11,800.00	\$11,800.00	100%	\$11,800.00	100%	\$11,800.00	100%	\$11,800.00	0%	\$0.00	0%	\$0.00
26	Valve #26	100%	Lump Sum	\$18,700.00	\$18,700.00	100%	\$18,700.00	100%	\$18,700.00	100%	\$18,700.00	0%	\$0.00	0%	\$0.00
27	Valve #27	100%	Lump Sum	\$19,400.00	\$19,400.00	100%	\$19,400.00	100%	\$19,400.00	100%	\$19,400.00	0%	\$0.00	0%	\$0.00
28	Valve #28	100%	Lump Sum	\$15,700.00	\$15,700.00	100%	\$15,700.00	100%	\$15,700.00	100%	\$15,700.00	0%	\$0.00	0%	\$0.00
29	Valve #29	100%	Lump Sum	\$16,900.00	\$16,900.00	100%	\$16,900.00	100%	\$16,900.00	100%	\$16,900.00	0%	\$0.00	0%	\$0.00
30	Valve #30	100%	Lump Sum	\$16,500.00	\$16,500.00	100%	\$16,500.00	100%	\$16,500.00	100%	\$16,500.00	0%	\$0.00	0%	\$0.00
31	Valve #31	100%	Lump Sum	\$14,800.00	\$14,800.00	100%	\$14,800.00	100%	\$14,800.00	100%	\$14,800.00	0%	\$0.00	0%	\$0.00
32	Valve #32	100%	Lump Sum	\$15,700.00	\$15,700.00	100%	\$15,700.00	100%	\$15,700.00	100%	\$15,700.00	0%	\$0.00	0%	\$0.00
33	Valve #33	100%	Lump Sum	\$11,800.00	\$11,800.00	100%	\$11,800.00	100%	\$11,800.00	100%	\$11,800.00	0%	\$0.00	0%	\$0.00
34	Valve #34	100%	Lump Sum	\$68,600.00	\$68,600.00	100%	\$68,600.00	100%	\$68,600.00	100%	\$68,600.00	0%	\$0.00	0%	\$0.00
35	Valve #35	100%	Lump Sum	\$16,400.00	\$16,400.00	100%	\$16,400.00	100%	\$16,400.00	100%	\$16,400.00	0%	\$0.00	0%	\$0.00
36	Valve #36	100%	Lump Sum	\$13,800.00	\$13,800.00	100%	\$13,800.00	100%	\$13,800.00	100%	\$13,800.00	0%	\$0.00	0%	\$0.00
37	Valve #37	100%	Lump Sum	\$51,700.00	\$51,700.00	100%	\$51,700.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00
38	Valve #38	100%	Lump Sum	\$69,500.00	\$69,500.00	100%	\$69,500.00	100%	\$69,500.00	100%	\$69,500.00	0%	\$0.00	100%	\$51,700.00
39	Valve #39	100%	Lump Sum	\$19,500.00	\$19,500.00	100%	\$19,500.00	100%	\$19,500.00	100%	\$19,500.00	0%	\$0.00	0%	\$0.00
40	Valve #40	100%	Lump Sum	\$15,500.00	\$15,500.00	100%	\$15,500.00	100%	\$15,500.00	100%	\$15,500.00	0%	\$0.00	0%	\$0.00
41	Valve #41	100%	Lump Sum	\$16,000.00	\$16,000.00	100%	\$16,000.00	100%	\$16,000.00	100%	\$16,000.00	0%	\$0.00	0%	\$0.00
42	Valve #42	100%	Lump Sum	\$18,600.00	\$18,600.00	100%	\$18,600.00	100%	\$18,600.00	100%	\$18,600.00	0%	\$0.00	0%	\$0.00
43	Valve #43	100%	Lump Sum	\$47,600.00	\$47,600.00	100%	\$47,600.00	100%	\$47,600.00	100%	\$47,600.00	0%	\$0.00	0%	\$0.00
44	Valve #44	100%	Lump Sum	\$16,200.00	\$16,200.00	100%	\$16,200.00	100%	\$16,200.00	100%	\$16,200.00	0%	\$0.00	0%	\$0.00
45	Valve #45	100%	Lump Sum	\$48,800.00	\$48,800.00	100%	\$48,800.00	100%	\$48,800.00	100%	\$48,800.00	0%	\$0.00	0%	\$0.00
46	Valve #46	100%	Lump Sum	\$48,500.00	\$48,500.00	100%	\$48,500.00	100%	\$48,500.00	100%	\$48,500.00	0%	\$0.00	0%	\$0.00
47	Valve #47	100%	Lump Sum	\$49,300.00	\$49,300.00	100%	\$49,300.00	100%	\$49,300.00	100%	\$49,300.00	0%	\$0.00	0%	\$0.00
48	Valve #48	100%	Lump Sum	\$13,100.00	\$13,100.00	100%	\$13,100.00	100%	\$13,100.00	100%	\$13,100.00	0%	\$0.00	0%	\$0.00
49	Valve #49	100%	Lump Sum	\$15,600.00	\$15,600.00	100%	\$15,600.00	100%	\$15,600.00	100%	\$15,600.00	0%	\$0.00	0%	\$0.00
50	Valve #50	100%	Lump Sum	\$49,500.00	\$49,500.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00
51	Valve #51	100%	Lump Sum	\$13,800.00	\$13,800.00	100%	\$13,800.00	100%	\$13,800.00	100%	\$13,800.00	0%	\$0.00	0%	\$0.00
52	Valve #52	100%	Lump Sum	\$11,300.00	\$11,300.00	100%	\$11,300.00	100%	\$11,300.00	100%	\$11,300.00	0%	\$0.00	0%	\$0.00
53	Valve #53	100%	Lump Sum	\$11,600.00	\$11,600.00	100%	\$11,600.00	100%	\$11,600.00	100%	\$11,600.00	0%	\$0.00	0%	\$0.00
54	Valve #54	100%	Lump Sum	\$11,400.00	\$11,400.00	100%	\$11,400.00	100%	\$11,400.00	100%	\$11,400.00	0%	\$0.00	0%	\$0.00
55	Valve #55	100%	Lump Sum	\$19,300.00	\$19,300.00	100%	\$19,300.00	100%	\$19,300.00	100%	\$19,300.00	0%	\$0.00	0%	\$0.00
56	Valve #56	100%	Lump Sum	\$13,800.00	\$13,800.00	100%	\$13,800.00	100%	\$13,800.00	100%	\$13,800.00	0%	\$0.00	0%	\$0.00
57	Valve #57	100%	Lump Sum	\$11,800.00	\$11,800.00	100%	\$11,800.00	100%	\$11,800.00	100%	\$11,800.00	0%	\$0.00	0%	\$0.00
58	Valve #58	100%	Lump Sum	\$11,800.00	\$11,800.00	100%	\$11,800.00	100%	\$11,800.00	100%	\$11,800.00	0%	\$0.00	0%	\$0.00
59	Valve #59	100%	Lump Sum	\$12,500.00	\$12,500.00	100%	\$12,500.00	100%	\$12,500.00	100%	\$12,500.00	0%	\$0.00	0%	\$0.00
60	Valve #60	100%	Lump Sum	\$11,700.00	\$11,700.00	100%	\$11,700.00	100%	\$11,700.00	100%	\$11,700.00	0%	\$0.00	0%	\$0.00
61	Valve #61	100%	Lump Sum	\$11,700.00	\$11,700.00	100%	\$11,700.00	100%	\$11,700.00	100%	\$11,700.00	0%	\$0.00	0%	\$0.00
62	Valve #62	100%	Lump Sum	\$11,600.00	\$11,600.00	100%	\$11,600.00	100%	\$11,600.00	100%	\$11,600.00	0%	\$0.00	0%	\$0.00
63	Valve #63	100%	Lump Sum	\$16,500.00	\$16,500.00	100%	\$16,500.00	100%	\$16,500.00	100%	\$16,500.00	0%	\$0.00	0%	\$0.00
64	Valve #64	100%	Lump Sum	\$15,500.00	\$15,500.00	100%	\$15,500.00	100%	\$15,500.00	100%	\$15,500.00	0%	\$0.00	0%	\$0.00
65	Valve #65	100%	Lump Sum	\$26,600.00	\$26,600.00	100%	\$26,600.00	100%	\$26,600.00	100%	\$26,600.00	0%	\$0.00	0%	</

BLOW OFF VALVE REPAIR (BOV-1)

DATE 07/30/04

ROSSI CONTRACTORS
201 WEST LAKE STREET
NORTHLAKE, ILLINOIS 60164

ACCOUNT # AMOUNT
WF-6631 \$109,349.78
WF-3520 (\$10,934.98)
WF-3530 (\$840.00)

#	ITEM	ORIGINAL CONTRACT QUANTITY	UNIT	UNIT PRICE	ORIGINAL CONTRACT PRICE	AMENDED CONTRACT QUANTITY	AMENDED CONTRACT PRICE	CURRENT QUANTITY	TO DATE EXTENSION	PREVIOUS QUANTITY	PAYMENT EXTENSION	THIS QUANTITY	PAYMENT EXTENSION	CONTRACT QUANTITY	BALANCE EXTENSION
80	Valve #80	100%	Lump Sum	\$19,400.00	\$19,400.00	100%	\$19,400.00	100%	\$19,400.00	0%	\$0.00	100%	\$19,400.00	0%	\$0.00
81	Valve #81	100%	Lump Sum	\$16,300.00	\$16,300.00	100%	\$16,300.00	100%	\$16,300.00	100%	\$16,300.00	0%	\$0.00	0%	\$0.00
82	Valve #82	100%	Lump Sum	\$19,100.00	\$19,100.00	100%	\$19,100.00	100%	\$19,100.00	100%	\$19,100.00	0%	\$0.00	0%	\$0.00
83	Valve #83	100%	Lump Sum	\$14,300.00	\$14,300.00	100%	\$14,300.00	100%	\$14,300.00	100%	\$14,300.00	0%	\$0.00	0%	\$0.00
84	Valve #84	100%	Lump Sum	\$16,000.00	\$16,000.00	100%	\$16,000.00	100%	\$16,000.00	100%	\$16,000.00	0%	\$0.00	0%	\$0.00
85	Valve #85	100%	Lump Sum	\$16,300.00	\$16,300.00	100%	\$16,300.00	100%	\$16,300.00	100%	\$16,300.00	0%	\$0.00	0%	\$0.00
86	Valve #86	100%	Lump Sum	\$16,500.00	\$16,500.00	100%	\$16,500.00	100%	\$16,500.00	100%	\$16,500.00	0%	\$0.00	0%	\$0.00
87	Valve #87	100%	Lump Sum	\$11,300.00	\$11,300.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00
88	Valve #88	100%	Lump Sum	\$0.00	\$0.00	100%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$0.00
89	Valve #89	100%	Lump Sum	\$15,100.00	\$15,100.00	100%	\$15,100.00	100%	\$15,100.00	100%	\$15,100.00	0%	\$0.00	0%	\$0.00
90	Valve #90	100%	Lump Sum	\$12,200.00	\$12,200.00	100%	\$12,200.00	100%	\$12,200.00	100%	\$12,200.00	0%	\$0.00	0%	\$0.00
91	Valve #91	100%	Lump Sum	\$11,200.00	\$11,200.00	100%	\$11,200.00	100%	\$11,200.00	100%	\$11,200.00	0%	\$0.00	0%	\$0.00
92	Valve #92	100%	Lump Sum	\$11,500.00	\$11,500.00	100%	\$11,500.00	100%	\$11,500.00	100%	\$11,500.00	0%	\$0.00	0%	\$0.00
93	Valve #93	100%	Lump Sum	\$0.00	\$0.00	100%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$0.00
94	Valve #94	100%	Lump Sum	\$11,900.00	\$11,900.00	100%	\$11,900.00	100%	\$11,900.00	100%	\$11,900.00	0%	\$0.00	0%	\$0.00
95	Valve #95	100%	Lump Sum	\$16,000.00	\$16,000.00	100%	\$16,000.00	100%	\$16,000.00	100%	\$16,000.00	0%	\$0.00	0%	\$0.00
96	Valve #96	100%	Lump Sum	\$16,800.00	\$16,800.00	100%	\$16,800.00	100%	\$16,800.00	100%	\$16,800.00	0%	\$0.00	0%	\$0.00
97	Valve #97	100%	Lump Sum	\$16,300.00	\$16,300.00	100%	\$16,300.00	100%	\$16,300.00	100%	\$16,300.00	0%	\$0.00	0%	\$0.00
98	Valve #98	100%	Lump Sum	\$16,400.00	\$16,400.00	100%	\$16,400.00	100%	\$16,400.00	0%	\$0.00	100%	\$16,400.00	0%	\$0.00
99	Valve #99	100%	Lump Sum	\$70,400.00	\$70,400.00	100%	\$70,400.00	100%	\$70,400.00	100%	\$70,400.00	0%	\$0.00	0%	\$0.00
100	Valve #100	100%	Lump Sum	\$15,000.00	\$15,000.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00
101	Valve #101	100%	Lump Sum	\$50,500.00	\$50,500.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00
102	Valve #102	100%	Lump Sum	\$51,000.00	\$51,000.00	100%	\$51,000.00	100%	\$51,000.00	100%	\$51,000.00	0%	\$0.00	0%	\$0.00
103	Valve #103	100%	Lump Sum	\$49,100.00	\$49,100.00	100%	\$49,100.00	100%	\$49,100.00	100%	\$49,100.00	0%	\$0.00	0%	\$0.00
104	Valve #104	100%	Lump Sum	\$0.00	\$0.00	100%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$0.00
105	Valve #105	100%	Lump Sum	\$0.00	\$0.00	100%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$0.00
106	Valve #106	100%	Lump Sum	\$16,700.00	\$16,700.00	100%	\$16,700.00	100%	\$16,700.00	100%	\$16,700.00	0%	\$0.00	0%	\$0.00
107	Valve #107	100%	Lump Sum	\$12,800.00	\$12,800.00	100%	\$12,800.00	100%	\$12,800.00	100%	\$12,800.00	0%	\$0.00	0%	\$0.00
108	Valve #108	100%	Lump Sum	\$70,700.00	\$70,700.00	100%	\$70,700.00	100%	\$70,700.00	100%	\$70,700.00	0%	\$0.00	0%	\$0.00
109	Valve #109	100%	Lump Sum	\$27,500.00	\$27,500.00	100%	\$27,500.00	100%	\$27,500.00	100%	\$27,500.00	0%	\$0.00	0%	\$0.00
110	Valve #110	100%	Lump Sum	\$27,300.00	\$27,300.00	100%	\$27,300.00	100%	\$27,300.00	100%	\$27,300.00	0%	\$0.00	0%	\$0.00
111	Valve #111	100%	Lump Sum	\$17,600.00	\$17,600.00	100%	\$17,600.00	100%	\$17,600.00	100%	\$17,600.00	0%	\$0.00	0%	\$0.00
112	Valve #112	100%	Lump Sum	\$0.00	\$0.00	100%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$0.00
113	Valve #113	100%	Lump Sum	\$0.00	\$0.00	100%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$0.00
114	Valve #114	100%	Lump Sum	\$0.00	\$0.00	100%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$0.00
115	Valve #115	100%	Lump Sum	\$0.00	\$0.00	100%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$0.00
116	Valve #116	100%	Lump Sum	\$19,400.00	\$19,400.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00
117	Valve #117	100%	Lump Sum	\$17,700.00	\$17,700.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00
118	Valve #118	100%	Lump Sum	\$16,200.00	\$16,200.00	100%	\$16,200.00	100%	\$16,200.00	100%	\$16,200.00	0%	\$0.00	0%	\$0.00
119	Valve #119	100%	Lump Sum	\$12,100.00	\$12,100.00	100%	\$12,100.00	100%	\$12,100.00	100%	\$12,100.00	0%	\$0.00	0%	\$0.00
120	Valve #120	100%	Lump Sum	\$24,500.00	\$24,500.00	100%	\$24,500.00	100%	\$24,500.00	100%	\$24,500.00	0%	\$0.00	0%	\$0.00
121	Valve #121	100%	Lump Sum	\$28,000.00	\$28,000.00	100%	\$28,000.00	100%	\$28,000.00	100%	\$28,000.00	0%	\$0.00	0%	\$0.00
122	Valve #122	100%	Lump Sum	\$26,700.00	\$26,700.00	100%	\$26,700.00	100%	\$26,700.00	100%	\$26,700.00	0%	\$0.00	0%	\$0.00
123	Valve #123	100%	Lump Sum	\$11,700.00	\$11,700.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00
124	Valve #124	100%	Lump Sum	\$12,100.00	\$12,100.00	100%	\$12,100.00	100%	\$12,100.00	100%	\$12,100.00	0%	\$0.00	0%	\$0.00
125	Valve #125	100%	Lump Sum	\$13,500.00	\$13,500.00	100%	\$13,500.00	100%	\$13,500.00	100%	\$13,500.00	0%	\$0.00	0%	\$0.00
126	Valve #126	100%	Lump Sum	\$11,800.00	\$11,800.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00
127	Valve #127	100%	Lump Sum	\$16,500.00	\$16,500.00	100%	\$16,500.00	100%	\$16,500.00	100%	\$16,500.00	0%	\$0.00	0%	\$0.00
128	Valve #128	100%	Lump Sum	\$15,100.00	\$15,100.00	100%	\$15,100.00	100%	\$15,100.00	100%	\$15,100.00	0%	\$0.00	0%	\$0.00
129	Valve #129	100%	Lump Sum	\$16,700.00	\$16,700.00	100%	\$16,700.00	100%	\$16,700.00	100%	\$16,700.00	0%	\$0.00	0%	\$0.00
130	Valve #130	100%	Lump Sum	\$12,300.00	\$12,300.00	100%	\$12,300.00	100%	\$12,300.00	100%	\$12,300.00	0%	\$0.00	0%	\$0.00
131	Valve #131	100%	Lump Sum	\$16,400.00	\$16,400.00	100%	\$16,400.00	100%	\$16,400.00	100%	\$16,400.00	0%	\$0.00	0%	\$0.00
132	Valve #132	100%	Lump Sum	\$16,500.00	\$16,500.00	100%	\$16,500.00	100%	\$16,500.00	100%	\$16,500.00	0%	\$0.00	0%	\$0.00
133	Valve #133	100%	Lump Sum	\$12,900.00	\$12,900.00	100%	\$12,900.00	100%	\$12,900.00	100%	\$12,900.00	0%	\$0.00	0%	\$0.00
134	Valve #134	100%	Lump Sum	\$12,900.00	\$12,900.00	100%	\$12,900.00	100%	\$12,900.00	100%	\$12,900.00	0%	\$0.00	0%	\$0.00
135	Valve #135	100%	Lump Sum	\$12,700.00	\$12,700.00	100%	\$12,700.00	100%	\$12,700.00	100%	\$12,700.00	0%	\$0.00	0%	\$0.00
136	Valve #136	100%	Lump Sum	\$12,100.00	\$12,100.00	100%	\$12,100.00	100%	\$12,100.00	100%	\$12,100.00	0%	\$0.00	0%	\$0.00
137	Valve #137	100%	Lump Sum	\$15,900.00	\$15,900.00	100%	\$15,900.00	100%	\$15,900.00	100%	\$15,900.00	0%	\$0.00	0%	\$0.00
138	Valve #138	100%	Lump Sum	\$11,800.00	\$11,800.00	100%	\$11,800.00	100%	\$11,800.00	100%	\$11,800.00	0%	\$0.00	0%	\$0.00
139	Valve #139	100%	Lump Sum	\$16,200.00	\$16,200.00	100%	\$16,200.00	100%	\$16,200.00	100%	\$16,200.00	0%	\$0.00	0%	\$0.00
140	Valve #140	100%	Lump Sum	\$16,500.00	\$16,500.00	100%	\$16,500.00	100%	\$16,500.00	100%	\$16,500.00	0%	\$0.00	0%	\$0.00
141	Valve #141	100%	Lump Sum	\$14,300.00	\$14,300.00	100%	\$14,300.00	100%	\$14,300.00	100%	\$14,300.00	0%	\$0.00	0%	\$0.00
142	Valve #142	100%	Lump Sum	\$15,500.00	\$15,500.00	100%	\$15,500.00	100%	\$15,500.00	100%	\$15,500.00	0%	\$0.00	0%	\$0.00
143	Valve #143	100%	Lump Sum	\$16,400.00	\$16,400.00	100%	\$16,400.00	100%	\$16,400.00	100%	\$16,400.00	0%	\$0.00	0%	\$0.00

ROSSI CONTRACTORS
201 WEST LAKE STREET
NORTHLAKE, ILLINOIS 60164ACCOUNT # AMOUNT
WF-6631 \$109,349.78
WF-3520 (\$10,934.98)
WF-3530 (\$840.00)

#	ITEM	ORIGINAL CONTRACT QUANTITY	UNIT	UNIT PRICE	ORIGINAL CONTRACT PRICE	AMENDED CONTRACT QUANTITY	AMENDED CONTRACT PRICE	CURRENT QUANTITY	TO DATE EXTENSION	PREVIOUS QUANTITY	PAYMENT EXTENSION	THIS QUANTITY	PAYMENT EXTENSION	CONTRACT QUANTITY	BALANCE EXTENSION
159	Valve #159	100%	Lump Sum	\$15,300.00	\$15,300.00	100%	\$15,300.00	100%	\$15,300.00	100%	\$15,300.00	0%	\$0.00	0%	\$0.00
160	Valve #160	100%	Lump Sum	\$15,400.00	\$15,400.00	100%	\$15,400.00	100%	\$15,400.00	100%	\$15,400.00	0%	\$0.00	0%	\$0.00
161	Valve #161	100%	Lump Sum	\$17,800.00	\$17,800.00	100%	\$17,800.00	100%	\$17,800.00	100%	\$17,800.00	0%	\$0.00	0%	\$0.00
162	Valve #162	100%	Lump Sum	\$16,500.00	\$16,500.00	100%	\$16,500.00	100%	\$16,500.00	100%	\$16,500.00	0%	\$0.00	0%	\$0.00
163	Valve #163	100%	Lump Sum	\$17,200.00	\$17,200.00	100%	\$17,200.00	100%	\$17,200.00	100%	\$17,200.00	0%	\$0.00	0%	\$0.00
164	Valve #164	100%	Lump Sum	\$12,500.00	\$12,500.00	100%	\$12,500.00	100%	\$12,500.00	100%	\$12,500.00	0%	\$0.00	0%	\$0.00
165	Valve #165	100%	Lump Sum	\$11,900.00	\$11,900.00	100%	\$11,900.00	100%	\$11,900.00	100%	\$11,900.00	0%	\$0.00	0%	\$0.00
166	Valve #166	100%	Lump Sum	\$15,800.00	\$15,800.00	100%	\$15,800.00	100%	\$15,800.00	100%	\$15,800.00	0%	\$0.00	0%	\$0.00
167	Valve #167	100%	Lump Sum	\$15,300.00	\$15,300.00	100%	\$15,300.00	100%	\$15,300.00	100%	\$15,300.00	0%	\$0.00	0%	\$0.00
168	Valve #168	100%	Lump Sum	\$16,400.00	\$16,400.00	100%	\$16,400.00	100%	\$16,400.00	100%	\$16,400.00	0%	\$0.00	0%	\$0.00
169	Valve #169	100%	Lump Sum	\$17,700.00	\$17,700.00	100%	\$17,700.00	100%	\$17,700.00	100%	\$17,700.00	0%	\$0.00	0%	\$0.00
170	Valve #170	100%	Lump Sum	\$15,800.00	\$15,800.00	100%	\$15,800.00	100%	\$15,800.00	100%	\$15,800.00	0%	\$0.00	0%	\$0.00
171	Valve #171	100%	Lump Sum	\$18,400.00	\$18,400.00	100%	\$18,400.00	100%	\$18,400.00	100%	\$18,400.00	0%	\$0.00	0%	\$0.00
172	Valve #172	100%	Lump Sum	\$15,900.00	\$15,900.00	100%	\$15,900.00	100%	\$15,900.00	100%	\$15,900.00	0%	\$0.00	0%	\$0.00
173	Valve #173	100%	Lump Sum	\$16,300.00	\$16,300.00	100%	\$16,300.00	100%	\$16,300.00	100%	\$16,300.00	0%	\$0.00	0%	\$0.00
174	Valve #174	100%	Lump Sum	\$17,700.00	\$17,700.00	100%	\$17,700.00	100%	\$17,700.00	100%	\$17,700.00	0%	\$0.00	0%	\$0.00
175	Valve #175	100%	Lump Sum	\$18,200.00	\$18,200.00	100%	\$18,200.00	100%	\$18,200.00	100%	\$18,200.00	0%	\$0.00	0%	\$0.00
176	Valve #176	100%	Lump Sum	\$16,900.00	\$16,900.00	100%	\$16,900.00	100%	\$16,900.00	100%	\$16,900.00	0%	\$0.00	0%	\$0.00
177	Valve #177	100%	Lump Sum	\$17,700.00	\$17,700.00	100%	\$17,700.00	100%	\$17,700.00	100%	\$17,700.00	0%	\$0.00	0%	\$0.00
178	Valve #178	100%	Lump Sum	\$16,800.00	\$16,800.00	100%	\$16,800.00	100%	\$16,800.00	100%	\$16,800.00	0%	\$0.00	0%	\$0.00
179	Valve #179	100%	Lump Sum	\$16,800.00	\$16,800.00	100%	\$16,800.00	100%	\$16,800.00	100%	\$16,800.00	0%	\$0.00	0%	\$0.00
180	Valve #180	100%	Lump Sum	\$48,400.00	\$48,400.00	100%	\$48,400.00	100%	\$48,400.00	100%	\$48,400.00	0%	\$0.00	0%	\$0.00
181	Valve #181	100%	Lump Sum	\$12,800.00	\$12,800.00	100%	\$12,800.00	100%	\$12,800.00	100%	\$12,800.00	0%	\$0.00	0%	\$0.00
182	Valve #182	100%	Lump Sum	\$11,800.00	\$11,800.00	100%	\$11,800.00	100%	\$11,800.00	100%	\$11,800.00	0%	\$0.00	0%	\$0.00
183	Valve #183	100%	Lump Sum	\$16,300.00	\$16,300.00	100%	\$16,300.00	100%	\$16,300.00	100%	\$16,300.00	0%	\$0.00	0%	\$0.00
184	Valve #184	100%	Lump Sum	\$12,600.00	\$12,600.00	100%	\$12,600.00	100%	\$12,600.00	100%	\$12,600.00	0%	\$0.00	0%	\$0.00
185	Valve #185	100%	Lump Sum	\$13,500.00	\$13,500.00	100%	\$13,500.00	100%	\$13,500.00	100%	\$13,500.00	0%	\$0.00	0%	\$0.00
186	Valve #186	100%	Lump Sum	\$12,600.00	\$12,600.00	100%	\$12,600.00	100%	\$12,600.00	100%	\$12,600.00	0%	\$0.00	0%	\$0.00
187	Valve #187	100%	Lump Sum	\$12,400.00	\$12,400.00	100%	\$12,400.00	100%	\$12,400.00	100%	\$12,400.00	0%	\$0.00	0%	\$0.00
188	Valve #188	100%	Lump Sum	\$14,900.00	\$14,900.00	100%	\$14,900.00	100%	\$14,900.00	100%	\$14,900.00	0%	\$0.00	0%	\$0.00
189	Valve #189	100%	Lump Sum	\$16,400.00	\$16,400.00	100%	\$16,400.00	100%	\$16,400.00	100%	\$16,400.00	0%	\$0.00	0%	\$0.00
190	Valve #190	100%	Lump Sum	\$16,400.00	\$16,400.00	100%	\$16,400.00	100%	\$16,400.00	100%	\$16,400.00	0%	\$0.00	0%	\$0.00
191	Valve #191	100%	Lump Sum	\$15,600.00	\$15,600.00	100%	\$15,600.00	100%	\$15,600.00	100%	\$15,600.00	0%	\$0.00	0%	\$0.00
192	Valve #192	100%	Lump Sum	\$15,100.00	\$15,100.00	100%	\$15,100.00	100%	\$15,100.00	100%	\$15,100.00	0%	\$0.00	0%	\$0.00
193	Valve #193	100%	Lump Sum	\$16,500.00	\$16,500.00	100%	\$16,500.00	100%	\$16,500.00	100%	\$16,500.00	0%	\$0.00	0%	\$0.00
194	Valve #194	100%	Lump Sum	\$16,500.00	\$16,500.00	100%	\$16,500.00	100%	\$16,500.00	100%	\$16,500.00	0%	\$0.00	0%	\$0.00
195	Valve #195	100%	Lump Sum	\$15,000.00	\$15,000.00	100%	\$15,000.00	100%	\$15,000.00	100%	\$15,000.00	0%	\$0.00	0%	\$0.00
196	Valve #196	100%	Lump Sum	\$15,100.00	\$15,100.00	100%	\$15,100.00	100%	\$15,100.00	100%	\$15,100.00	0%	\$0.00	0%	\$0.00
197	Valve #197	100%	Lump Sum	\$15,600.00	\$15,600.00	100%	\$15,600.00	100%	\$15,600.00	100%	\$15,600.00	0%	\$0.00	0%	\$0.00
198	Valve #198	100%	Lump Sum	\$11,800.00	\$11,800.00	100%	\$11,800.00	100%	\$11,800.00	100%	\$11,800.00	0%	\$0.00	0%	\$0.00
199	Valve #199	100%	Lump Sum	\$16,500.00	\$16,500.00	100%	\$16,500.00	100%	\$16,500.00	100%	\$16,500.00	0%	\$0.00	0%	\$0.00
200	Valve #200	100%	Lump Sum	\$16,500.00	\$16,500.00	100%	\$16,500.00	100%	\$16,500.00	100%	\$16,500.00	0%	\$0.00	0%	\$0.00
201	Valve #201	100%	Lump Sum	\$0.00	\$0.00	100%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$0.00
202	Valve #202	100%	Lump Sum	\$11,400.00	\$11,400.00	100%	\$11,400.00	100%	\$11,400.00	100%	\$11,400.00	0%	\$0.00	0%	\$0.00
203	Valve #203	100%	Lump Sum	\$16,000.00	\$16,000.00	100%	\$16,000.00	100%	\$16,000.00	100%	\$16,000.00	0%	\$0.00	0%	\$0.00
204	Valve #204	100%	Lump Sum	\$17,700.00	\$17,700.00	100%	\$17,700.00	100%	\$17,700.00	100%	\$17,700.00	0%	\$0.00	0%	\$0.00
205	Valve #205	100%	Lump Sum	\$17,200.00	\$17,200.00	100%	\$17,200.00	100%	\$17,200.00	100%	\$17,200.00	0%	\$0.00	0%	\$0.00
206	Valve #206	100%	Lump Sum	\$15,900.00	\$15,900.00	100%	\$15,900.00	100%	\$15,900.00	100%	\$15,900.00	0%	\$0.00	0%	\$0.00
207	Valve #207	100%	Lump Sum	\$15,200.00	\$15,200.00	100%	\$15,200.00	100%	\$15,200.00	100%	\$15,200.00	0%	\$0.00	0%	\$0.00
208	Valve #208	100%	Lump Sum	\$15,700.00	\$15,700.00	100%	\$15,700.00	100%	\$15,700.00	100%	\$15,700.00	0%	\$0.00	0%	\$0.00
209	Valve #209	100%	Lump Sum	\$17,200.00	\$17,200.00	100%	\$17,200.00	100%	\$17,200.00	100%	\$17,200.00	0%	\$0.00	0%	\$0.00
210	Valve #210	100%	Lump Sum	\$19,500.00	\$19,500.00	100%	\$19,500.00	100%	\$19,500.00	100%	\$19,500.00	0%	\$0.00	0%	\$0.00
211	Valve #211	100%	Lump Sum	\$16,000.00	\$16,000.00	100%	\$16,000.00	100%	\$16,000.00	100%	\$16,000.00	0%	\$0.00	0%	\$0.00
212	Valve #212	100%	Lump Sum	\$17,600.00	\$17,600.00	100%	\$17,600.00	100%	\$17,600.00	100%	\$17,600.00	0%	\$0.00	0%	\$0.00
213	Valve #213	100%	Lump Sum	\$16,400.00	\$16,400.00	100%	\$16,400.00	100%	\$16,400.00	100%	\$16,400.00	0%	\$0.00	0%	\$0.00
214	Valve #214	100%	Lump Sum	\$12,000.00	\$12,000.00	100%	\$12,000.00	100%	\$12,000.00	100%	\$12,000.00	0%	\$0.00	0%	\$0.00
215	Valve #215	100%	Lump Sum	\$15,000.00	\$15,000.00	100%	\$15,000.00	100%	\$15,000.00	100%	\$15,000.00	0%	\$0.00	0%	\$0.00
216	Valve #216	100%	Lump Sum	\$15,800.00	\$15,800.00	100%	\$15,800.00	100%	\$15,800.00	100%	\$15,800.00	0%	\$0.00	0%	\$0.00
217	Valve #217	100%	Lump Sum	\$16,300.00	\$16,300.00	100%	\$16,300.00	100%	\$16,300.00	100%	\$16,300.00	0%	\$0.00	0%	\$0.00
218	Valve #218	100%	Lump Sum	\$26,200.00	\$26,200.00	100%	\$26,200.00	100%	\$26,200.00	100%	\$26,200.00	0%	\$0.00	0%	\$0.00
219	Valve #219	100%	Lump Sum	\$15,400.00	\$15,400.00	100%	\$15,400.00	100%	\$15,400.00	100%	\$15,400.00	0%	\$0.00	0%	\$0.00
220	Valve #220	100%	Lump Sum	\$16,000.00	\$16,000.00	100%	\$16,000.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$16,000.00
221	Valve #221	100%	Lump Sum	\$15,400.00	\$15,400.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00
222	Valve #222	100%	Lump Sum	\$12,900.00	\$12,900.00	100%	\$12,900.00	100%	\$12,900.00	100%	\$12,900.00	0%	\$0.00	0%	\$0.00
223	Valve #223	100%	Lump Sum	\$16,800.00	\$16,800.00	100%	\$16,800.00	100%	\$16,800.00	100%	\$16,800.00	0%	\$0.00	0%	\$0.00
224	Valve #224	100%	Lump Sum	\$25,400.00	\$25,400.00	100%	\$25,400.00	100%	\$25,400.00	100%	\$25,400.00	0%	\$0.00	0%	\$0.00
225	Valve #225	100%	Lump Sum	\$15,700.00	\$15,700.00	100%	\$15,700.00	100%	\$15,700.00	100%	\$15,700.00	0%	\$0.00	0%	\$0.00
226	Valve #226	100%	Lump Sum	\$25,200.00	\$25,200.00	100%	\$25,200.00	100%	\$25,200.00	100%	\$25,200.00	0%	\$0.00	0%	\$0.00
227	Valve #227	100%	Lump Sum	\$12,400.00	\$12,400.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00
228	Valve #228	100%	Lump Sum	\$11,600.00	\$11,600.00	100%	\$11,600.00	100%	\$11,600.00	100%	\$11,600.00	0%	\$0.00	0%	\$0.00
229	Valve #229	100%	Lump Sum	\$11,500.00	\$11,500.00	100%	\$11,500.00	100%	\$11,500.00	100%	\$11,500.00	0%	\$0.00	0%	\$0.00
230	Valve #230	100%	Lump Sum	\$0.00	\$0.00	100%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$0.00
231	Valve #231	100%	Lump Sum	\$16,000.00	\$16,000.00	100%	\$16,000.00	100%	\$16,000.00	100%	\$16,000.00	0%	\$0.00	0%	\$0.00
232	Valve #232	100%	Lump Sum	\$15,400.00	\$15,400.00	100%	\$15,400.00	100%	\$15,400.00	100%	\$15,400.00	0%	\$0.00	0%	\$0.00
233	Valve #233	100%	Lump Sum	\$14,900.00	\$14,900.00	100%	\$14,90								

BLOW OFF VALVE REPAIR (BOV-1)

DATE 07/30/04

ROSSI CONTRACTORS
201 WEST LAKE STREET
NORTHLAKE, ILLINOIS 60164

ACCOUNT # AMOUNT
WF-6631 \$109,349.78
WF-3520 (\$10,934.98)
WF-3530 (\$840.00)

#	ITEM	ORIGINAL CONTRACT QUANTITY	UNIT	UNIT PRICE	ORIGINAL CONTRACT PRICE	AMENDED CONTRACT QUANTITY	AMENDED CONTRACT PRICE	CURRENT QUANTITY	TO DATE EXTENSION	PREVIOUS QUANTITY	PAYMENT EXTENSION	THIS QUANTITY	PAYMENT EXTENSION	CONTRACT QUANTITY	BALANCE EXTENSION
238	Valve #238	100%	Lump Sum	\$69,900.00	\$69,900.00	100%	\$69,900.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$69,900.00
239	Valve #239	100%	Lump Sum	\$50,200.00	\$50,200.00	100%	\$50,200.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$50,200.00
240	Valve #240	100%	Lump Sum	\$16,300.00	\$16,300.00	100%	\$16,300.00	100%	\$16,300.00	100%	\$16,300.00	0%	\$0.00	0%	\$0.00
241	Valve #241	100%	Lump Sum	\$15,800.00	\$15,800.00	100%	\$15,800.00	100%	\$15,800.00	100%	\$15,800.00	0%	\$0.00	0%	\$0.00
242	Valve #242	100%	Lump Sum	\$16,400.00	\$16,400.00	100%	\$16,400.00	100%	\$16,400.00	100%	\$16,400.00	0%	\$0.00	0%	\$0.00
243	Valve #243	100%	Lump Sum	\$15,800.00	\$15,800.00	100%	\$15,800.00	100%	\$16,400.00	100%	\$16,400.00	0%	\$0.00	0%	\$0.00
244	Valve #244	100%	Lump Sum	\$0.00	\$0.00	100%	\$0.00	0%	\$0.00	100%	\$15,800.00	0%	\$0.00	0%	\$0.00
245	Valve #245	100%	Lump Sum	\$0.00	\$0.00	100%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$0.00
246	Valve #246	100%	Lump Sum	\$25,400.00	\$25,400.00	100%	\$25,400.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$0.00
247	Valve #247	100%	Lump Sum	\$16,200.00	\$16,200.00	100%	\$16,200.00	100%	\$16,200.00	100%	\$16,200.00	0%	\$0.00	0%	\$0.00
248	Valve #248	100%	Lump Sum	\$16,900.00	\$16,900.00	100%	\$16,900.00	100%	\$16,900.00	100%	\$16,900.00	0%	\$0.00	0%	\$0.00
249	Valve #249	100%	Lump Sum	\$16,400.00	\$16,400.00	100%	\$16,400.00	100%	\$16,400.00	100%	\$16,400.00	0%	\$0.00	0%	\$0.00
250	Valve #250	100%	Lump Sum	\$0.00	\$0.00	100%	\$0.00	0%	\$0.00	100%	\$16,400.00	0%	\$0.00	0%	\$0.00
251	Valve #251	100%	Lump Sum	\$12,500.00	\$12,500.00	100%	\$12,500.00	100%	\$12,500.00	100%	\$12,500.00	0%	\$0.00	0%	\$0.00
252	Valve #252	100%	Lump Sum	\$16,300.00	\$16,300.00	100%	\$16,300.00	100%	\$16,300.00	100%	\$16,300.00	0%	\$0.00	0%	\$0.00
253	Valve #253	100%	Lump Sum	\$15,100.00	\$15,100.00	100%	\$15,100.00	100%	\$15,100.00	100%	\$15,100.00	0%	\$0.00	0%	\$0.00
254	Valve #254	100%	Lump Sum	\$12,900.00	\$12,900.00	100%	\$12,900.00	100%	\$12,900.00	100%	\$12,900.00	0%	\$0.00	0%	\$0.00
255	Valve #255	100%	Lump Sum	\$47,600.00	\$47,600.00	100%	\$47,600.00	100%	\$47,600.00	100%	\$47,600.00	0%	\$0.00	0%	\$0.00
256	Valve #256	100%	Lump Sum	\$16,400.00	\$16,400.00	100%	\$16,400.00	100%	\$16,400.00	100%	\$16,400.00	0%	\$0.00	0%	\$0.00
257	Valve #257	100%	Lump Sum	\$16,400.00	\$16,400.00	100%	\$16,400.00	100%	\$16,400.00	100%	\$16,400.00	0%	\$0.00	0%	\$0.00
258	Valve #258	100%	Lump Sum	\$15,900.00	\$15,900.00	100%	\$15,900.00	100%	\$15,900.00	100%	\$15,900.00	0%	\$0.00	0%	\$0.00
259	Valve #259	100%	Lump Sum	\$15,300.00	\$15,300.00	100%	\$15,300.00	100%	\$15,300.00	100%	\$15,300.00	0%	\$0.00	0%	\$0.00
260	Valve #260	100%	Lump Sum	\$16,200.00	\$16,200.00	100%	\$16,200.00	100%	\$16,200.00	100%	\$16,200.00	0%	\$0.00	0%	\$0.00
261	Valve #261	100%	Lump Sum	\$16,000.00	\$16,000.00	100%	\$16,000.00	100%	\$16,000.00	100%	\$16,000.00	0%	\$0.00	0%	\$0.00
262	Valve #262	100%	Lump Sum	\$15,900.00	\$15,900.00	100%	\$15,900.00	100%	\$15,900.00	100%	\$15,900.00	0%	\$0.00	0%	\$0.00
263	Valve #263	100%	Lump Sum	\$17,000.00	\$17,000.00	100%	\$17,000.00	100%	\$17,000.00	100%	\$17,000.00	0%	\$0.00	0%	\$0.00
264	Valve #264	100%	Lump Sum	\$11,800.00	\$11,800.00	100%	\$11,800.00	100%	\$11,800.00	100%	\$11,800.00	0%	\$0.00	0%	\$0.00
265	Valve #265	100%	Lump Sum	\$16,200.00	\$16,200.00	0%	\$0.00	0%	\$0.00	100%	\$11,800.00	0%	\$0.00	0%	\$0.00
266	Valve #266	100%	Lump Sum	\$11,400.00	\$11,400.00	100%	\$11,400.00	100%	\$0.00	0%	\$0.00	0%	\$0.00	0%	\$0.00
267	Valve #267	100%	Lump Sum	\$12,100.00	\$12,100.00	100%	\$12,100.00	100%	\$11,400.00	100%	\$11,400.00	0%	\$0.00	0%	\$0.00
268	Valve #268	100%	Lump Sum	\$19,100.00	\$19,100.00	100%	\$19,100.00	100%	\$12,100.00	100%	\$12,100.00	0%	\$0.00	0%	\$0.00
269	Valve #269	100%	Lump Sum	\$29,200.00	\$29,200.00	100%	\$29,200.00	100%	\$19,100.00	100%	\$19,100.00	0%	\$0.00	0%	\$0.00
270	Valve #270	100%	Lump Sum	\$28,700.00	\$28,700.00	100%	\$28,700.00	100%	\$29,200.00	100%	\$29,200.00	0%	\$0.00	0%	\$0.00
271	Valve #271	100%	Lump Sum	\$15,600.00	\$15,600.00	100%	\$15,600.00	100%	\$28,700.00	100%	\$28,700.00	0%	\$0.00	0%	\$0.00
272	Valve #272	100%	Lump Sum	\$15,600.00	\$15,600.00	100%	\$15,600.00	100%	\$15,600.00	100%	\$15,600.00	0%	\$0.00	0%	\$0.00
273	Valve #273	100%	Lump Sum	\$17,400.00	\$17,400.00	100%	\$17,400.00	100%	\$15,600.00	100%	\$15,600.00	0%	\$0.00	0%	\$0.00
274	Valve #274	100%	Lump Sum	\$15,800.00	\$15,800.00	100%	\$15,800.00	100%	\$17,400.00	100%	\$17,400.00	0%	\$0.00	0%	\$0.00
275	Valve #275	100%	Lump Sum	\$25,900.00	\$25,900.00	100%	\$25,900.00	100%	\$15,800.00	100%	\$15,800.00	0%	\$0.00	0%	\$0.00
276	Valve #276	100%	Lump Sum	\$16,700.00	\$16,700.00	100%	\$16,700.00	100%	\$25,900.00	100%	\$25,900.00	0%	\$0.00	0%	\$0.00
277	Valve #277	100%	Lump Sum	\$0.00	\$0.00	100%	\$0.00	0%	\$16,700.00	100%	\$16,700.00	0%	\$0.00	0%	\$0.00
278	Valve #278	100%	Lump Sum	\$15,800.00	\$15,800.00	100%	\$15,800.00	100%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$0.00
279	Valve #279	100%	Lump Sum	\$16,200.00	\$16,200.00	100%	\$16,200.00	100%	\$15,800.00	100%	\$15,800.00	0%	\$0.00	0%	\$0.00
280	Valve #280	100%	Lump Sum	\$19,300.00	\$19,300.00	100%	\$19,300.00	100%	\$16,200.00	100%	\$16,200.00	0%	\$0.00	0%	\$0.00
281	Valve #281	100%	Lump Sum	\$25,200.00	\$25,200.00	100%	\$25,200.00	100%	\$19,300.00	100%	\$19,300.00	0%	\$0.00	0%	\$0.00
282	Valve #282	100%	Lump Sum	\$14,400.00	\$14,400.00	100%	\$14,400.00	100%	\$25,200.00	100%	\$25,200.00	0%	\$0.00	0%	\$0.00
283	Valve #283	100%	Lump Sum	\$25,800.00	\$25,800.00	100%	\$25,800.00	100%	\$14,400.00	100%	\$14,400.00	0%	\$0.00	0%	\$0.00
284	Valve #284	100%	Lump Sum	\$25,400.00	\$25,400.00	100%	\$25,400.00	100%	\$25,800.00	100%	\$25,800.00	0%	\$0.00	0%	\$0.00
285	Valve #285	100%	Lump Sum	\$30,700.00	\$30,700.00	100%	\$30,700.00	100%	\$25,400.00	100%	\$25,400.00	0%	\$0.00	0%	\$0.00
286	Valve #286	100%	Lump Sum	\$12,500.00	\$12,500.00	100%	\$12,500.00	100%	\$30,700.00	100%	\$30,700.00	0%	\$0.00	0%	\$0.00
287	Valve #287	100%	Lump Sum	\$15,700.00	\$15,700.00	100%	\$15,700.00	100%	\$12,500.00	100%	\$12,500.00	0%	\$0.00	0%	\$0.00
288	Valve #288	100%	Lump Sum	\$16,600.00	\$16,600.00	100%	\$16,600.00	100%	\$15,700.00	100%	\$15,700.00	0%	\$0.00	0%	\$0.00
289	Valve #289	100%	Lump Sum	\$0.00	\$0.00	100%	\$0.00	0%	\$16,600.00	100%	\$16,600.00	0%	\$0.00	0%	\$0.00
290	Valve #290	100%	Lump Sum	\$16,400.00	\$16,400.00	100%	\$16,400.00	100%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$0.00
291	Valve #291	100%	Lump Sum	\$19,700.00	\$19,700.00	100%	\$19,700.00	100%	\$16,400.00	100%	\$16,400.00	0%	\$0.00	0%	\$0.00
292	Valve #292	100%	Lump Sum	\$16,500.00	\$16,500.00	100%	\$16,500.00	100%	\$19,700.00	100%	\$19,700.00	0%	\$0.00	0%	\$0.00
293	Valve #293	100%	Lump Sum	\$16,400.00	\$16,400.00	100%	\$16,400.00	100%	\$16,500.00	100%	\$16,500.00	0%	\$0.00	0%	\$0.00
294	Valve #294	100%	Lump Sum	\$15,000.00	\$15,000.00	100%	\$15,000.00	100%	\$16,400.00	100%	\$16,400.00	0%	\$0.00	0%	\$0.00
295	Valve #295	100%	Lump Sum	\$16,100.00	\$16,100.00	100%	\$16,100.00	100%	\$15,000.00	100%	\$15,000.00	0%	\$0.00	0%	\$0.00
296	Valve #296	100%	Lump Sum	\$15,900.00	\$15,900.00	100%	\$15,900.00	100%	\$16,100.00	100%	\$16,100.00	0%	\$0.00	0%	\$0.00
297	Valve #297	100%	Lump Sum	\$16,100.00	\$16,100.00	100%	\$16,100.00	100%	\$15,900.00	100%	\$15,900.00	0%	\$0.00	0%	\$0.00
298	Valve #298	100%	Lump Sum	\$16,200.00	\$16,200.00	100%	\$16,200.00	100%	\$16,100.00	100%	\$16,100.00	0%	\$0.00	0%	\$0.00
299	Valve #299	100%	Lump Sum	\$16,400.00	\$16,400.00	100%	\$16,400.00	100%	\$16,200.00	100%	\$16,200.00	0%	\$0.00	0%	\$0.00
300	Valve #300	100%	Lump Sum	\$13,900.00	\$13,900.00	100%	\$13,900.00	100%	\$16,400.00	100%	\$16,400.00	0%	\$0.00	0%	\$0.00
301	Valve #301	100%	Lump Sum	\$15,600.00	\$15,600.00	100%	\$15,600.00	100%	\$13,900.00	100%	\$13,900.00	0%	\$0.00	0%	\$0.00
302	Valve #302	100%	Lump Sum	\$14,900.00	\$14,900.00	100%	\$14,900.00	100%	\$15,600.00	100%	\$15,600.00	0%	\$0.00	0%	\$0.00
303	Valve #303	100%	Lump Sum	\$14,800.00	\$14,800.00	100%	\$14,800.00	100%	\$14,900.00	100%	\$14,900.00	0%	\$0.00	0%	\$0.00
304	Valve #304	100%	Lump Sum	\$16,300.00	\$16,300.00	100%	\$16,300.00	100%	\$14,800.00	100%	\$14,800.00	0%	\$0.00	0%	\$0.00
305	Valve #305	100%	Lump Sum	\$20,100.00	\$20,100.00	100%	\$20,100.00	100%	\$16,300.00	100%	\$16,300.00	0%	\$0.00	0%	\$0.00
306	Valve #306	100%	Lump Sum	\$16,600.00	\$16,600.00	100%	\$16,600.00	100%	\$20,100.00	100%	\$20,100.00	0%	\$0.00	0%	\$0.00
307	Valve #307	100%	Lump Sum	\$15,500.00	\$15,500.00	100%	\$15,500.00	100%	\$16,600.00	100%	\$16,600.00	0%	\$0.00	0%	\$0.00
308	Valve #308	100%	Lump Sum	\$13,100.00	\$13,100.00	100%	\$13,100.00	100%	\$15,500.00	100%	\$15,500.00	0%	\$0.00	0%	\$0.00
309	Valve #309	100%	Lump Sum	\$16,100.00	\$16,100.00	100%	\$16,100.00	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	\$13,100.00
310	Valve #310	100%	Lump Sum	\$15,300.00	\$15,300.00	100%	\$15,300.00	100%	\$16,100.00	100%	\$16,100.00	0%	\$0.00	0%	\$0.00
311	Valve #311	100%	Lump Sum	\$15,500.00	\$15,500.00	100%	\$15,500.00	100%	\$15,300.00	100%	\$15,300.00	0%	\$0.00	0%	\$0.00

ROSSI CONTRACTORS
201 WEST LAKE STREET
NORTHLAKE, ILLINOIS 60164

ACCOUNT # AMOUNT
WF-6631 \$109,349.78
WF-3520 (\$10,934.98)
WF-3530 (\$840.00)

#	ITEM	ORIGINAL CONTRACT QUANTITY	UNIT	UNIT PRICE	ORIGINAL CONTRACT PRICE	AMENDED CONTRACT QUANTITY	AMENDED CONTRACT PRICE	CURRENT QUANTITY	TO DATE EXTENSION	PREVIOUS QUANTITY	PAYMENT EXTENSION	THIS QUANTITY	PAYMENT EXTENSION	CONTRACT QUANTITY	BALANCE EXTENSION
317	Valve #317	100%	Lump Sum	\$13,500.00	\$13,500.00	100%	\$13,500.00	100%	\$13,500.00	100%	\$13,500.00	0%	\$0.00	0%	\$0.00
318	Valve #318	100%	Lump Sum	\$12,700.00	\$12,700.00	100%	\$12,700.00	100%	\$12,700.00	100%	\$12,700.00	0%	\$0.00	0%	\$0.00
319	Valve #319	100%	Lump Sum	\$17,600.00	\$17,600.00	100%	\$17,600.00	100%	\$17,600.00	100%	\$17,600.00	0%	\$0.00	0%	\$0.00
320	Valve #320	100%	Lump Sum	\$11,200.00	\$11,200.00	100%	\$11,200.00	100%	\$11,200.00	100%	\$11,200.00	0%	\$0.00	0%	\$0.00
321	Valve #321	100%	Lump Sum	\$13,300.00	\$13,300.00	100%	\$13,300.00	100%	\$13,300.00	100%	\$13,300.00	0%	\$0.00	0%	\$0.00
322	Valve #322	100%	Lump Sum	\$15,300.00	\$15,300.00	100%	\$15,300.00	100%	\$15,300.00	100%	\$15,300.00	0%	\$0.00	0%	\$0.00
323	Valve #323	100%	Lump Sum	\$13,100.00	\$13,100.00	100%	\$13,100.00	100%	\$13,100.00	100%	\$13,100.00	0%	\$0.00	0%	\$0.00
324	Valve #324	100%	Lump Sum	\$16,300.00	\$16,300.00	100%	\$16,300.00	100%	\$16,300.00	100%	\$16,300.00	0%	\$0.00	0%	\$0.00
325	Valve #325	100%	Lump Sum	\$16,800.00	\$16,800.00	100%	\$16,800.00	100%	\$16,800.00	100%	\$16,800.00	0%	\$0.00	0%	\$0.00
326	Valve #326	100%	Lump Sum	\$15,800.00	\$15,800.00	100%	\$15,800.00	100%	\$15,800.00	100%	\$15,800.00	0%	\$0.00	0%	\$0.00
327	Valve #327	100%	Lump Sum	\$16,400.00	\$16,400.00	100%	\$16,400.00	100%	\$16,400.00	100%	\$15,800.00	0%	\$0.00	0%	\$0.00
328	Valve #328	100%	Lump Sum	\$31,200.00	\$31,200.00	100%	\$31,200.00	100%	\$31,200.00	100%	\$31,200.00	0%	\$0.00	0%	\$0.00
329	Valve #329	100%	Lump Sum	\$11,800.00	\$11,800.00	100%	\$11,800.00	100%	\$11,800.00	100%	\$31,200.00	0%	\$0.00	0%	\$0.00
330	Valve #330	100%	Lump Sum	\$20,400.00	\$20,400.00	100%	\$20,400.00	100%	\$20,400.00	100%	\$11,800.00	0%	\$0.00	0%	\$0.00
331	Valve #331	100%	Lump Sum	\$15,500.00	\$15,500.00	100%	\$15,500.00	100%	\$15,500.00	100%	\$20,400.00	0%	\$0.00	0%	\$0.00
332	Valve #332	100%	Lump Sum	\$15,600.00	\$15,600.00	100%	\$15,600.00	100%	\$15,600.00	100%	\$15,500.00	0%	\$0.00	0%	\$0.00
333	Valve #333	100%	Lump Sum	\$12,300.00	\$12,300.00	100%	\$12,300.00	100%	\$12,300.00	100%	\$15,600.00	0%	\$0.00	0%	\$0.00
334	Valve #334	100%	Lump Sum	\$11,300.00	\$11,300.00	100%	\$11,300.00	100%	\$11,300.00	100%	\$12,300.00	0%	\$0.00	0%	\$0.00
335	Valve #335	100%	Lump Sum	\$16,300.00	\$16,300.00	100%	\$16,300.00	100%	\$16,300.00	100%	\$11,300.00	0%	\$0.00	0%	\$0.00
336	Valve #336	100%	Lump Sum	\$16,500.00	\$16,500.00	100%	\$16,500.00	100%	\$16,500.00	100%	\$16,300.00	0%	\$0.00	0%	\$0.00
337	Valve #337	100%	Lump Sum	\$16,100.00	\$16,100.00	100%	\$16,100.00	100%	\$16,100.00	100%	\$16,500.00	0%	\$0.00	0%	\$0.00
338	Valve #338	100%	Lump Sum	\$12,500.00	\$12,500.00	100%	\$12,500.00	100%	\$12,500.00	100%	\$16,100.00	0%	\$0.00	0%	\$0.00
339	Valve #339	100%	Lump Sum	\$16,200.00	\$16,200.00	100%	\$16,200.00	100%	\$16,200.00	100%	\$12,500.00	0%	\$0.00	0%	\$0.00
340	Valve #340	100%	Lump Sum	\$15,000.00	\$15,000.00	100%	\$15,000.00	100%	\$15,000.00	100%	\$16,200.00	0%	\$0.00	0%	\$0.00
341	Valve #341	100%	Lump Sum	\$24,800.00	\$24,800.00	100%	\$24,800.00	100%	\$24,800.00	100%	\$15,000.00	0%	\$0.00	0%	\$0.00
342	Valve #342	100%	Lump Sum	\$15,600.00	\$15,600.00	100%	\$15,600.00	100%	\$15,600.00	100%	\$24,800.00	0%	\$0.00	0%	\$0.00
343	Valve #343	100%	Lump Sum	\$13,000.00	\$13,000.00	100%	\$13,000.00	100%	\$13,000.00	100%	\$15,600.00	0%	\$0.00	0%	\$0.00
344	Valve #344	100%	Lump Sum	\$15,800.00	\$15,800.00	100%	\$15,800.00	100%	\$15,800.00	100%	\$13,000.00	0%	\$0.00	0%	\$0.00
345	Valve #345	100%	Lump Sum	\$11,600.00	\$11,600.00	100%	\$11,600.00	100%	\$11,600.00	100%	\$15,800.00	0%	\$0.00	0%	\$0.00
346	Valve #346	100%	Lump Sum	\$11,900.00	\$11,900.00	100%	\$11,900.00	100%	\$11,900.00	100%	\$11,600.00	0%	\$0.00	0%	\$0.00
347	Valve #347	100%	Lump Sum	\$21,200.00	\$21,200.00	100%	\$21,200.00	100%	\$21,200.00	100%	\$11,900.00	0%	\$0.00	0%	\$0.00
348	Valve #348	100%	Lump Sum	\$16,300.00	\$16,300.00	100%	\$16,300.00	100%	\$16,300.00	100%	\$21,200.00	0%	\$0.00	0%	\$0.00
349	Valve #349	100%	Lump Sum	\$28,700.00	\$28,700.00	100%	\$28,700.00	100%	\$28,700.00	100%	\$16,300.00	0%	\$0.00	0%	\$0.00
350	Valve #350	100%	Lump Sum	\$16,400.00	\$16,400.00	100%	\$16,400.00	100%	\$16,400.00	100%	\$28,700.00	0%	\$0.00	0%	\$0.00
351	Valve #351	100%	Lump Sum	\$16,100.00	\$16,100.00	100%	\$16,100.00	100%	\$16,100.00	100%	\$16,400.00	0%	\$0.00	0%	\$0.00
352	Valve #352	100%	Lump Sum	\$15,200.00	\$15,200.00	100%	\$15,200.00	100%	\$15,200.00	100%	\$16,100.00	0%	\$0.00	0%	\$0.00
353	Valve #353	100%	Lump Sum	\$16,100.00	\$16,100.00	100%	\$16,100.00	100%	\$16,100.00	100%	\$15,200.00	0%	\$0.00	0%	\$0.00
354	Valve #354	100%	Lump Sum	\$14,600.00	\$14,600.00	100%	\$14,600.00	100%	\$14,600.00	100%	\$16,100.00	0%	\$0.00	0%	\$0.00
355	Valve #355	100%	Lump Sum	\$36,300.00	\$36,300.00	100%	\$36,300.00	100%	\$36,300.00	100%	\$14,600.00	0%	\$0.00	0%	\$0.00
356	Valve #356	100%	Lump Sum	\$26,900.00	\$26,900.00	100%	\$26,900.00	100%	\$26,900.00	100%	\$36,300.00	0%	\$0.00	0%	\$0.00
357	Valve #357	100%	Lump Sum	\$15,800.00	\$15,800.00	100%	\$15,800.00	100%	\$15,800.00	100%	\$26,900.00	0%	\$0.00	0%	\$0.00
358	Valve #358	100%	Lump Sum	\$16,500.00	\$16,500.00	100%	\$16,500.00	100%	\$16,500.00	100%	\$15,800.00	0%	\$0.00	0%	\$0.00
359	Valve #359	100%	Lump Sum	\$15,500.00	\$15,500.00	100%	\$15,500.00	100%	\$15,500.00	100%	\$16,500.00	0%	\$0.00	0%	\$0.00
360	Valve #360	100%	Lump Sum	\$12,300.00	\$12,300.00	100%	\$12,300.00	100%	\$12,300.00	100%	\$15,500.00	0%	\$0.00	0%	\$0.00
361	Valve #361	100%	Lump Sum	\$16,300.00	\$16,300.00	100%	\$16,300.00	100%	\$16,300.00	100%	\$12,300.00	0%	\$0.00	0%	\$0.00
362	Valve #362	100%	Lump Sum	\$19,000.00	\$19,000.00	100%	\$19,000.00	100%	\$19,000.00	100%	\$16,300.00	0%	\$0.00	0%	\$0.00
363	Valve #363	100%	Lump Sum	\$0.00	\$0.00	100%	\$0.00	0%	\$0.00	0%	\$19,000.00	0%	\$0.00	0%	\$0.00
364	Valve #364	100%	Lump Sum	\$15,900.00	\$15,900.00	100%	\$15,900.00	100%	\$15,900.00	100%	\$0.00	0%	\$0.00	100%	\$0.00
365	Valve #365	100%	Lump Sum	\$16,100.00	\$16,100.00	100%	\$16,100.00	100%	\$16,100.00	100%	\$15,900.00	0%	\$0.00	0%	\$0.00
366	Valve #366	100%	Lump Sum	\$28,400.00	\$28,400.00	100%	\$28,400.00	100%	\$28,400.00	100%	\$16,100.00	0%	\$0.00	0%	\$0.00
367	Valve #367	100%	Lump Sum	\$15,500.00	\$15,500.00	100%	\$15,500.00	100%	\$15,500.00	100%	\$28,400.00	0%	\$0.00	0%	\$0.00
368	Valve #368	100%	Lump Sum	\$0.00	\$0.00	100%	\$0.00	0%	\$0.00	0%	\$15,500.00	0%	\$0.00	0%	\$0.00
369	Valve #369	100%	Lump Sum	\$12,900.00	\$12,900.00	100%	\$12,900.00	100%	\$12,900.00	100%	\$0.00	0%	\$0.00	100%	\$0.00
370	Valve #370	100%	Lump Sum	\$25,500.00	\$25,500.00	100%	\$25,500.00	100%	\$25,500.00	100%	\$12,900.00	0%	\$0.00	0%	\$0.00
371	Valve #371	100%	Lump Sum	\$11,900.00	\$11,900.00	100%	\$11,900.00	100%	\$11,900.00	100%	\$25,500.00	0%	\$0.00	0%	\$0.00
372	Valve #372	100%	Lump Sum	\$15,700.00	\$15,700.00	100%	\$15,700.00	100%	\$15,700.00	100%	\$11,900.00	0%	\$0.00	0%	\$0.00
373	Valve #373	100%	Lump Sum	\$20,600.00	\$20,600.00	100%	\$20,600.00	100%	\$20,600.00	100%	\$15,700.00	0%	\$0.00	0%	\$0.00
374	Valve #374	100%	Lump Sum	\$12,300.00	\$12,300.00	100%	\$12,300.00	100%	\$12,300.00	100%	\$20,600.00	0%	\$0.00	0%	\$0.00
375	Valve #375	100%	Lump Sum	\$11,900.00	\$11,900.00	100%	\$11,900.00	100%	\$11,900.00	100%	\$12,300.00	0%	\$0.00	0%	\$0.00
376	Valve #376	100%	Lump Sum	\$15,900.00	\$15,900.00	100%	\$15,900.00	100%	\$15,900.00	100%	\$11,900.00	0%	\$0.00	0%	\$0.00
377	Valve #377	100%	Lump Sum	\$26,100.00	\$26,100.00	100%	\$26,100.00	100%	\$26,100.00	100%	\$15,900.00	0%	\$0.00	0%	\$0.00
378	Valve #378	100%	Lump Sum	\$13,700.00	\$13,700.00	100%	\$13,700.00	100%	\$13,700.00	100%	\$26,100.00	0%	\$0.00	0%	\$0.00
379	Valve #379	100%	Lump Sum	\$17,200.00	\$17,200.00	100%	\$17,200.00	100%	\$17,200.00	100%	\$13,700.00	0%	\$0.00	0%	\$0.00
380	Valve #380	100%	Lump Sum	\$12,500.00	\$12,500.00	100%	\$12,500.00	100%	\$12,500.00	100%	\$17,200.00	0%	\$0.00	0%	\$0.00
381	Valve #381	100%	Lump Sum	\$47,900.00	\$47,900.00	100%	\$47,900.00	100%	\$47,900.00	100%	\$12,500.00	0%	\$0.00	0%	\$0.00
382	Valve #382	100%	Lump Sum	\$18,800.00	\$18,800.00	100%	\$18,800.00	100%	\$18,800.00	100%	\$47,900.00	0%	\$0.00	0%	\$0.00
383	Valve #383	100%	Lump Sum	\$12,600.00	\$12,600.00	100%	\$12,600.00	100%	\$12,600.00	100%	\$18,800.00	0%	\$0.00	0%	\$0.00
384	Valve #384	100%	Lump Sum	\$14,900.00	\$14,900.00	100%	\$14,900.00	100%	\$14,900.00	100%	\$12,600.00	0%	\$0.00	0%	\$0.00
385	Valve #385	100%	Lump Sum	\$13,300.00	\$13,300.00	100%	\$13,300.00	100%	\$13,300.00	100%	\$14,900.00	0%	\$0.00	0%	\$0.00
386	Valve #386	100%	Lump Sum	\$47,800.00	\$47,800.00	100%	\$47,800.00	100%	\$47,800.00	100%	\$13,300.00	0%	\$0.00	0%	\$0.00
387	Step 8 - Dewatering of Owner's Water Main	1,700,000	C.F.	\$0.18	\$306,000.00	1,700,000	\$306,000.00	276,013	\$49,682.34	276,013	\$49,682.34	0	\$0.00	1,423,987	\$256,317.66
388	Step 6 - Repair Exterior Leakage of Resilient Wedge Valve	35	EA.	\$2,048.00	\$71,680.00	35	\$71,680.00	39	\$79,872.00	39	\$79,872.00	0	\$0.00	(4)	(\$8,192.00)
389	Step 3 - Retirement of Resilient Wedge Valve	20	EA.	\$2,093.00	\$41,860.00	20	\$41,860.00	0	\$0.00	0	\$0.00	0	\$0.00	20	\$41,860.00
390	Step 7 - Remove and Replace 6" Resilient Wedge Valves	20	EA.	\$2,650.00	\$53										

BLOW OFF VALVE REPAIR (BOV-1)

DATE 07/30/04

ROSSI CONTRACTORS
201 WEST LAKE STREET
NORTHLAKE, ILLINOIS 60164

ACCOUNT # AMOUNT
WF-6631 \$109,349.78
WF-3520 (\$10,934.98)
WF-3530 (\$840.00)

#	ITEM	ORIGINAL CONTRACT QUANTITY	UNIT	UNIT PRICE	ORIGINAL CONTRACT PRICE	AMENDED CONTRACT QUANTITY	AMENDED CONTRACT PRICE	CURRENT QUANTITY	TO DATE EXTENSION	PREVIOUS QUANTITY	PAYMENT EXTENSION	THIS QUANTITY	PAYMENT EXTENSION	CONTRACT QUANTITY	BALANCE EXTENSION
391	Step 7 - Remove and Replace 8" Resilient Wedge Valves	20	EA.	\$2,945.00	\$58,900.00	20	\$58,900.00	2	\$5,890.00	2	\$5,890.00	0	\$0.00	18	\$53,010.00
392	Step 7 - Remove and Replace 12" Resilient Wedge Valves	20	EA.	\$3,661.00	\$73,220.00	20	\$73,220.00	0	\$0.00	0	\$0.00	0	\$0.00	20	\$73,220.00
393	Step 5 - Remove and Replace Valve and Piping Joint Bolts	18	EA.	\$2,200.00	\$39,600.00	18	\$39,600.00	3	\$6,600.00	3	\$6,600.00	0	\$0.00	15	\$33,000.00
394	Initial Anodes for Corrosion Control	965	EA.	\$1.00	\$965.00	965	\$965.00	796	\$796.00	787	\$787.00	9	\$9.00	169	\$169.00
395	Traffic Control and Protection	354	EA.	\$789.19	\$279,375.00	344	\$271,483.00	341	\$269,115.47	337	\$265,958.69	4	\$3,156.78	3	\$2,367.53
396	Additional Anodes for Corrosion Control	60	EA.	\$1.00	\$60.00	60	\$60.00	0	\$0.00	0	\$0.00	0	\$0.00	60	\$60.00
397	Repair of Damage to exterior coating of prestress conc pipe	250	S.F.	\$230.00	\$57,500.00	250	\$57,500.00	31	\$7,222.00	31	\$7,222.00	0	\$0.00	219	\$50,278.00
I-1	Granular Foundation Material	1,000	C.Y.	\$30.80	\$30,800.00	1,000	\$30,800.00	0	\$0.00	0	\$0.00	0	\$0.00	1,000	\$30,800.00
I-2	Class "SI" Concrete	100	C.Y.	\$100.00	\$10,000.00	100	\$10,000.00	0	\$0.00	0	\$0.00	0	\$0.00	100	\$10,000.00
I-3	Class B Concrete	100	C.Y.	\$80.00	\$8,000.00	100	\$8,000.00	0	\$0.00	0	\$0.00	0	\$0.00	100	\$8,000.00
I-4	Extension Stem	70	EA.	\$342.00	\$23,940.00	70	\$23,940.00	70	\$23,940.00	70	\$23,940.00	0	\$0.00	0	\$0.00
I-5	Valve Box with Cover	15	EA.	\$469.00	\$7,035.00	15	\$7,035.00	15	\$7,035.00	15	\$7,035.00	0	\$0.00	0	\$0.00
I-6	Valve Box Cover	50	EA.	\$100.00	\$5,000.00	50	\$5,000.00	2	\$200.00	2	\$200.00	0	\$0.00	48	\$4,800.00
I-7	Pavement, remove & replace--portland cement concrete surface	15	S.Y.	\$200.00	\$3,000.00	15	\$3,000.00	6	\$1,155.56	6	\$1,155.56	0	\$0.00	9	\$1,844.44
I-8	Pavement, remove & replace--bituminous concrete surface--Rigid Base	15	S.Y.	\$100.00	\$1,500.00	15	\$1,500.00	0	\$0.00	0	\$0.00	0	\$0.00	15	\$1,500.00
I-9	Pavement, remove & replace--bituminous concrete surface--Flexible Base (B.A.M.)	15	S.Y.	\$100.00	\$1,500.00	15	\$1,500.00	0	\$0.00	0	\$0.00	0	\$0.00	15	\$1,500.00
I-10	Pavement, remove & replace--bituminous concrete surface--Flexible Base (Aggregate)	15	S.Y.	\$100.00	\$1,500.00	15	\$1,500.00	0	\$0.00	0	\$0.00	0	\$0.00	15	\$1,500.00
CO 1	Extra lead wire	0	L.F.	\$2.00	\$0.00	354	\$708.00	341	\$682.00	337	\$674.00	4	\$8.00	13	\$26.00
CO 1	Silicone around junction box and installation of box into frame and lid	0	L.F.	\$3.00	\$0.00	354	\$1,062.00	341	\$1,023.00	337	\$1,011.00	4	\$12.00	13	\$39.00
CO 2	Additional valve boxes	0	EA.	\$469.00	\$0.00	100	\$46,900.00	100	\$46,900.00	100	\$46,900.00	0	\$0.00	0	\$0.00
CO 3	Delete valves #6, 12, 100, 101, 116, 123, 126, 221, 227 and deletes 9 of 354 traffic control sites				Items 6, 12, 100, 101, 116, 123, 126, 221, 227, and 395 adjusted above										
CO 4	Additional Valve Boxes and Covers	0	EA.	\$469.00	\$0.00	100	\$46,900.00	45	\$21,105.00	44	\$20,636.00	1	\$469.00	55	\$25,795.00
CO 4	Additional Valve Stems	0	EA.	\$342.00	\$0.00	100	\$34,200.00	56	\$19,152.00	54	\$18,468.00	2	\$684.00	44	\$15,048.00
CO 5	Repair 16" Conc. Pipe: Site #259	0%	Lump Sum	\$4,841.30	\$0.00	100%	\$4,841.30	1	\$4,841.30	1	\$4,841.30	0	\$0.00	0	\$0.00
CO 6	Delete valves #49, 117, 265, 87 and 1 Traffic Control Site.				Items 49, 117, 265, 87, and 395 adjusted above										
CO 6	Valve #387	0%	Lump Sum	\$18,400.00	\$0.00	100%	\$18,400.00	100%	\$18,400.00	100%	\$18,400.00	0%	\$0.00	0%	\$0.00
CO 6	Valve #388	0%	Lump Sum	\$24,500.00	\$0.00	100%	\$24,500.00	100%	\$24,500.00	100%	\$24,500.00	0%	\$0.00	0%	\$0.00
CO 6	Valve #389	0%	Lump Sum	\$27,900.00	\$0.00	100%	\$27,900.00	100%	\$27,900.00	100%	\$27,900.00	0%	\$0.00	0%	\$0.00
CO 7	Site #129 PipeTape Repair	0%	Lump Sum	\$9,359.24	\$0.00	100%	\$9,359.24	100%	\$9,359.24	100%	\$9,359.24	0%	\$0.00	0%	\$0.00
CO 8	Site #148 PipeTape Repair	0%	Lump Sum	\$5,765.86	\$0.00	100%	\$5,765.86	100%	\$5,765.86	100%	\$5,765.86	0%	\$0.00	0%	\$0.00
CO 9	Step 6 - Repair Exterior Leakage of Resilient Wedge Valve	0%	Lump Sum	\$20,480.00	\$0.00	100%	\$20,480.00	70%	\$14,336.00	30%	\$6,144.00	40%	\$8,192.00	30%	\$6,144.00
CO 10	Delete Valve #308 & #220 & traffic control	0%	Lump Sum	(\$30,678.40)	\$0.00	100%	(\$30,678.40)	0%	\$0.00	0%	\$0.00	0%	\$0.00	100%	(\$30,678.40)
CO 11	Asphalt restoration in Bensenville	0%	Lump Sum	\$18,419.00	\$0.00	100%	\$18,419.00	100%	\$18,419.00	0%	\$0.00	100%	\$18,419.00	0%	\$0.00
CO 12	Additional concrete work Valves #1-#7	0	S.Y.	\$200.00	\$0.00	50	\$10,000.00	48	\$9,600.00	0	\$0.00	48	\$9,600.00	2	\$400.00

WEST TRANSMISSION MAIN (TIB-1)

DATE 07/30/04

ROSSI CONTRACTORS
201 WEST LAKE STREET
NORTHLAKE, ILLINOIS 60164ACCOUNT # AMOUNT
WF-7590 \$1,395,820.35
WF-3520 (\$139,582.04)
WF-3530 (\$840.00)

#	ITEM	ORIGINAL CONTRACT QUANTITY	UNIT	UNIT PRICE	ORIGINAL CONTRACT PRICE	AMENDED CONTRACT QUANTITY	AMENDED CONTRACT PRICE	CURRENT QUANTITY	TO DATE EXTENSION	PREVIOUS QUANTITY	PAYMENT EXTENSION	THIS QUANTITY	PAYMENT EXTENSION	CONTRACT QUANTITY	BALANCE EXTENSION
64	ZINC ANODES	550.00	EA.	\$1.07	\$588.50	550.00	\$588.50	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	550.00	\$588.50
65	HEADER CABLE	20,000.00	FT	\$1.07	\$21,400.00	20,000.00	\$21,400.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	20,000.00	\$21,400.00
66	REMOVAL & DISPOSAL OF PETROLEUM CONTAMINATED SOIL	1,000.00	C. Y.	\$101.65	\$101,650.00	1,000.00	\$101,650.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	1,000.00	\$101,650.00
ROCK TUNNEL & PIPE UNDER SALT CREEK															
67	72-IN DIA STEEL PIPE IN ROCK TUN & SHAFT	1,375.00	L. F.	\$810.12	\$1,113,915.00	1,375.00	\$1,113,915.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	1,375.00	\$1,113,915.00
68	84-IN MINIMUM DIA ROCK TUNNEL	1,190.00	L. F.	\$2,549.81	\$3,034,273.90	1,190.00	\$3,034,273.90	842.00	\$2,146,940.02	302.00	\$770,042.62	540.00	\$1,376,897.40	348.00	\$887,333.88
CO#01	ADDITION														
	1. 8" DI WATER MAIN	0.00	L. F.	\$49.21	\$0.00	975.00	\$47,979.75	961.00	\$47,290.81	961.00	\$47,290.81	0.00	\$0.00	14.00	\$688.94
	2. 8" GATE VALVE IN VALVE BOX	0.00	EA	\$3,957.84	\$0.00	3.00	\$11,873.52	3.00	\$11,873.52	3.00	\$11,873.52	0.00	\$0.00	0.00	\$0.00
	3. 8" GATE VALVE IN VALVE VAULT	0.00	EA	\$4,257.84	\$0.00	3.00	\$12,773.52	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	3.00	\$12,773.52
	4. 6" GATE VALVE IN VALVE VAULT	0.00	EA	\$4,057.84	\$0.00	5.00	\$20,289.20	1.00	\$4,057.84	1.00	\$4,057.84	0.00	\$0.00	4.00	\$16,231.36
	1. AMEND QTY OF ITEM # 40 ABOVE														
	2. AMEND QTY OF ITEM # 41 ABOVE														
CO#02	AMEND QTY OF ITEM NOS. 27 & 28 ABOVE														
CO#03	REMOVE & DISPOSE 16" WEST SHORE PIPE	0.00	L.F.	\$28.00	\$0.00	3,100.00	\$86,800.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	3,100.00	\$86,800.00
CO#04	ADDITION														
	1. AMEND QTY OF ITEM NOS. 2 & 3 ABOVE														
	DEDUCTION														
	1. AMEND QTY OF ITEM NOS. 1, 23, 19, 18 & 24	0.00	S.Y.	\$20.33	\$0.00	(1,287.00)	(\$26,164.71)	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	(1,287.00)	(\$26,164.71)
CO#05	1. AMEND QTY OF ITEM NO. 40 ABOVE														
	2. AMEND QTY OF LINE ITEM NO.1 OF CO#01														
CO#06	WELD AADDITIONAL JOINTS OF 72" PIPE	0.00	EA	\$1,275.00	\$0.00	235.00	\$299,625.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	235.00	\$299,625.00
CONTRACT SUB-TOTALS					\$12,730,597.31		\$13,362,702.11		\$2,574,123.66		\$1,178,303.31		\$1,395,820.35		\$10,788,578.45
RETENTION					10.00%				(\$257,412.37)		(\$117,830.33)		(\$139,582.04)		\$257,412.37
CONTRACT TOTALS									\$2,316,711.29		\$1,060,472.98		\$1,256,238.31		\$11,045,990.82
EXCESS DEDUCTS/BONUS															
	1X EXCESS ENGINEERING COSTS-ABH		HRS.	(\$60.00)				39.00	(\$2,340.00)	25.00	(\$1,500.00)	14.00	(\$840.00)		
	2X EXCESS ENGINEERING COSTS-DWC		HRS.	(\$60.00)				0.00	\$0.00	0.00	\$0.00	0.00	\$0.00		
NET PAYMENT TO CONTRACTOR									\$2,314,371.29		\$1,058,972.98		\$1,255,398.31		
CHANGE ORDER PERCENTAGE									4.97%						

STAFF APPROVALS	
ENGINEERING	<i>SAC</i>
ACCOUNTING	<i>CRJ</i>

WEST TRANSMISSION MAIN

(TIB-1)

ROSSI CONTRACTORS
201 WEST LAKE STREET
NORTHLAKE, ILLINOIS 60164

DATE 07/30/04

ACCOUNT # AMOUNT
WF-7590 \$1,395,820.35
WF-3520 (\$139,582.04)
WF-3530 (\$840.00)

#	ITEM	ORIGINAL CONTRACT QUANTITY	UNIT	UNIT PRICE	ORIGINAL CONTRACT PRICE	AMENDED CONTRACT QUANTITY	AMENDED CONTRACT PRICE	CURRENT QUANTITY	TO DATE EXTENSION	PREVIOUS QUANTITY	PAYMENT EXTENSION	THIS QUANTITY	PAYMENT EXTENSION	CONTRACT QUANTITY	BALANCE EXTENSION
1	72" STEEL PIPE IN TRENCH	8,940.00	L. F.	\$288.07	\$2,575,345.80	8,855.00	\$2,550,859.85	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	8,855.00	\$2,550,859.85
2	72" STEEL PIPE IN CASING	315.00	L.F.	\$2,258.56	\$711,446.40	400.00	\$903,424.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	400.00	\$903,424.00
3	84" STEEL TUNNEL CASING	265.00	L. F.	\$1,610.35	\$426,742.75	350.00	\$563,622.50	115.00	\$185,190.25	115.00	\$185,190.25	0.00	\$0.00	235.00	\$378,432.25
4	84" STEEL CASING IN OPEN CUT	48.00	L. F.	\$1,018.64	\$48,894.72	48.00	\$48,894.72	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	48.00	\$48,894.72
5	72" CONC PIPE CONN AT BUTTERFLD RD	20.00	L. F.	\$3,167.20	\$63,344.00	20.00	\$63,344.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	20.00	\$63,344.00
6	72" CONC PIPE CONN AT ILL PRAIRIE PATH	20.00	L. F.	\$3,244.24	\$64,884.80	20.00	\$64,884.80	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	20.00	\$64,884.80
7	12" DIP SEWER REPLACEMENT	30.00	L. F.	\$86.42	\$2,592.60	30.00	\$2,592.60	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	30.00	\$2,592.60
8	10" PVC SEWER REPLACEMENT	30.00	L.F.	\$65.75	\$1,972.50	30.00	\$1,972.50	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	30.00	\$1,972.50
9	12" RCP SEWER REPLACEMENT	120.00	L. F.	\$66.48	\$7,977.60	120.00	\$7,977.60	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	120.00	\$7,977.60
10	15" RCP SEWER REPLACEMENT	60.00	L. F.	\$61.77	\$3,706.20	60.00	\$3,706.20	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	60.00	\$3,706.20
11	18" RCP SEWER REPLACEMENT	20.00	L. F.	\$95.13	\$1,902.60	20.00	\$1,902.60	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	20.00	\$1,902.60
12	24" RCP SEWER REPLACEMENT	30.00	L. F.	\$82.20	\$2,466.00	30.00	\$2,466.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	30.00	\$2,466.00
13	72" BUTTERFLY VALVE & VAULT	1.00	EA.	\$85,065.00	\$85,065.00	1.00	\$85,065.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	1.00	\$85,065.00
14	72" ROV BUTTERFLY VALVE & VAULT	1.00	EA.	\$155,235.60	\$155,235.60	1.00	\$155,235.60	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	1.00	\$155,235.60
15	12" BLOW-OFF IN MANHOLE	3.00	EA.	\$24,902.11	\$74,706.33	3.00	\$74,706.33	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	3.00	\$74,706.33
16	AIR RELEASE VALVE & MANHOLE	2.00	EA.	\$8,906.68	\$17,813.36	2.00	\$17,813.36	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	2.00	\$17,813.36
17	AIR RELEASE VALVE & ACCESS MANHOLE	6.00	EA.	\$10,486.00	\$62,916.00	6.00	\$62,916.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	6.00	\$62,916.00
18	GRANULAR TRENCH BACKFILL	38,000.00	C.Y.	\$18.08	\$687,040.00	37,596.00	\$679,735.68	1,111.00	\$20,086.88	1,111.00	\$20,086.88	0.00	\$0.00	36,485.00	\$659,648.80
19	ASPHALT PAVEMENT REMOVE & REPLACE	21,720.00	S. Y.	\$37.45	\$813,414.00	21,376.00	\$800,531.20	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	21,376.00	\$800,531.20
20	CONCRETE PAVT REMOVE & REPLACE	3,800.00	S. Y.	\$79.95	\$303,810.00	3,800.00	\$303,810.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	3,800.00	\$303,810.00
21	REFLECTIVE CRACK CONTROL TREAT.	650.00	S. Y.	\$4.55	\$2,957.50	650.00	\$2,957.50	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	650.00	\$2,957.50
22	1-1/2" GRIND AND OVERLAY	650.00	S. Y.	\$20.33	\$13,214.50	650.00	\$13,214.50	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	650.00	\$13,214.50
23	CURB & GUTTER, REM & REPLACE	2,000.00	L.F.	\$16.05	\$32,100.00	1,968.00	\$31,586.40	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	1,968.00	\$31,586.40
24	TOPSOIL & SEEDING	2,450.00	S. Y.	\$5.92	\$14,504.00	2,183.00	\$12,923.36	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	2,183.00	\$12,923.36
25	CURB INLET, REM & REPLACE	7.00	EA.	\$1,760.15	\$12,321.05	7.00	\$12,321.05	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	7.00	\$12,321.05
26	CHAIN LINK FENCE, REM & REPLACE	1,150.00	L.F.	\$18.44	\$21,206.00	1,150.00	\$21,206.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	1,150.00	\$21,206.00
27	SOUTH FENCE GATE, REM & REPLACE	1.00	EA.	\$29,960.00	\$29,960.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00
28	NORTH FENCE GATE, REM & REPLACE	1.00	EA.	\$29,960.00	\$29,960.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00
29	NOT USED														
30	NOT USED														
31	TRAFFIC CONTROL & PROTECTION	1.00	L. S.	\$149,479.00	\$149,479.00	1.00	\$149,479.00	0.15	\$22,421.85	0.10	\$14,947.90	0.05	\$7,473.95	0.85	\$127,057.15
32	CORROSION MONITORING SYSTEM	1.00	L. S.	\$1,391,000.00	\$1,391,000.00	1.00	\$1,391,000.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	1.00	\$1,391,000.00
33	TRENCH WATER CONTROL	1.00	L. S.	\$114,490.00	\$114,490.00	1.00	\$114,490.00	0.10	\$11,449.00	0.00	\$0.00	0.10	\$11,449.00	0.90	\$103,041.00
34	GUARD RAIL, REMOVE & REINSTALL	180.00	L. F.	\$16.17	\$2,910.60	180.00	\$2,910.60	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	180.00	\$2,910.60
35	CHAIN LINK FENCE, REM & REINSTALL	180.00	L. F.	\$18.40	\$3,312.00	180.00	\$3,312.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	180.00	\$3,312.00
36	MODIFICATION TO PIPELAYING DUE TO PETROLEUM CONTAMINATED SOIL	400.00	L. F.	\$2.04	\$816.00	400.00	\$816.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	400.00	\$816.00
37	ROV 15D MODIFICATIONS	1.00	L. S.	\$80,785.00	\$80,785.00	1.00	\$80,785.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	1.00	\$80,785.00
38	EXT PROT COATING FOR PCP SECTIONS	185.00	P. S.	\$1.07	\$197.95	185.00	\$197.95	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	185.00	\$197.95
39	REPLACE EXIST BFF ON SW TR MAIN	1.00	L. S.	\$51,434.90	\$51,434.90	1.00	\$51,434.90	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	1.00	\$51,434.90
40	6-INCH DI PIPE WATER MAIN	1,500.00	L. F.	\$35.52	\$53,280.00	600.00	\$21,312.00	471.00	\$16,729.92	471.00	\$16,729.92	0.00	\$0.00	129.00	\$4,582.08
41	6-INCH DIA GATE VALVE WITH VALVE BOX	8.00	EA.	\$3,757.84	\$30,062.72	5.00	\$18,789.20	4.00	\$15,031.36	4.00	\$15,031.36	0.00	\$0.00	1.00	\$3,757.84
42	FIRE HYDRANT WITH AUXILIARY VALVE	5.00	EA.	\$4,331.36	\$21,656.80	5.00	\$21,656.80	5.00	\$21,656.80	5.00	\$21,656.80	0.00	\$0.00	0.00	\$0.00
43	1-INCH COPPER SERVICE CONNECTION	6.00	EA.	\$1,250.83	\$7,504.98	6.00	\$7,504.98	7.00	\$8,755.81	7.00	\$8,755.81	0.00	\$0.00	(1.00)	(\$1,250.83)
44	CONNECT TO EXISTING 6-IN WATER MAIN	5.00	EA.	\$4,564.62	\$22,823.10	5.00	\$22,823.10	5.00	\$22,823.10	5.00	\$22,823.10	0.00	\$0.00	0.00	\$0.00
45	CONNECT TO EXISTING 8-IN WATER MAIN	1.00	EA.	\$4,795.40	\$4,795.40	1.00	\$4,795.40	1.00	\$4,795.40	1.00	\$4,795.40	0.00	\$0.00	0.00	\$0.00
INDETERMINATE ITEMS															
46	STEEL SHEETING LEFT IN PLACE	500.00	S. F.	\$53.50	\$26,750.00	500.00	\$26,750.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	500.00	\$26,750.00
47	GRANULAR FOUNDATION MATERIAL	500.00	C. Y.	\$21.19	\$10,595.00	500.00	\$10,595.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	500.00	\$10,595.00
48	CLASS "SI" CONCRETE	50.00	C. Y.	\$21.19	\$1,059.50	50.00	\$1,059.50	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	50.00	\$1,059.50
49	CLASS B CONCRETE	50.00	C. Y.	\$85.39	\$4,269.50	50.00	\$4,269.50	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	50.00	\$4,269.50
50	LEVELING BINDER	50.00	TON	\$58.85	\$2,942.50	50.00	\$2,942.50	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	50.00	\$2,942.50
51	ROCK EXCAVATION	50.00	C. Y.	\$107.00	\$5,350.00	50.00	\$5,350.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	50.00	\$5,350.00
52	TEMP PAVT SURFACE OVER TRENCH	5,000.00	S. Y.	\$32.10	\$160,500.00	5,000.00	\$160,500.00	1,091.00	\$35,021.10	1,091.00	\$35,021.10	0.00	\$0.00	3,909.00	\$125,478.90
53	PAVEMENT BASE, REMOVE & REPLACE	200.00	S. Y.	\$48.15	\$9,630.00	200.00	\$9,630.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	200.00	\$9,630.00
54	RECTIFIER, 18 AMPERE, 60 VOLT	4.00	EA.	\$1.07	\$4.28	4.00	\$4.28	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	4.00	\$4.28
55	RECTIFIER, 60 AMPERE, 60 VOLT	4.00	EA.	\$1.07	\$4.28	4.00	\$4.28	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	4.00	\$4.28
56	ANODE HEADER CABLE TEST BOX	40.00	EA.	\$1.07	\$42.80	40.00	\$42.80	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	40.00	\$42.80
57	ANODE COLUMN TEST BOX	32.00	EA.	\$1.07	\$34.24	32.00	\$34.24	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	32.00	\$34.24
58	IMPRESSED CURRENT ANODE COLUMN	600.00	FT	\$1.07	\$642.00	600.00	\$642.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	600.00	\$642.00
59	MAGNESIUM DEEP ANODE BED	1,500.00	FT	\$1.07	\$1,605.00	1,500.00	\$1,605.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	1,500.00	\$1,605.00
60	ZINC DEEP ANODE BED	14,000.00	FT	\$1.07	\$14,980.00	14,000.00	\$14,980.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	14,000.00	\$14,980.00
61	HIGH-SILICON CAST IRON ANODE	40.00	EA.	\$1.07	\$42.80	40.00	\$42.80	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	40.00	\$42.80
62	LINEAR ANODE ASSEMBLIES	17,000.00	FT	\$1.07	\$18,190.00	17,000.00	\$18,190.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	17,000.00	\$18,190.00
63	MAGNESIUM ANODES	75.00	EA.	\$1.07	\$80.25	75.00	\$80.25	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	75.00	\$80.25

DU PAGE WATER COMMISSION

PAYMENT # 37

WEST TRANSMISSION MAIN (TW-2)

DATE 07/30/04

ROSSI CONTRACTORS
201 WEST LAKE STREET
NORTHLAKE, ILLINOIS 60164

ACCOUNT #	AMOUNT
WF-7500	\$119,720.39
WF-1398	0.00
WF-6631	10,870.89
WF-3520	(\$3,785.97)
WF-3530	\$0.00

#	ITEM	ORIGINAL CONTRACT QUANTITY	UNIT	UNIT PRICE	ORIGINAL CONTRACT PRICE	AMENDED CONTRACT QUANTITY	AMENDED CONTRACT PRICE	CURRENT QUANTITY	TO DATE EXTENSION	PREVIOUS QUANTITY	PAYMENT EXTENSION	THIS QUANTITY	PAYMENT EXTENSION	CONTRACT QUANTITY	BALANCE EXTENSION
CO43	SETTLE CEMENT MORTAR LINING DISPUTE	0.00	L.S.	\$330,000.00	\$0.00	1.00	\$330,000.00	1.00	\$330,000.00	1.00	\$330,000.00	0.00	\$0.00	0.00	\$0.00
	CONTRACT SUB-TOTALS				\$17,476,112.15		\$18,307,440.77		\$17,756,465.28		\$17,625,874.00		\$130,591.28		\$550,975.49
	RETENTION	2.90%							(\$514,776.87)		(\$510,990.90)		(\$3,785.97)		\$514,776.87
	CONTRACT TOTALS								\$17,241,688.41		\$17,114,883.10		\$126,805.31		\$1,065,752.36

EXCESS DEDUCTS/BONUS


1X EXCESS ENGINEERING COSTS-ABH	HRS.	(\$60.00)	565.00	(\$33,900.00)	565.00	(\$33,900.00)	0.00	\$0.00
2X EXCESS ENGINEERING COSTS-DWC	HRS.	(\$60.00)	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00
3X SHORT NOTICE TRIP TO PKBRG WV 5/2/00		NOTE: DWC & ABH COSTS		(\$1,716.00)		(\$1,716.00)		\$0.00
4X LINING PROBLEM TRIP TO PKBRG WV 8/22-23/00		NOTE: DWC & ABH COSTS		(\$3,153.96)		(\$3,153.96)		\$0.00

NET PAYMENT TO CONTRACTOR

\$17,202,918.45	\$17,076,113.14	\$126,805.31
-----------------	-----------------	--------------

CHANGE ORDER PERCENTAGE

4.76%



WEST TRANSMISSION MAIN (TW-2)

DATE 07/30/04

ROSSI CONTRACTORS
201 WEST LAKE STREET
NORTHLAKE, ILLINOIS 60164

ACCOUNT #	AMOUNT
WF-7500	\$119,720.39
WF-1398	0.00
WF-6631	10,870.89
WF-3520	(\$3,785.97)
WF-3530	\$0.00

#	ITEM	ORIGINAL CONTRACT QUANTITY	UNIT	UNIT PRICE	ORIGINAL CONTRACT PRICE	AMENDED CONTRACT QUANTITY	AMENDED CONTRACT PRICE	CURRENT QUANTITY	TO DATE EXTENSION	PREVIOUS QUANTITY	PAYMENT EXTENSION	THIS QUANTITY	PAYMENT EXTENSION	CONTRACT QUANTITY	BALANCE EXTENSION
1	48" STEEL PIPE IN TRENCH	49,500.00	L. F.	\$171.50	\$8,489,250.00	49,500.00	\$8,489,250.00	48,970.00	\$8,398,355.00	48,914.00	\$8,388,751.00	58.00	\$9,604.00	530.00	\$90,895.00
2	20" STEEL PIPE IN TRENCH	130.00	L.F.	\$60.00	\$7,800.00	130.00	\$7,800.00	115.00	\$6,900.00	115.00	\$6,900.00	0.00	\$0.00	15.00	\$900.00
3	16" STEEL PIPE IN TRENCH	15.00	L. F.	\$50.00	\$750.00	15.00	\$750.00	18.00	\$900.00	18.00	\$900.00	0.00	\$0.00	(3.00)	(\$150.00)
4	48" STEEL PIPE IN CASING	860.00	L. F.	\$250.00	\$215,000.00	860.00	\$215,000.00	866.00	\$216,500.00	866.00	\$216,500.00	0.00	\$0.00	(6.00)	(\$1,500.00)
5	72" STEEL TUNNEL CASING	710.00	L. F.	\$1,396.00	\$991,160.00	710.00	\$991,160.00	716.00	\$999,536.00	716.00	\$999,536.00	0.00	\$0.00	(6.00)	(\$8,376.00)
6	72" STEEL CASING UNDER RAILROAD	150.00	L. F.	\$1,478.00	\$221,700.00	150.00	\$221,700.00	150.00	\$221,700.00	150.00	\$221,700.00	0.00	\$0.00	0.00	\$0.00
7	48" STEEL PIPE CONN. AT BUTTERFIELD RD	1.00	L. S.	\$40,000.00	\$40,000.00	1.00	\$40,000.00	1.00	\$40,000.00	1.00	\$40,000.00	0.00	\$0.00	0.00	\$0.00
8	42" CONC PIPE CONN - GREAT WEST TRAIL	1.00	L.S.	\$35,000.00	\$35,000.00	1.00	\$35,000.00	1.00	\$35,000.00	1.00	\$35,000.00	0.00	\$0.00	0.00	\$0.00
9	20" CONC PIPE CONN AT KUHN RD	1.00	L. S.	\$15,000.00	\$15,000.00	1.00	\$15,000.00	1.00	\$15,000.00	1.00	\$15,000.00	0.00	\$0.00	0.00	\$0.00
10	DIP SEWER SERVICE REPLACEMENT	525.00	L. F.	\$70.00	\$36,750.00	525.00	\$36,750.00	374.00	\$26,180.00	374.00	\$26,180.00	0.00	\$0.00	151.00	\$10,570.00
11	NOT USED														
12	8" DIP SEWER REPLACEMENT	120.00	L. F.	\$69.00	\$8,280.00	120.00	\$8,280.00	58.00	\$4,002.00	36.00	\$2,484.00	22.00	\$1,518.00	62.00	\$4,278.00
13	10" DIP SEWER REPLACEMENT	1,600.00	L. F.	\$67.22	\$107,552.00	1,600.00	\$107,552.00	1,157.00	\$77,773.54	1,157.00	\$77,773.54	0.00	\$0.00	443.00	\$29,778.46
14	12" DIP SEWER REPLACEMENT	450.00	L. F.	\$50.40	\$22,680.00	450.00	\$22,680.00	488.00	\$24,595.20	488.00	\$24,595.20	0.00	\$0.00	(38.00)	(\$1,915.20)
15	16" DIP SEWER REPLACEMENT	120.00	L. F.	\$66.40	\$7,968.00	120.00	\$7,968.00	135.00	\$8,964.00	135.00	\$8,964.00	0.00	\$0.00	(15.00)	(\$996.00)
16	NOT USED														
17	24" DIP SEWER REPLACEMENT	200.00	L. F.	\$230.00	\$46,000.00	200.00	\$46,000.00	238.00	\$54,740.00	238.00	\$54,740.00	0.00	\$0.00	(38.00)	(\$8,740.00)
18	30" DIP SEWER REPLACEMENT	30.00	L. F.	\$115.20	\$3,456.00	30.00	\$3,456.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	30.00	\$3,456.00
19	NOT USED														
20	12" RCP SEWER REPLACEMENT	350.00	L. F.	\$60.00	\$21,000.00	350.00	\$21,000.00	319.00	\$19,140.00	319.00	\$19,140.00	0.00	\$0.00	31.00	\$1,860.00
21	15" RCP SEWER REPLACEMENT	210.00	L. F.	\$59.40	\$12,474.00	210.00	\$12,474.00	205.00	\$12,177.00	205.00	\$12,177.00	0.00	\$0.00	5.00	\$297.00
22	18" RCP SEWER REPLACEMENT	50.00	L. F.	\$64.00	\$3,200.00	50.00	\$3,200.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	50.00	\$3,200.00
23	21" RCP SEWER REPLACEMENT	40.00	L.F.	\$103.20	\$4,128.00	40.00	\$4,128.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	40.00	\$4,128.00
24	24" RCP SEWER REPLACEMENT	150.00	L.F.	\$77.20	\$11,580.00	150.00	\$11,580.00	113.00	\$8,723.60	113.00	\$8,723.60	0.00	\$0.00	37.00	\$2,856.40
25	27" RCP SEWER REPLACEMENT	220.00	L.F.	\$75.90	\$16,698.00	220.00	\$16,698.00	190.00	\$14,421.00	190.00	\$14,421.00	0.00	\$0.00	30.00	\$2,277.00
26	30" RCP SEWER REPLACEMENT	30.00	L.F.	\$115.20	\$3,456.00	30.00	\$3,456.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	30.00	\$3,456.00
27	48" BUTTERFLY VALVE & VAULT	9.00	EA.	\$35,315.00	\$317,835.00	9.00	\$317,835.00	9.00	\$317,835.00	8.55	\$301,943.25	0.45	\$15,891.75	0.00	\$0.00
28	20" BUTTERFLY VALVE & VAULT	1.00	EA.	\$20,414.00	\$20,414.00	1.00	\$20,414.00	1.00	\$20,414.00	1.00	\$20,414.00	0.00	\$0.00	0.00	\$0.00
29	16" BUTTERFLY VALVE & VAULT	1.00	EA.	\$19,370.00	\$19,370.00	1.00	\$19,370.00	1.00	\$19,370.00	1.00	\$19,370.00	0.00	\$0.00	0.00	\$0.00
30	48" ROV BUTTERFLY VALVE & VAULT	1.00	EA.	\$157,620.00	\$157,620.00	1.00	\$157,620.00	1.00	\$157,620.00	1.00	\$157,620.00	0.00	\$0.00	0.00	\$0.00
31	12" BLOW-OFF IN MANHOLE	11.00	EA.	\$20,000.00	\$220,000.00	11.00	\$220,000.00	10.00	\$200,000.00	9.50	\$190,000.00	0.50	\$10,000.00	1.00	\$20,000.00
32	AIR RELEASE VALVE & MANHOLE	8.00	EA.	\$7,470.00	\$59,760.00	8.00	\$59,760.00	8.00	\$59,760.00	8.00	\$59,760.00	0.00	\$0.00	0.00	\$0.00
33	AIR RELEASE VALVE & ACCESS MANHOLE	29.00	EA.	\$8,392.00	\$243,368.00	29.00	\$243,368.00	31.00	\$260,152.00	30.00	\$251,760.00	1.00	\$8,392.00	(2.00)	(\$16,784.00)
34	GRANULAR TRENCH BACKFILL	99,000.00	C.Y.	\$16.50	\$1,633,500.00	99,000.00	\$1,633,500.00	89,380.00	\$1,474,770.00	88,906.00	\$1,466,949.00	474.00	\$7,821.00	9,620.00	\$158,730.00
35	ASPHALT PAVEMENT REMOVE & REPLACE	40,800.00	S. Y.	\$33.57	\$1,369,656.00	40,338.00	\$1,354,146.66	44,802.00	\$1,504,003.14	44,087.00	\$1,480,000.59	715.00	\$24,002.55	(4,464.00)	(\$149,856.48)
36	4" BIT.CONC. OVER 6" AGG BASE IN W.CHIC.	8,350.00	S. Y.	\$15.72	\$131,262.00	8,350.00	\$131,262.00	6,907.00	\$108,578.04	6,907.00	\$108,578.04	0.00	\$0.00	1,443.00	\$22,683.96
37	REFLECTIVE CRACK CONTROL TREAT.	53,000.00	S. Y.	\$0.60	\$31,800.00	53,000.00	\$31,800.00	21,784.00	\$13,070.40	21,784.00	\$13,070.40	0.00	\$0.00	31,216.00	\$18,729.60
38	1-1/2" GRIND AND OVERLAY	53,000.00	S.Y.	\$5.40	\$286,200.00	53,000.00	\$286,200.00	60,324.00	\$325,749.60	58,657.00	\$316,747.80	1,667.00	\$9,001.80	(7,324.00)	(\$39,549.60)
39	ASPHALT DRIVEWAY REMOVE & REPLACE	1,980.00	S.Y.	\$21.72	\$43,005.60	3,180.00	\$69,069.60	3,289.00	\$71,437.08	3,289.00	\$71,437.08	0.00	\$0.00	(109.00)	(\$2,367.48)
40	CONCRETE DRIVEWAY, REM & REPL	20.00	S.Y.	\$31.00	\$620.00	20.00	\$620.00	24.00	\$744.00	24.00	\$744.00	0.00	\$0.00	(4.00)	(\$124.00)
41	STONE DRIVEWAY, REM & REPL	500.00	S. Y.	\$5.60	\$2,800.00	500.00	\$2,800.00	207.00	\$1,159.20	207.00	\$1,159.20	0.00	\$0.00	293.00	\$1,640.80
42	CURB & GUTTER REMOVE & REPLACE	2,300.00	L.F.	\$17.00	\$39,100.00	5,800.00	\$98,600.00	6,619.00	\$112,523.00	6,619.00	\$112,523.00	0.00	\$0.00	(819.00)	(\$13,923.00)
43	AGG. SHOULDER, REMOVE & REPLACE	11,000.00	S.Y.	\$11.07	\$121,770.00	13,500.00	\$149,445.00	15,650.00	\$173,245.50	15,051.00	\$166,614.57	599.00	\$6,630.93	(2,150.00)	(\$23,800.50)
44	ASPHALT SHOULDER, REM & REPL	925.00	S.Y.	\$23.07	\$21,339.75	925.00	\$21,339.75	962.00	\$22,193.34	962.00	\$22,193.34	0.00	\$0.00	(37.00)	(\$853.59)
45	SIDEWALK, REM & REPL	1,630.00	S.F.	\$4.00	\$6,520.00	1,630.00	\$6,520.00	1,944.00	\$7,776.00	1,944.00	\$7,776.00	0.00	\$0.00	(314.00)	(\$1,256.00)
46	TOP SOIL & SEEDING	22,520.00	S.Y.	\$3.80	\$85,576.00	22,520.00	\$85,576.00	27,024.00	\$102,691.20	27,024.00	\$102,691.20	0.00	\$0.00	(4,504.00)	(\$17,115.20)
47	TOPSOIL & SODDING	3,370.00	S.Y.	\$6.45	\$21,736.50	7,370.00	\$47,536.50	8,840.00	\$57,018.00	8,840.00	\$57,018.00	0.00	\$0.00	(1,470.00)	(\$9,481.50)
48	SANITARY & STORM MH, REM & REPL	10.00	EA.	\$21,000.00	\$21,000.00	10.00	\$21,000.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	10.00	\$21,000.00
49	CATCH BASIN, REM & REPL	1.00	EA.	\$2,300.00	\$2,300.00	1.00	\$2,300.00	1.00	\$2,300.00	1.00	\$2,300.00	0.00	\$0.00	0.00	\$0.00
50	INLET, CURB OR GUTTER REM & REPL	33.00	EA.	\$750.00	\$24,750.00	33.00	\$24,750.00	6.00	\$4,500.00	5.00	\$3,750.00	1.00	\$750.00	27.00	\$20,250.00
51	CHAIN LINK FENCE, REM & REINSTALL	30.00	L. F.	\$30.00	\$900.00	210.00	\$6,300.00	230.00	\$6,900.00	230.00	\$6,900.00	0.00	\$0.00	(20.00)	(\$600.00)
52	REM. & DISP. OF PETRO. CONT. SOIL	10,925.00	C.Y.	\$1.00	\$10,925.00	10,925.00	\$10,925.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	10,925.00	\$10,925.00
53	MOD. TO PIPELAYING DUE TO CONT. SOIL	2,300.00	L.F.	\$16.85	\$38,755.00	2,300.00	\$38,755.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	2,300.00	\$38,755.00
54	VALVE OPERATOR MODIFICATION	1.00	L.S.	\$362,363.00	\$362,363.00	1.00	\$362,363.00	1.00	\$362,363.00	0.97	\$351,492.11	0.03	\$10,870.89	0.00	\$0.00
55	TRAFFIC CONTROL PROTECTION & SIGNAL	1.00	L.S.	\$273,950.00	\$273,950.00	1.00	\$273,950.00	1.00	\$273,950.00	0.99	\$271,210.50	0.01	\$2,739.50	0.00	\$0.00
56	NOT USED														
57	DETECTOR LOOP REPLACEMENT	1,780.00	L.F.	\$18.00	\$32,040.00	1,780.00	\$32,040.00	1,342.00	\$24,156.00	1,342.00	\$24,156.00	0.00	\$0.00	438.00	\$7,884.00
58	TRENCH & BACKFILL FOR ELECT. WORK	245.00	L.F.	\$4.00	\$980.00	245.00	\$980.00	240.00	\$960.00	240.00	\$960.00	0.00	\$0.00	5.00	\$20.00
59	COND. IN TRENCH, 1.25" GALV. STEEL	532.00	L. F.	\$4.00	\$2,128.00	532.00	\$2,128.00	480.00	\$1,840.00	480.00	\$1,840.00	0.00	\$0.00	72.00	\$288.00
60	COND. IN TRENCH, 2" GALV. STEEL	6.00	L.F.	\$5.00	\$30.00	6.00	\$30.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	6.00	\$30.00
61	COND. IN TRENCH, 2.5" GALV. STEEL	7.00	L.F.	\$8.00	\$56.00	7.00	\$56.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	7.00	\$56.00
62	COND. IN TRENCH, 4" GALV. STEEL	11.00	L.F.	\$13.00	\$143.00	11.00	\$143.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	11.00	\$143.00
63	REM. & REINST. ELECT. CABLE FROM COND	1,378.00	EA.	\$1.20	\$1,653.60	1,378.00	\$1,653.60	340.00	\$408.00	340.00	\$408.00	0.00	\$0.00	1,038.00	\$1,245.60
64	CUT & SPLICE COND. 1.25" DIA.	1.00	EA.	\$180.00	\$180.00	1.00	\$180.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	1.00	\$180.00
65	CUT & SPLICE COND. 2.5" DIA.	1.00	EA.	\$190.00	\$190.00	1.00	\$190.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	1.00	\$190.00

WEST TRANSMISSION MAIN (TW-2)

DATE 07/30/04

ROSSI CONTRACTORS
201 WEST LAKE STREET
NORTHLAKE, ILLINOIS 60164

ACCOUNT #	AMOUNT
WF-7500	\$119,720.39
WF-1398	0.00
WF-6631	10,870.89
WF-3520	(\$3,785.97)
WF-3530	\$0.00

#	ITEM	ORIGINAL CONTRACT QUANTITY	UNIT	UNIT PRICE	ORIGINAL CONTRACT PRICE	AMENDED CONTRACT QUANTITY	AMENDED CONTRACT PRICE	CURRENT QUANTITY	TO DATE EXTENSION	PREVIOUS QUANTITY	PAYMENT EXTENSION	THIS QUANTITY	PAYMENT EXTENSION	CONTRACT QUANTITY	BALANCE EXTENSION
66	CUT & SPLICE COND. 4" DIA.	1.00	EA.	\$300.00	\$300.00	1.00	\$300.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	1.00	\$300.00
67	CONCRETE HANDHOLE, REM & REPL	1.00	EA.	\$1,100.00	\$1,100.00	1.00	\$1,100.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	1.00	\$1,100.00
68	DRILL CONCRETE HANDHOLE	2.00	EA.	\$145.00	\$290.00	2.00	\$290.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	2.00	\$290.00
69	DRILL EXISTING FOUNDATION	1.00	EA.	\$255.00	\$255.00	1.00	\$255.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	1.00	\$255.00
70	TEMP. TR. SIGNAL INSTALLATION	1.00	EA.	\$19,600.00	\$19,600.00	1.00	\$19,600.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	1.00	\$19,600.00
71	REM & REINST. EX. MAIST ARM ASSEMBLY	1.00	EA.	\$800.00	\$800.00	1.00	\$800.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	1.00	\$800.00
72	MAINTENANCE OF EXIST. TR. SIGNAL	5.00	EA.	\$5,000.00	\$25,000.00	5.00	\$25,000.00	5.00	\$25,000.00	5.00	\$25,000.00	0.00	\$0.00	0.00	\$0.00
73	SILT FENCE, SEDIMENT & EROS. CONTRL	450.00	L.F.	\$3.75	\$1,687.50	450.00	\$1,687.50	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	450.00	\$1,687.50
74	SILT FENCE, SEDIMENT & EROS. CONTRL	4,060.00	L.F.	\$1.50	\$6,090.00	7,060.00	\$10,590.00	7,067.00	\$10,600.50	7,067.00	\$10,600.50	0.00	\$0.00	(7.00)	(\$10.50)
75	STRAW BALE BARRIER, EROS. CONTROL	90.00	BALE	\$8.00	\$720.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00
76	EXCELSIOR BLANKET, EROS. CONTROL	920.00	S.Y.	\$1.50	\$1,380.00	920.00	\$1,380.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	920.00	\$1,380.00
77	UNPAVED INLET PROT. SEDIMENT CONTR.	19.00	EA.	\$60.00	\$1,140.00	19.00	\$1,140.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	19.00	\$1,140.00
78	PAVED INLET PROT. SEDIMENT CONTROL	46.00	EA.	\$15.00	\$690.00	46.00	\$690.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	46.00	\$690.00
79	ROCK AT CUL/DITCH CHECKS, ER. CONTR	10.00	EA.	\$200.00	\$2,000.00	10.00	\$2,000.00	12.00	\$2,400.00	12.00	\$2,400.00	0.00	\$0.00	(2.00)	(\$400.00)
80	8" HIGH METAL SHELF, REM & REINSTALL	1.00	L.S.	\$2,700.00	\$2,700.00	1.00	\$2,700.00	1.00	\$2,700.00	1.00	\$2,700.00	0.00	\$0.00	0.00	\$0.00
81	GROUP OF 4 TRAILERS, REM & REINSTALL	1.00	L.S.	\$2,700.00	\$2,700.00	1.00	\$2,700.00	1.00	\$2,700.00	1.00	\$2,700.00	0.00	\$0.00	0.00	\$0.00
82	CORROSION MONITOR, & CONTROL SYST.	1.00	L.S.	\$136,765.00	\$136,765.00	1.00	\$136,765.00	0.98	\$134,029.70	0.98	\$134,029.70	0.00	\$0.00	0.02	\$2,735.30
83	TRENCH WATER CONTROL	1.00	L.S.	\$77,456.00	\$77,456.00	1.00	\$77,456.00	1.00	\$77,456.00	0.98	\$75,906.88	0.02	\$1,549.12	0.00	\$0.00
84A	8" DI PIPE WATERMAIN	1,370.00	L.F.	\$52.55	\$71,993.50	1,370.00	\$71,993.50	1,386.00	\$72,834.30	1,386.00	\$72,834.30	0.00	\$0.00	(16.00)	(\$840.80)
84B	8" GATE VALVE & VAULT	2.00	EA.	\$2,300.00	\$4,600.00	2.00	\$4,600.00	2.00	\$4,600.00	2.00	\$4,600.00	0.00	\$0.00	0.00	\$0.00
84C	FIRE HYDRANT WITH AUX. VALVE	2.00	EA.	\$2,500.00	\$5,000.00	2.00	\$5,000.00	2.00	\$5,000.00	2.00	\$5,000.00	0.00	\$0.00	0.00	\$0.00
84D	1" SERVICE CONNECTION, LONG	9.00	EA.	\$2,000.00	\$18,000.00	9.00	\$18,000.00	9.00	\$18,000.00	9.00	\$18,000.00	0.00	\$0.00	0.00	\$0.00
84E	1" SERVICE CONNECTION, SHORT	9.00	EA.	\$1,500.00	\$13,500.00	9.00	\$13,500.00	6.00	\$9,000.00	6.00	\$9,000.00	0.00	\$0.00	3.00	\$4,500.00
84F	8" DI PIPE WATERMAIN	1,840.00	L.F.	\$37.60	\$69,184.00	1,840.00	\$69,184.00	1,839.00	\$69,146.40	1,839.00	\$69,146.40	0.00	\$0.00	1.00	\$37.60
84G	6" DI PIPE WATERMAIN	90.00	L.F.	\$37.60	\$3,384.00	90.00	\$3,384.00	67.00	\$2,519.20	67.00	\$2,519.20	0.00	\$0.00	23.00	\$864.80
84H	8" GATE VALVE & VAULT	2.00	EA.	\$2,300.00	\$4,600.00	4.00	\$9,200.00	4.00	\$9,200.00	4.00	\$9,200.00	0.00	\$0.00	0.00	\$0.00
84I	8" GATE VALVE & BOX	1.00	EA.	\$800.00	\$800.00	1.00	\$800.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	1.00	\$800.00
84J	6" GATE VALVE & VAULT	4.00	EA.	\$600.00	\$2,400.00	2.00	\$1,200.00	2.00	\$1,200.00	2.00	\$1,200.00	0.00	\$0.00	0.00	\$0.00
84K	FIRE HYDRANT WITH AUX. VALVE	5.00	EA.	\$2,500.00	\$12,500.00	5.00	\$12,500.00	5.00	\$12,500.00	5.00	\$12,500.00	0.00	\$0.00	0.00	\$0.00
84L	1" SERVICE CONNECTION, LONG	12.00	EA.	\$2,000.00	\$24,000.00	12.00	\$24,000.00	9.00	\$18,000.00	9.00	\$18,000.00	0.00	\$0.00	3.00	\$6,000.00
84M	1" SERVICE CONNECTION, SHORT	12.00	EA.	\$1,500.00	\$18,000.00	12.00	\$18,000.00	10.00	\$15,000.00	10.00	\$15,000.00	0.00	\$0.00	2.00	\$3,000.00
84N	AUGER FOR INSTALLATION OF MAIN	20.00	L.F.	\$200.00	\$4,000.00	20.00	\$4,000.00	20.00	\$4,000.00	20.00	\$4,000.00	0.00	\$0.00	0.00	\$0.00
84O	12" DI PIPE WATERMAIN	4,230.00	L.F.	\$55.59	\$235,145.70	4,230.00	\$0.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	4,230.00	\$0.00
84P	12" GATE VALVE & VAULT	2.00	EA.	\$2,500.00	\$5,000.00	2.00	\$0.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	2.00	\$0.00
84Q	FIRE HYDRANT WITH AUX. VALVE	2.00	EA.	\$2,500.00	\$5,000.00	2.00	\$0.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	2.00	\$0.00
84R	ASPHALT PAVT, REM & REPLCE	1,400.00	S.Y.	\$34.00	\$47,600.00	1,400.00	\$0.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	1,400.00	\$0.00
84S	12" DI PIPE WATERMAIN	4,060.00	L.F.	\$46.75	\$189,805.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00
84T	12" GATE VALVE & VAULT	1.00	EA.	\$2,500.00	\$2,500.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00
84U	FIRE HYDRANT WITH AUX. VALVE	2.00	EA.	\$2,500.00	\$5,000.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00
84V	AUGER FOR INSTALLATION OF MAIN	15.00	L.F.	\$200.00	\$3,000.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00
84W	ASPHALT PAVT, REM & REPLCE	1,500.00	S.Y.	\$34.00	\$51,000.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00
85	STEEL SHEETING LEFT IN PLACE	1,000.00	S.F.	\$40.00	\$40,000.00	1,000.00	\$40,000.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	1,000.00	\$40,000.00
86	GRANULAR FOUNDATION MATERIAL	2,000.00	C.Y.	\$18.00	\$36,000.00	2,000.00	\$36,000.00	1,421.00	\$25,578.00	1,421.00	\$25,578.00	0.00	\$0.00	579.00	\$10,422.00
87	CLASS "SI" CONCRETE	200.00	C.Y.	\$72.55	\$14,510.00	200.00	\$14,510.00	29.00	\$2,103.95	29.00	\$2,103.95	0.00	\$0.00	171.00	\$12,406.05
88	CLASS B CONCRETE	300.00	C.Y.	\$61.50	\$18,450.00	300.00	\$18,450.00	50.00	\$3,075.00	50.00	\$3,075.00	0.00	\$0.00	250.00	\$15,375.00
89	LEVELING BINDER	3,000.00	TON	\$44.00	\$132,000.00	3,000.00	\$132,000.00	2,424.00	\$106,656.00	2,444.00	\$98,736.00	180.00	\$7,920.00	576.00	\$25,344.00
90	DIRECT BOND (CORR. CONT.DRG. ITEM 90)	2.00	EA.	\$9,000.00	\$18,000.00	2.00	\$18,000.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	2.00	\$18,000.00
91	GROUNDBED DRAIN (COR.CONT.DRG. #91)	2.00	EA.	\$11,000.00	\$22,000.00	2.00	\$22,000.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	2.00	\$22,000.00
92	ROCK EXCAVATION	100.00	C.Y.	\$50.00	\$5,000.00	100.00	\$5,000.00	72.00	\$3,600.00	72.00	\$3,600.00	0.00	\$0.00	28.00	\$1,400.00
93	PAVT. BASE, REM & REPLACE	1,500.00	S.Y.	\$34.00	\$51,000.00	1,500.00	\$51,000.00	1,518.00	\$51,612.00	1,518.00	\$39,134.00	367.00	\$12,478.00	(18.00)	(\$612.00)
94	2" ADDITIONAL BIT. MIX	1,000.00	S.Y.	\$9.00	\$9,000.00	1,000.00	\$9,000.00	675.00	\$6,075.00	675.00	\$6,075.00	0.00	\$0.00	325.00	\$2,925.00
95	EXT.PROT.COAT.CONC.PIPE SECTIONS	100.00	EA.	\$520.00	\$52,000.00	100.00	\$52,000.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	100.00	\$52,000.00
96	1" TYPE K COPPER WATER SERVICE	1,000.00	L.F.	\$30.00	\$30,000.00	1,000.00	\$30,000.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	1,000.00	\$30,000.00
97	VALVE VAULT, REM & REPLACEMENT	1.00	EA.	\$2,500.00	\$2,500.00	1.00	\$2,500.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	1.00	\$2,500.00
98	RELOCATE 2" GAS MAIN	280.00	L.F.	\$50.00	\$14,000.00	280.00	\$14,000.00	80.00	\$4,000.00	80.00	\$4,000.00	0.00	\$0.00	200.00	\$10,000.00
99	CAST-IN-PLACE CONC.VAULT FOR ROV 6	1.00	EA.	\$18,700.00	\$18,700.00	1.00	\$18,700.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	1.00	\$18,700.00
100	COND. IN TRENCH, 1.25" GALV. STEEL	250.00	L.F.	\$3.90	\$975.00	250.00	\$975.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	250.00	\$975.00
101	COND. IN TRENCH, 1.5" GALV. STEEL	50.00	L.F.	\$4.30	\$215.00	50.00	\$215.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	50.00	\$215.00
102	COND. IN TRENCH, 2" GALV. STEEL	60.00	L.F.	\$4.80	\$288.00	60.00	\$288.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	60.00	\$288.00
103	COND. IN TRENCH, 2.5" GALV. STEEL	60.00	L.F.	\$7.40	\$444.00	60.00	\$444.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	60.00	\$444.00
104	COND. IN TRENCH, 3" GALV. STEEL	60.00	L.F.	\$9.60	\$576.00	60.00	\$576.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	60.00	\$576.00
105	COND. IN TRENCH, 3.5" GALV. STEEL	60.00	L.F.	\$12.00	\$720.00	60.00	\$720.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	60.00	\$720.00
106	COND. IN TRENCH, 4" GALV. STEEL	20.00	L.F.	\$12.50	\$250.00	20.00	\$250.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	20.00	\$250.00
107	CONC. HANDHOLE, REM & REPLACE	1.00	EA.	\$1,100.00	\$1,100.00	1.00	\$1,100.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	1.00	\$1,100.00
108	DETECTOR LOOP REPLACEMENT	200.00	L.F.	\$18.00	\$3,600.00	200.00	\$3,600.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	200.00	\$3,600.00
109	REMOVE EL.CABLE FROM COND.& REINST.	500.00	L.F.	\$1.20	\$600.00	500.00	\$600.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	500.00	\$600.00
110	TRENCH & BACKFILL FOR ELECT. WORK	300.00	L.F.	\$3.40	\$1,020.00	300.00	\$1,020.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	300.00	\$1,020.00

WEST TRANSMISSION MAIN (TW-2)

DATE 07/30/04

ROSSI CONTRACTORS
201 WEST LAKE STREET
NORTHLAKE, ILLINOIS 60164

ACCOUNT #	AMOUNT
WF-7500	\$119,720.39
WF-1398	0.00
WF-6631	10,870.89
WF-3520	(\$3,785.97)
WF-3530	\$0.00

#	ITEM	ORIGINAL CONTRACT QUANTITY	UNIT	UNIT PRICE	ORIGINAL CONTRACT PRICE	AMENDED CONTRACT QUANTITY	AMENDED CONTRACT PRICE	CURRENT QUANTITY	TO DATE EXTENSION	PREVIOUS QUANTITY	PAYMENT EXTENSION	THIS QUANTITY	PAYMENT EXTENSION	CONTRACT QUANTITY	BALANCE EXTENSION
CO1	TIME EXTENSION - 14 DAYS (PHASE I ONLY)														
CO2	SEDIMENT LOGS IN LIEU OF STRAW BALES	0.00	L.YD	\$38.61	\$0.00	390.00	\$15,057.90	264.00	\$10,193.04	264.00	\$10,193.04	0.00	\$0.00	126.00	\$4,864.86
CO3	ADD 3" BIT CONC FOR PAVT IN W.CHICAGO	0.00	S.Y.	\$9.82	\$0.00	8,350.00	\$81,997.00	6,907.00	\$67,826.74	6,907.00	\$67,826.74	0.00	\$0.00	1,443.00	\$14,170.26
CO4	ADD COST-CASING @ NORTH & ST.CHARLES	0.00	L.S.	\$5,400.00	\$0.00	1.00	\$5,400.00	1.00	\$5,400.00	1.00	\$5,400.00	0.00	\$0.00	0.00	\$0.00
CO5	ADD PAVT THICKNESS PER DUDOT														
	1. BIT DRIVEWAYS--GENEVA TO MAIN ST	0.00	S.Y.	\$4.80	\$0.00	800.00	\$3,840.00	612.00	\$2,937.60	612.00	\$2,937.60	0.00	\$0.00	188.00	\$902.40
	2. BIT SHOULDERS--GENEVA TO MAIN ST	0.00	S.Y.	\$13.85	\$0.00	1,000.00	\$13,850.00	962.00	\$13,323.70	962.00	\$13,323.70	0.00	\$0.00	38.00	\$526.30
CO6	ADD COST-SAWING & PAVT MARKINGS	0.00	L.S.	\$2,808.17	\$0.00	1.00	\$2,808.17	1.00	\$2,808.17	1.00	\$2,808.17	0.00	\$0.00	0.00	\$0.00
CO7	ADD COST-ADJUST HH, CB & SAWCUT CURB	0.00	L.S.	\$2,697.00	\$0.00	1.00	\$2,697.00	1.00	\$2,697.00	1.00	\$2,697.00	0.00	\$0.00	0.00	\$0.00
CO8	CREDIT--66" DIA CASING INSTEAD OF 72"	0.00	L.F.	(\$10.00)	\$0.00	860.00	(\$8,600.00)	866.00	(\$8,660.00)	866.00	(\$8,660.00)	0.00	\$0.00	(6.00)	\$60.00
CO9	1. ADD 2500 LF C&G TO ITEM 42 ABOVE														
	2. DEDUCT 330 SY PAVT-- ITEM 35 ABOVE														
CO10	1. ADD 180 LF FENCE TO ITEM 51 ABOVE														
	2. R & R FENCE AT MCCORMICK EASEMENT	0.00	L.S.	\$5,931.20	\$0.00	1.00	\$5,931.20	1.00	\$5,931.20	1.00	\$5,931.20	0.00	\$0.00	0.00	\$0.00
CO11	ADD AIR RELEASE VALVE & MH, ST.39+00	0.00	EA.	\$7,470.00	\$0.00	1.00	\$7,470.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	1.00	\$7,470.00
CO12	DI SOLID SLEEVE COUPLING FOR WM REPL.	0.00	EA.	\$250.00	\$0.00	12.00	\$3,000.00	12.00	\$3,000.00	12.00	\$3,000.00	0.00	\$0.00	0.00	\$0.00
CO13	SEEDING AT 200LB/ACRE IN FOREST PR.	0.00	S.Y.	\$4.90	\$0.00	3,900.00	\$19,110.00	1,528.00	\$7,487.20	1,528.00	\$7,487.20	0.00	\$0.00	2,372.00	\$11,622.80
CO14	ADD COST FOR WETLAND GAP-PR.CR. RD	0.00	EA.	\$19,221.60	\$0.00	1.00	\$19,221.60	1.00	\$19,221.60	1.00	\$19,221.60	0.00	\$0.00	0.00	\$0.00
CO15	4" YELLOW PAVT. STRIPING-WINFIELD RD	0.00	L.F.	\$0.39	\$0.00	13,100.00	\$5,109.00	13,100.00	\$5,109.00	13,100.00	\$5,109.00	0.00	\$0.00	0.00	\$0.00
CO16	ADD COST DUE TO REVISED TR. CONT.DRG.	0.00	L.S.	\$119,736.00	\$0.00	1.00	\$119,736.00	1.00	\$119,736.00	0.99	\$118,538.64	0.01	\$1,197.36	0.00	\$0.00
CO17	WAIVE PIPE DIR. & STOCKPILING (NO COST)														
CO18	ADD COST-WATER SERVICES-WINFLD WORK														
	1. 1" LONG AND SHORT SERVICES	0.00	EA.	\$500.00	\$0.00	34.00	\$17,000.00	34.00	\$17,000.00	34.00	\$17,000.00	0.00	\$0.00	0.00	\$0.00
	2. 1.5" SHORT SERVICE	0.00	L.S.	\$2,500.00	\$0.00	1.00	\$2,500.00	1.00	\$2,500.00	1.00	\$2,500.00	0.00	\$0.00	0.00	\$0.00
CO19	TIME RESTRAINT & TEMP. ROAD-WAYNE TWP	0.00	L.S.	\$30,000.00	\$0.00	1.00	\$30,000.00	1.00	\$30,000.00	1.00	\$30,000.00	0.00	\$0.00	0.00	\$0.00
CO20	EXTRA TR. CONTROL SIGNS IN WINFIELD	0.00	L.S.	\$5,960.00	\$0.00	1.00	\$5,960.00	1.00	\$5,960.00	1.00	\$5,960.00	0.00	\$0.00	0.00	\$0.00
CO21	AMEND QTY OF ITEMS 47, 74 & CO2 ABOVE														
CO22	ADD. WORK AT ROV2 AND ROV3														
	1. ELECTRICAL REVISIONS AT ROV2	0.00	L.S.	\$4,050.30	\$0.00	1.00	\$4,050.30	1.00	\$4,050.30	1.00	\$4,050.30	0.00	\$0.00	0.00	\$0.00
	2. BOLLARDS AT ROV2	0.00	EA.	\$880.00	\$0.00	3.00	\$2,640.00	3.00	\$2,640.00	3.00	\$2,640.00	0.00	\$0.00	0.00	\$0.00
	3. ELECTRICAL REVISIONS AT ROV3	0.00	L.S.	\$35,589.70	\$0.00	1.00	\$35,589.70	1.00	\$35,589.70	1.00	\$35,589.70	0.00	\$0.00	0.00	\$0.00
CO23	INSTALL EIM ACTUATOR AT ROV2	0.00	L.S.	\$17,455.00	\$0.00	1.00	\$17,455.00	1.00	\$17,455.00	1.00	\$17,455.00	0.00	\$0.00	0.00	\$0.00
CO24	AMEND QTY OF ITEMS 84H & 84J ABOVE														
CO25	AMEND QTY OF ITEMS 39 & 43 ABOVE														
CO26	12" WM AT CTY FRM RD--WINFLD WORK	0.00	L.F.	\$90.00	\$0.00	120.00	\$10,800.00	120.00	\$10,800.00	120.00	\$10,800.00	0.00	\$0.00	0.00	\$0.00
CO27	WINFIELD WORK														
	AMEND QTY OF 84S THRU 84W ABOVE														
	ADD ITEMS 84SR THRU 84WR BELOW														
	84SR--12" DIP WATER MAIN	0.00	L.F.	\$87.51	\$0.00	4,060.00	\$355,290.60	3,945.00	\$345,226.95	3,945.00	\$345,226.95	0.00	\$0.00	115.00	\$10,063.65
	84TR--12" GATE VALVE & VAULT	0.00	EA.	\$3,145.00	\$0.00	5.00	\$15,725.00	5.00	\$15,725.00	5.00	\$15,725.00	0.00	\$0.00	0.00	\$0.00
	84UR--FIRE HYD WITH AUX VALVE	0.00	EA.	\$3,200.00	\$0.00	10.00	\$32,000.00	10.00	\$32,000.00	10.00	\$32,000.00	0.00	\$0.00	0.00	\$0.00
	84VR--AUGER FOR INST. OF MAIN	0.00	L.F.	\$300.00	\$0.00	75.00	\$22,500.00	80.00	\$24,000.00	80.00	\$24,000.00	0.00	\$0.00	(5.00)	(\$1,500.00)
	84WR--ASPHALT PAVT. REM & REPLACE	0.00	SY	\$34.00	\$0.00	156.00	\$5,304.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	156.00	\$5,304.00
CO28	BLOCK WALL & ALTERATIONS IN WINFIELD	0.00	EA.	\$7,335.00	\$0.00	1.00	\$7,335.00	1.00	\$7,335.00	1.00	\$7,335.00	0.00	\$0.00	0.00	\$0.00
CO29	24" DIP SEWER REPLACEMENT	0.00	L.F.	\$100.00	\$0.00	130.00	\$13,000.00	130.00	\$13,000.00	130.00	\$13,000.00	0.00	\$0.00	0.00	\$0.00
CO30	AMEND QTY OF ITEMS 42 & 35 ABOVE														
CO31	AMEND QTY OF ITEMS #84O THRU 84R-- WINFIELD WORK														
CO32	TIME EXTENSION-- 169 CALANDER DAYS														
CO33	REPAIR EXIST. PAVEMENT IN DWC YARD	0.00	L.S.	\$1,373.00	\$0.00	1.00	\$1,373.00	1.00	\$1,373.00	1.00	\$1,373.00	0.00	\$0.00	0.00	\$0.00
CO34	ADD. COST--MODIFICATIONS TO ROV3	0.00	L.S.	\$7,396.13	\$0.00	1.00	\$7,396.13	1.00	\$7,396.13	1.00	\$7,396.13	0.00	\$0.00	0.00	\$0.00
CO35	ADD. COST--TR. CONT. REVISION#2-DUDOT	0.00	L.S.	\$22,438.50	\$0.00	1.00	\$22,438.50	1.00	\$22,438.50	0.99	\$22,214.12	0.01	\$224.38	0.00	\$0.00
CO36	ADD. COST--SHEET PILING MOB/DEMOB AND BACKFILL AT WAYNE TWP. BRIDGE	0.00	L.S.	\$32,981.11	\$0.00	1.00	\$32,981.11	1.00	\$32,981.11	1.00	\$32,981.11	0.00	\$0.00	0.00	\$0.00
CO37	REPAIR EXIST. 72" WEST RES. INF. VALVE	0.00	L.S.	\$2,638.08	\$0.00	1.00	\$2,638.08	1.00	\$2,638.08	1.00	\$2,638.08	0.00	\$0.00	0.00	\$0.00
CO38	WATERPROOF SIX EXIST. MH @ DWC YARD	0.00	L.S.	\$22,780.00	\$0.00	1.00	\$22,780.00	1.00	\$22,780.00	1.00	\$22,780.00	0.00	\$0.00	0.00	\$0.00
CO39	ADD.COST--OVERTIME WORK, WINFIELD	0.00	L.S.	\$40,960.45	\$0.00	1.00	\$40,960.45	1.00	\$40,960.45	1.00	\$40,960.45	0.00	\$0.00	0.00	\$0.00
CO40	ADD. COST-- ELECT. DUCT BANK, ROV 4&5	0.00	L.S.	\$13,429.96	\$0.00	1.00	\$13,429.96	1.00	\$13,429.96	1.00	\$13,429.96	0.00	\$0.00	0.00	\$0.00
CO41	EXTRA WORK AT ROV2 (11/22/2002)	0.00	L.S.	\$1,373.04	\$0.00	1.00	\$1,373.04	1.00	\$1,373.04	1.00	\$1,373.04	0.00	\$0.00	0.00	\$0.00
CO42	CREDIT FOR ROV & VAULT LESS EXPENSES	0.00	L.S.	(\$109,878.08)	\$0.00	1.00	(\$109,878.08)	1.00	(\$109,878.08)	1.00	(\$109,878.08)	0.00	\$0.00	0.00	\$0.00

DU PAGE WATER COMMISSION

INSTALLATION OF CATHODIC PROTECTION STATION - WESTMONT (QR6-005A)

ACCT. # WF-6631

ROSSI CONTRACTORS

201 WEST LAKE STREET

NORTHLAKE, IL 60164

	FRI 03/19/04	WED 03/24/04	TUE 03/30/04	WED 05/19/04	HOURS UNITS	RATE	EXTENTION	FEE	AMOUNT
LABOR									
LABOR FOREMAN - (J. GUMBER)	4.00	8.00		6.00	18.00	37.89	682.02		
LABOR FOREMAN - OT (C. FIELD)		0.50			0.50	52.89	26.45		
OPERATOR CLASS 1 - (P. RYAN)	4.00	8.00			12.00	46.63	559.56		
OPERATOR CLASS 1 - OT (P. RYAN)		0.50			0.50	63.58	31.79		
BOTTOM LABOR - (ISAC ZEPEDA)	4.00	8.00		6.00	18.00	37.24	670.32		
BOTTOM LABOR - (IGNACIO ZEPEDA)	4.00	8.00			12.00	37.24	446.88		
TOP LABOR - (M. BIRARDI)	4.00	8.00			12.00	36.89	442.68		
TOP LABOR - OT (M. BIRARDI)		0.50			0.50	51.39	25.70		
TRUCK DRIVER - (R. BADER)	4.00	4.00	4.00		12.00	34.75	417.00		
TRUCK DRIVER - (C. MORAVEC)	4.00				4.00	34.75	139.00		
							<u>3,441.40</u>	40.00%	4,817.96
SUPPLIES									
DICICCO CONCRETE PRODUCTS INC. INV. # 2195	720.00						<u>720.00</u>		
							<u>720.00</u>	10.00%	792.00
EQUIPMENT									
320CL BACKHOE	4.00	8.00			12.00	67.65	811.80		
B-600 VAN	4.00	8.00			12.00	16.58	198.96		
SERVICE PICKUP 3/4 T	4.00	8.00		6.00	18.00	11.69	210.42		
SEMI TRACTOR 6X4 GVW 75,000	8.00	8.00	4.00		20.00	44.53	890.60		
LOWBOY TRAILER - 50T	4.00		4.00		8.00	15.03	120.24		
DROP DECK TRAILER	4.00	8.00			12.00	11.11	133.32		
TRENCH BOX		1.00			1.00	84.00	84.00		
							<u>2,449.34</u>	10.00%	2,694.27
									<u>8,304.23</u>

CONTINUED

BY: EJK DATE: 7-28-04
 PROJECT: WF-6631 AMT: 8,304.23
 APPROVED: ORP AMT:
 PREPARED:

DU PAGE WATER COMMISSION

WATER MAIN REPAIR - 897 N. PRESIDENT ST. CAROL STREAM (QR6-007A)

ACCT. # WF-6631

ROSSI CONTRACTORS

201 WEST LAKE STREET

NORTHLAKE, IL 60164

	FRI 01/23/04	SAT 01/24/04	MON 01/26/04	TUES 01/27/04	WED 01/28/04	THU 01/29/04	FRI 01/30/04	WED 02/04/04	HOURS UNITS	RATE	EXTENTION	FEE	AMOUNT
LABOR													
LABOR FOREMAN - (C. FIELD)	8.00		8.00	8.00	8.00	8.00	8.00	8.00	56.00	37.89	2,121.84		
LABOR FOREMAN - OT (C. FIELD)	3.50	9.00	2.00	1.50	4.00	3.00	2.00	1.00	26.00	52.89	1,375.14		
OPERATOR CLASS 1 - (P. RYAN)	8.00								8.00	46.63	373.04		
OPERATOR CLASS 1 - OT (P. RYAN)	3.00	9.00							12.00	63.58	762.96		
OPERATOR CLASS 1 - (N. SENESE)			8.00	8.00	8.00	8.00	8.00		40.00	46.63	1,865.20		
OPERATOR CLASS 1 - OT (N. SENESE)			0.50	0.50	3.50	2.50	0.50		7.50	63.58	476.85		
BOTTOM LABOR - (J. MARTINEZ)	8.00			8.00	8.00	8.00	8.00		40.00	37.24	1,489.60		
BOTTOM LABOR - OT (J. MARTINEZ)	3.00	8.00				1.50			12.50	51.92	649.00		
BOTTOM LABOR - (R. FUENTES)	8.00		8.00	8.00	8.00	8.00	8.00	8.00	56.00	37.24	2,085.44		
BOTTOM LABOR - OT (R. FUENTES)	3.00	8.00				1.50			12.50	51.92	649.00		
BOTTOM LABOR - (J. CAMPBELL)			8.00	8.00		8.00	8.00	8.00	40.00	37.24	1,489.60		
BOTTOM LABOR - OT (J. MARTINEZ)						1.50	1.50		3.00	51.92	155.76		
BOTTOM LABOR - (R. SERNA)				8.00					8.00	37.24	297.92		
BOTTOM LABOR - OT (R. SERNA)									0.00	51.92	0.00		
BOTTOM LABOR - (IGNACIO ZEPEDA)				8.00		8.00			16.00	37.24	595.84		
BOTTOM LABOR - OT (IGNACIO ZEPEDA)						1.50			1.50	51.92	77.88		
TOP LABOR - (ISAC ZEPEDA)	8.00		8.00						16.00	36.89	590.24		
TOP LABOR - OT (ISAC ZEPEDA)	3.00	8.00							11.00	51.39	565.29		
TOP LABOR - (M. ZUNIGA)	5.00					8.00	8.00		21.00	36.89	774.69		
TOP LABOR - OT (M. ZUNIGA)		8.00							8.00	51.39	411.12		
TOP LABOR - (M. BIRARDI)				8.00					8.00	36.89	295.12		
TOP LABOR - OT (M. BIRARDI)				0.50					0.50	51.39	25.70		
TOP LABOR - (M. SERRANO)					8.00	8.00		8.00	24.00	36.89	885.36		
TOP LABOR - OT (M. SERRANO)					0.50	2.50		0.50	3.50	51.39	179.87		
TRUCK DRIVER - (R. BADER)	8.00						8.00		16.00	34.75	556.00		
TRUCK DRIVER - OT (R. BADER)	3.50	8.00					0.50		12.00	48.43	581.16		
TRUCK DRIVER - (C. MORAVEC)	8.00		8.00	8.00	8.00	8.00	8.00	8.00	56.00	34.75	1,946.00		
TRUCK DRIVER - OT (C. MORAVEC)	2.50	9.50	2.00		3.00	1.50	2.00	0.50	21.00	48.43	1,017.03		
TRUCK DRIVER - (N. JOHNSON)	8.00							8.00	16.00	34.75	556.00		
TRUCK DRIVER - OT (N. JOHNSON)	1.50							0.50	2.00	48.43	96.86		
TRUCK DRIVER - (S. LAUDANDO)	5.00								5.00	34.75	173.75		
TRUCK DRIVER - (J. O'SHEA)								8.00	8.00	34.75	278.00		
TRUCK DRIVER - OT (J. O'SHEA)		8.50							8.50	48.43	411.66		
ADVANCED WELDING INV. # 4569	4,573.00										4,573.00		
											28,381.92	40.00%	39,734.69
SUPPLIES													
R & R MATERIALS INV. # 40855	658.05	789.00		100.00	264.08	202.68	1,407.88	599.48			4,021.17		
LEE JENSEN SALES CO INC INV. # 45479	500.00										500.00		
TAPECOAT INV. # 231203						397.50					397.50		
VILLA PARK ELECTRICAL SUPPLY CO., INC. INV. # 1541992						223.80					223.80		
THE GLENROCK CO. INV. # 1/219160						110.15					110.15		
HOME DEPOT INV. # 3010663						250.26					250.26		
HOME DEPOT INV. # 3010666						24.90					24.90		
PRAIRIE MATERIAL SALES, INC. INV. # 91776407							1,087.58				1,087.58		
											6,615.36	10.00%	7,276.90
EQUIPMENT													
320CL BACKHOE	8.00	8.00	8.00	8.00	8.00	8.00	8.00	8.50	64.50	67.65	4,363.43		
B-600 VAN	11.50	9.00	10.00	8.50	12.00	11.00	10.00	8.50	80.50	16.58	1,334.69		
SERVICE PICKUP 3/4 T	8.00	8.00	8.00	8.00	8.00	8.00	8.00	8.00	64.00	11.69	748.16		
SALT TRUCK	8.00								8.00	25.87	206.96		
SEMI TRACTOR 6X4 GVW 75,000	35.50	24.00	8.50	8.50	11.00	10.50	19.50	33.00	150.50	44.53	6,701.77		
TRAILER DUMP	27.50	24.00	8.50	8.50	11.00	10.50	19.50	17.00	126.50	16.02	2,026.53		
LOWBOY TRAILER - 50T	8.00								8.00	15.03	120.24		
GENERATOR - 5500 WATT	8.00	8.00	8.00	8.00	8.00	16.00	16.00		72.00	3.66	263.52		

DU PAGE WATER COMMISSION

WATER MAIN REPAIR - 897 N. PRESIDENT ST. CAROL STREAM (QR6-007A)

ACCT # WF-6631

ROSSI CONTRACTORS

201 WEST LAKE STREET

NORTHLAKE, IL 60164

	FRI 01/23/04	SAT 01/24/04	MON 01/26/04	TUES 01/27/04	WED 01/28/04	THU 01/29/04	FRI 01/30/04	WED 02/04/04	HOURS UNITS	RATE	EXTENTION	FEE	AMOUNT
3" ELECTRICAL PUMP	8.00	8.00	8.00	8.00	8.00	8.00	8.00		56.00	2.91	162.96		
3" HOSES	16.00	16.00	16.00	16.00	16.00	16.00	16.00		112.00	0.14	15.68		
4" TRASH PUMP	8.00	8.00	8.00	8.00	8.00	8.00	8.00		56.00	18.23	1,020.88		
4" HOSES	16.00	16.00	16.00	16.00	16.00	16.00	16.00		112.00	0.21	23.52		
TYPE II BARRICADES	24.00	24.00	24.00	24.00	24.00	24.00	24.00		168.00	2.50	420.00		
TRAFFIC PLATES - 8' X 10'	1.00	1.00	1.00	1.00	1.00	1.00	1.00		7.00	18.00	126.00		
TRAFFIC PLATES - 4' X 16'	2.00	2.00	2.00	2.00	2.00	2.00	2.00		14.00	27.00	378.00		
TRAFFIC PLATES - 4' X 8'	2.00	2.00	2.00	2.00	2.00	2.00	2.00		14.00	13.00	182.00		
COMPRESSOR - 185CFM		8.00	8.00	16.00	8.00	8.00			48.00	9.89	474.72		
CONCRETE BLANKETS		4.00	4.00	4.00	4.00	4.00	4.00		24.00	3.60	86.40		
JERSEY WALLS		4.00	4.00	4.00	4.00	4.00	4.00		24.00	10.00	240.00		
JACKHAMMER - 90#		16.00	16.00	16.00	16.00	16.00	16.00		96.00	0.92	88.32		
JACKHAMMER - 30#				8.00	8.00	8.00	8.00		32.00	0.81	25.92		
CHIPPING GUN				1.00	1.00	1.00	1.00		4.00	5.00	20.00		
DUMP TRUCK - 1 TON				8.50					8.50	20.07	170.60		
TORCH - 20#					1.00	1.00	1.00		3.00	5.00	15.00		
GRINDER - ELECTRIC					16.00	16.00	16.00		48.00	0.49	23.52		
CONCRETE VIBRATOR - 2"							8.00		8.00	2.84	22.72		
DROP DECK TRAILER								16.00	16.00	11.11	177.76		
FUEL TRUCK								8.00	8.00	25.87	206.96		
											<u>19,646.26</u>	10.00%	<u>21,610.89</u>
													<u>68,622.48</u>

BY: EJK CHFI RLR 01/31/04
8-5-04
ACCT #: WF-6631
68,622.48
ACCT #:
APPROVED: CRP

DU PAGE WATER COMMISSION

WATER MAIN REPAIR - 897 N. PRESIDENT ST. CAROL STREAM (QR6-007B)

ACCT. # WF-6631

ROSSI CONTRACTORS

201 WEST LAKE STREET

NORTHLAKE, IL 60164

	THU 04/15/04	FRI 04/16/04	HOURS UNITS	RATE	EXTENTION	FEE	AMOUNT
LABOR							
LABOR FOREMAN - (C. FIELD)	4.00	8.00	12.00	37.89	454.68		
LABOR FOREMAN - OT (C. FIELD)		0.50	0.50	52.89	26.45		
OPERATOR CLASS 1 - (N. SENESE)	8.00	8.00	16.00	46.63	746.08		
OPERATOR CLASS 1 - OT (N. SENESE)		0.50	0.50	63.58	31.79		
BOTTOM LABOR - (R. FUENTES)	4.00	8.00	12.00	37.24	446.88		
TOP LABOR - (H. GUTIERREZ)	4.00	8.00	12.00	36.89	442.68		
TOP LABOR - OT (H. GUTIERREZ)		0.50	0.50	51.39	25.70		
TRUCK DRIVER - (C. MORAVEC)	4.00	8.00	12.00	34.75	417.00		
TRUCK DRIVER - OT (C. MORAVEC)		4.00	4.00	48.43	193.72		
					<u>2,784.98</u>	40.00%	3,898.97
SUPPLIES							
R & R MATERIALS INV. # 41110	249.60	100.00			349.60		
PRAIRIE MATERIAL SALES, INC. INV. # 91857402		217.88			217.88		
					<u>567.48</u>	10.00%	624.23
EQUIPMENT							
446B BACKHOE	8.00	8.00	16.00	44.01	704.16		
B-600 VAN	4.00	8.00	12.00	16.58	198.96		
SERVICE PICKUP 3/4 T	4.00	8.00	12.00	11.69	140.28		
SEMI TRACTOR 6X4 GVW 75,000	4.00	12.00	16.00	44.53	712.48		
TRAILER DUMP		8.00	8.00	16.02	128.16		
LOWBOY TRAILER - 50T	4.00	4.00	8.00	15.03	120.24		
					<u>2,004.28</u>	10.00%	2,204.71
							<u>6,727.91</u>

CONFIRMED

BY: ELK CLP 8/5/04 8-5-04ACCT #: WF-6631 AMT: 6,727.91ACCT #: AMT: APPROVED ELK CLP

CP STATION INSTALLATION - PLAINFIELD RD. @ CREST AVE., DARIEN, IL (QR6-008A)

ACCT. # WF-6631

ROSSI CONTRACTORS

201 WEST LAKE STREET

NORTHLAKE, IL 60164

	THU 03/11/04	FRI 03/12/04	MON 03/15/04	TUES 03/16/04	WED 03/17/04	THU 03/18/04	FRI 05/28/04	HOURS UNITS	RATE	EXTENTION	FEE	AMOUNT
LABOR												
LABOR FOREMAN - (N. D'ANDREA)	8.00	8.00						16.00	37.89	606.24		
LABOR FOREMAN - OT (N. D'ANDREA)	0.50	0.50						1.00	52.89	52.89		
LABOR FOREMAN - (J. GUMBER)			2.00					2.00	37.89	75.78		
LABOR FOREMAN - (J. HANSEN)							4.50	4.50	37.89	170.51		
OPERATOR CLASS 1 - (P. RYAN)	1.00	8.00	2.00					11.00	46.63	512.93		
OPERATOR CLASS 1 - OT (P. RYAN)		0.50						0.50	63.58	31.79		
OPERATOR CLASS 1 - (N. SENESE)			2.00	4.00	8.00	4.00		18.00	46.63	839.34		
BOTTOM LABOR - (J. CAMPBELL)	8.00			4.00				12.00	37.24	446.88		
BOTTOM LABOR - (R. TAVARES)	8.00	8.00	1.00					17.00	37.24	633.08		
BOTTOM LABOR - (C. FIELD)	2.00	2.00	2.00	4.00	8.00	3.00		21.00	37.24	782.04		
BOTTOM LABOR - (ISAC ZEPEDA)		8.00	1.00					9.00	37.24	335.16		
BOTTOM LABOR - (R. FUENTES)			2.00	4.00	8.00	3.00		17.00	37.24	633.08		
BOTTOM LABOR - (IGNACIO ZEPEDA)			2.00	4.00	8.00			14.00	37.24	521.36		
TOP LABOR - (M. BIRARDI)	8.00	8.00	2.00				4.50	22.50	36.89	830.03		
TOP LABOR - OT (M. BIRARDI)	0.50	0.50						1.00	51.39	51.39		
TOP LABOR - (H. GUTIERREZ)	2.00		2.00	4.00		3.00		11.00	36.89	405.79		
TOP LABOR - (J. MARTINEZ)							4.50	4.50	36.89	166.01		
TOP LABOR - (J. SERNA)							4.50	4.50	36.89	166.01		
TRUCK DRIVER - (C. MORAVEC)	6.50		5.50		8.00	4.00		24.00	34.75	834.00		
TRUCK DRIVER - (J. SCHMIDT)	5.00		8.00				4.50	17.50	34.75	608.13		
TRUCK DRIVER - (T. GRASSER)	3.00	8.00						11.00	34.75	382.25		
TRUCK DRIVER - (J. O'SHEA)			3.50			4.00		7.50	34.75	260.63		
TRUCK DRIVER - (P. JOHNSON)				4.00			4.50	8.50	34.75	295.38		
TRUCK DRIVER - (S. LAUDANDO)				1.00				1.00	34.75	34.75		
										9,675.45	40.00%	13,545.63
SUPPLIES												
NAFISCO, INC. INV. # 63135	602.50									602.50		
R & R MATERIALS INV. # 4115					308.80	70.00	50.00			428.80		
PRAIRIE MATERIAL SALES, INC. INV. # 91864397					707.50					707.50		
PRAIRIE MATERIAL SALES, INC. INV. # 91864398						210.00				210.00		
ALLIED ASPHALT PAVING COMPANY INV. # 89577							149.80			149.80		
										2,098.60	10.00%	2,308.46
EQUIPMENT												
320CL BACKHOE	8.00	8.00	8.00	8.00	8.00	8.00		48.00	67.65	3,247.20		
B-600 VAN	8.00	8.00	8.00	8.00	8.00	4.00		44.00	16.58	729.52		
SERVICE PICKUP 3/4 T	16.00	16.00	8.00					40.00	11.69	467.60		
SEMI TRACTOR 6X4 GVW 75,000	16.00	8.00	9.00	8.00	8.00	12.00		61.00	44.53	2,716.33		
TRAILER DUMP	8.00	8.00		8.00	8.00	4.00		36.00	16.02	576.72		
LOWBOY TRAILER - 50T	4.00		4.00			4.00		12.00	15.03	180.36		
TRAFFIC PLATES - 8' X 16'		2.00	2.00	2.00				6.00	27.00	162.00		
COMPRESSOR - 185CFM							8.00	8.00	9.89	79.12		
DUMP TRUCK - 5 TON							10.00	10.00	21.51	215.10		
BOOM TRUCK							5.00	5.00	21.02	105.10		
CRANE FOR BOOM TRUCK							5.00	5.00	9.71	48.55		
JACKHAMMER - 90#							8.00	8.00	0.92	7.36		
DOUBLE DRUM ROLLER							8.00	8.00	8.58	68.64		
COMPACTOR - VIBRATORY PLATE				8.00	8.00			16.00	8.58	137.28		
CONCRETE VIBRATOR - 2"					8.00			8.00	2.84	22.72		
DROP DECK TRAILER	4.00		5.00			4.00		13.00	11.11	144.43		
CONCRETE SAW	2.00	2.00	4.00					20.00	5.70	114.00		
TRENCH BOX	1.00		1.00	1.00				4.00	84.00	336.00		
										9,358.03	10.00%	10,293.83
												26,147.92

EHK CRP
 DATE: 2-5-04
 WF 6631 AMT: 26,147.92
 AMT:
 APPROVED

CP REPAIR - 75TH STREET @ NAPER BLVD., NAPERVILLE (QR6-008B)

ACCT. # WF-6631

ROSSI CONTRACTORS

201 WEST LAKE STREET

NORTHLAKE, IL 60164

	WED 05/19/04	THU 05/20/04	FRI 05/21/04	TUES 05/25/04	HOURS UNITS	RATE	EXTENTION	FEE	AMOUNT
LABOR									
LABOR FOREMAN - (C. FRANKOVICH)	2.00	2.00	1.50	2.00	7.50	37.89	284.18		
LABOR FOREMAN - (C. FIELD)	5.00	8.00	5.00		18.00	37.89	682.01		
LABOR FOREMAN - OT (C. FIELD)		0.50	0.50		1.00	52.89	52.89		
LABOR FOREMAN - (J. HANSEN)				3.50	3.50	37.89	132.62		
OPERATOR CLASS 1 - (P. RYAN)	4.00	8.00	5.00		17.00	46.63	792.71		
OPERATOR CLASS 1 - OT (P. RYAN)		0.50	0.50		1.00	63.58	63.58		
BOTTOM LABOR - (R. FUENTES)		8.00	5.00		13.00	37.24	484.12		
BOTTOM LABOR - (J. SERNA)				2.50	2.50	37.24	93.10		
TOP LABOR - (M. BIRARDI)				3.50	3.50	36.89	129.12		
TOP LABOR - (H. GUTIERREZ)	5.00	8.00	5.00		18.00	36.89	664.01		
TOP LABOR - OT (H. GUTIERREZ)		0.50	0.50		1.00	51.39	51.39		
TOP LABOR - (J. MARTINEZ)				2.50	2.50	36.89	92.23		
TRUCK DRIVER - (C. MORAVEC)	4.00		4.00		8.00	34.75	278.00		
TRUCK DRIVER - (J. SCHMIDT)		8.00		3.50	11.50	34.75	399.62		
TRUCK DRIVER - OT (J. SCHMIDT)		0.50			0.50	48.43	24.22		
TRUCK DRIVER - (T. GRASSER)		8.00			8.00	34.75	278.00		
TRUCK DRIVER - OT (T. GRASSER)		0.50			0.50	48.43	24.21		
TRUCK DRIVER - (P. JOHNSON)				3.50	3.50	34.75	121.63		
							<u>4,647.64</u>	40.00%	6,506.70
SUPPLIES									
PRAIRIE MATERIAL SALES INC. INV. # 540887	216.00						216.00		
R & R MATERIALS INV. # 41158	51.16						51.16		
ALLIED ASPHALT PAVING CO. INV. # 89326	57.40						<u>57.40</u>		
							<u>324.56</u>	10.00%	357.02
EQUIPMENT									
320CL BACKHOE	8.00	8.00	8.00		24.00	67.65	1,623.60		
B-600 VAN	8.00	8.00	8.00	8.00	32.00	16.58	530.56		
SEMI TRACTOR 6X4 GVW 75,000	8.00	20.00	8.00		36.00	44.53	1,603.08		
TRAILER DUMP		16.00			16.00	16.02	256.32		
LOWBOY TRAILER - 50T	8.00		8.00		16.00	15.03	240.48		
DUMP TRUCK - 5 TON				8.00	8.00	21.51	172.08		
BOOM TRUCK				4.00	4.00	21.02	84.08		
CRANE FOR BOOM TRUCK				4.00	4.00	9.71	38.84		
VIBRATORY PAVEMENT ROLLER				8.00	8.00	8.58	68.64		
DROP DECK TRAILER		4.00			4.00	11.11	44.44		
CONCRETE SAW	8.00				8.00	5.70	45.60		
TRENCH BOX		1.00	1.00		2.00	84.00	168.00		
TYPE I BARRICADES	12.00	12.00	12.00	12.00	48.00	2.50	120.00		
ROAD CONSTRUCTION SIGN	1.00	1.00	1.00	1.00	4.00	1.50	6.00		
GENERATOR - 12000		8.00	8.00		16.00	5.48	87.68		
							<u>5,089.40</u>	10.00%	5,598.34
									<u>12,462.06</u>

BY: ELK

CONFIRMED

DATE: 5/25/04ACCT #: WF-6631 AMT: 12,462.06ACCT #: CP AMT: APPROVED CP

DU PAGE WATER COMMISSION

8" BLOW OFF VALVE REPAIR - NAPERVILLE (QR6-009A)

ACCT. # WF-6631

ROSSI CONTRACTORS

201 WEST LAKE STREET

NORTHLAKE, IL 60164

	WED 04/21/04	THU 04/22/04	HOURS UNITS	RATE	EXTENTION	FEE	AMOUNT
LABOR							
LABOR FOREMAN - (J. HANSEN)	8.00	8.00	16.00	37.89	606.24		
LABOR FOREMAN - OT (J. HANSEN)	0.50	0.50	1.00	52.89	52.89		
OPERATOR CLASS 1 - (D. POHL)	8.00	8.00	16.00	46.63	746.08		
OPERATOR CLASS 1 - OT (D. POHL)	0.50	0.50	1.00	63.58	63.58		
BOTTOM LABOR - (J. CAMPBELL)	8.00	8.00	16.00	37.24	595.84		
BOTTOM LABOR - (J. SERNA)	8.00	8.00	16.00	37.24	595.84		
TOP LABOR - (P. LAUDANDO)	8.00	8.00	16.00	36.89	590.24		
TOP LABOR - OT (P. LAUDANDO)	0.50	0.50	1.00	51.39	51.39		
TRUCK DRIVER - (C. MORAVEC)		4.00	4.00	34.75	139.00		
TRUCK DRIVER - (J. SCHMIDT)	8.00	8.00	16.00	34.75	556.00		
TRUCK DRIVER - OT (J. SCHMIDT)	0.50	0.50	1.00	48.43	48.43		
TRUCK DRIVER - (J. O'SHEA)	4.00		4.00	34.75	139.00		
					<u>4,184.53</u>	40.00%	5,858.34
SUPPLIES							
R & R MATERIALS INV. # 41159	229.00				<u>229.00</u>		
					<u>229.00</u>	10.00%	251.90
EQUIPMENT							
446B BACKHOE	8.00	8.00	16.00	44.01	704.16		
B-600 VAN	8.00	8.00	16.00	16.58	265.28		
SERVICE PICKUP 3/4 T	8.00	8.00	16.00	11.69	187.04		
SEMI TRACTOR 6X4 GVW 75,000	13.00	13.00	26.00	44.53	1,157.78		
LOWBOY TRAILER - 50T	5.00	5.00	10.00	15.03	150.30		
COMPACTOR - VIBRATORY PLATE	8.00	8.00	16.00	8.58	137.28		
DROP DECK TRAILER	8.00	8.00	16.00	11.11	177.76		
					<u>2,779.60</u>	10.00%	3,057.56
							<u>9,167.80</u>

BY: ex CRP 8/15/04ACCT: WF 6631 AMT: 9,167.80AMT: 9,167.80AMT: 9,167.80

CHANGE ORDER

DUPAGE WATER COMMISSION

SHEET 1 OF 3

PROJECT NAME: Blow-Off Valve Improvements

CHANGE ORDER NO. 14

LOCATION: DuPage County

CONTRACT NO. BOV-1/02

CONTRACTOR: Rossi Contractors, Inc.

DATE: August 4, 2004

I. A. **DESCRIPTION OF CHANGES INVOLVED:**

Retirement of Valve #36, by welding steel plate inside of the 54" diameter main, covering the 12" outlet. Remove and salvage existing valve frame(s) and lid(s) for delivery to the Commission. Remove and dispose of all other remaining valve connections and piping from grade to 2 feet below grade and restore surface.

B. **REASON FOR CHANGE:**

The depth of this valve was incorrectly identified as 25 feet rather than 43 feet. The cost and difficulty associated with gaining access to a valve this deep for future maintenance and repair is great, and the need to keep this valve operational is minimal.

C. **REVISION IN CONTRACT PRICE:**

1. Add Retirement of Valve #36	\$37,600.00
2. Delete Unit Price Item No. 36 (Step 1 for Valve #36)	<u>(\$51,700.00)</u>
Total	(\$14,100.00)

II. CHANGE ORDER CONDITIONS:

1. The Completion Date established in the Original Contract or as modified by previous Change Orders is hereby extended by 0 calendar days, making the final completion date April 27, 2005.
2. Any additional work to be performed under this Change Order shall be carried out in compliance with the specifications included in the preceding Description of Changes Involved, with the Supplemental Contract Drawings designated as Blow Off Valve Improvements, and under the provisions of the Original Contract, including compliance with applicable Equipment Specifications, General Specifications, and Project Specifications for the same type of work.
3. This Change Order unless otherwise provided herein does not relieve the contractor from strict compliance with the guarantee provisions of the Original Contract, particularly those pertaining to performance and operation of equipment.
4. The Contractor expressly agrees he will place under coverage of his Performance and Payment Bonds and Contractor's Insurance all work covered by this Change Order. The Contractor will furnish to the Owner evidence of increased coverage of his Performance and Payment Bonds for the accrued value of all Change Orders which exceeds the Original Contract Price by twenty percent (20%).

III. ADJUSTMENTS IN CONTRACT PRICE:

1.	Original Contract Price	\$ <u>7,812,435.00</u>
2.	Net change due to all previous Change Orders Nos. 1 through 12*	\$ <u>(66,735.00)</u>
3.	Contract Price, not including this Change Order	\$ <u>7,745,700.00</u>
4.	Reduction to Contract Price due to this Change Order	\$ <u>(14,100.00)</u>
5.	Contract Price including this Change Order	\$ <u>7,731,600.00</u>

RECOMMENDED FOR ACCEPTANCE:

PROJECT COORDINATOR: _____ ()
Date

ACCEPTED:

CONTRACTOR: Rossi Contractors, Inc.

By: _____ ()
Signature of Authorized Representative Date

DUPAGE WATER COMMISSION:

By: _____ ()
Robert L. Martin Date
General Manager

* Change Order No. 13 pending.